

ILC Marx Modulator R&D Status

ILC GDE Meeting

IHEP, Beijing, PRC February 6, 2007

Ray Larsen


Stanford Linear Accelerator Center

Outline

- I. Baseline Design
- II. Alternate Design: Marx
- III. Progress Report: G. Leyh
- IV. Preliminary Schedule
- V. Summary
- VI Acknowledgment

I. Baseline Design

- 3 large packages: 150 kW Charger, Capacitor-Switch-Bank-Bouncer Modulator and Pulse Transformer



A



B



C




D

A. Capacitor Stack, B. Dual IGBT Switch, C. Bouncer Filter Chokes, D. Pulse Transformer

-Bouncer smooths pulse top to +/- 0.5%

-8-10 units built by FNAL/DESY

ILC Baseline: 38m 10 MW Linac RF Station



Outline

- I. Baseline Design
- **II. Alternate Design: Marx**
- III. Progress Report: G. Leyh
- IV. Preliminary Schedule
- V. Summary
- VI Acknowledgment

II. Marx Modulator


- Being investigated as alternate design to present switched cap "Bouncer" design

Goals:

*Reduce size, weight, space by 3-4X
Reduce cost by >2X
Increase efficiency
Demonstrate operation in 2007.*

Specifications:

*120 kV, 140 A, 1.63 ms, 5 Hz
125 kW output power to klystron
Efficiency from wall-plug ~90%*





II. Alternate Design Motivation


- Generate HV by stacked switched cells DC coupled; smooth pulse by digitally controlled elements (Vernier); air cooled
- Eliminate oil-filled multi-ton Pulse Transformer
- Reduce total foot print by ~3X, Cost by ~2X
- Modular design with N+1 Cell redundancy for higher Availability, shorter Mean Time to Repair (MTTR)
- N+1 Redundancy at 12 kV cell level, charge and discharge switch level, capacitor level
- Cells air-cooled inside water-cooled enclosure; easier maintenance handling, replacement, off-line repair
- Charge directly from 34.5:8 kV distribution transformer; simple buck regulator cell; eliminate oil-filled charger transformer

[Note: Charger topology may be redesigned further to solve power factor / phase load balancing issues.]

II. Marx Conceptual Circuit Design




II. Marx Assembly Overview



DETAIL, MARX MODULATOR CORE


II. 12 kV Cell Detail

4+1 Redundant Switch Arrays
for charge, discharge



12kV MARX CELL, FRONT VIEW

6+2 Redundant
Capacitors



12kV MARX CELL, REAR VIEW

III. ILC Marx Modulator Progress Report

G.E. Leyh, SLAC 29 January 2007



ILC MARX DEVELOPMENT PROGRESS												
	Jul 06	Aug 06	Sep 06	Oct 06	Nov 06	Dec 06	Jan 07	Feb 07				
Marx Output, Kilovolts			12 12 24	24 24 24 24	24 24 40 48	60 60 60 60	65 65 80 80					
Complete Modulator Frame	• • •											
Build Marx Test Chamber	• • •	• •										
Install Emanating Cable Plant		• • • •										
High Power Chargers, Test Load Ready						◆						
Electrical Safety Review, 2-Cell Operation		◆										
Install Required Safety Equipment		• • •										
First 2-Cell Testing, Debug			• • •									
First 4-Cell Test (4x6kV)				•								
Electrical Safety Review, 4-Cell Operation				◆								
Fab, Install Additional Safety Equipment				• • • •	• •							
4-Cell Testing, De-Bug (4x12kV)					• • •							
DCB Self-Reset Fixed						⊙						
6-Cell Testing						• • •						
FWD Recovery Fixed							⊙					
SLAC Shutdown						• •						
8-Cell Testing							• • • •					
OC Blanking Fixed								⊙				
Photodetector Noise Fixed											⊙	
10-Cell Testing												

Performing Measurements




- Single cell on test stand.
- Capacitor safety shunting device, long handle
- Long wait period before handling after shorting.
- Probe suspended, repositioned for point-to-point measurements
- Very slow process – automated test, maintenance fixtures & procedures need to be developed

8-Cell, 80kV Output Waveforms



February 2, 2007


ILC FA Electronics R&D
R. Larsen SLAC



Other Accomplishments

- **Additional Tasks Completed**
 - *Diagnostic Controller system*
 - *150 kW Charger Supply and Resistive Load*
 - *Air-water cooled enclosure*
 - *Second Level Vernier correction box (LLNL)*

Diagnostic Controller Details





Dual Fiber Optic
Timing &
Data Links

Programmable
Logic Array

Duplex Timing &
Data Channels
Each Cell
(Mounted on Rear)

February 2, 2007



16 Ch Ground Station

150 kW Air-Cooled load

Disc Resistor
Stacks (2)

120 kV
Input
Cable

Rear View
Axial Fans



February 2, 2007




ILC HA Electronics R&D
R. Larsen SLAC





Disc Resistor &
Cooling Fin Stacks

Integrated Instrument Rack


Layout - Front View



RACK 'A'	LEVEL	RACK 'B'
AC POWER DIST	19	
INTLK, UTIL SUMMARY	18	TEK 4-CHANNEL OSCILLOSCOPE
	17	
	16	
BUCK REGULATOR CONTROLLER	15	OPTO DIAG 1
	14	
	13	OPTO DIAG 2
	12	
	11	KEYBOARD
	10	
FAST ANALOG REG	9	300VDC CTRL PS
	8	
	7	
GROUND STATION EXT	6	GROUND STATION
	5	
	4	
	3	
	2	
	1	



BLOWER & HEAT EXCHANGER 1		BLOWER & HEAT EXCHANGER 2
---------------------------	--	---------------------------



IV. Preliminary Schedule

ID	Task Name	Duration	Start	Finish	2007												2008		
					Qtr 1, 2007			Qtr 2, 2007			Qtr 3, 2007			Qtr 4, 2007			Qtr 1, 2008		
					Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb
1	DEMONSTRATION INITIAL OPERATION	254 days	Fri 1/12/07	Wed 1/2/08	[Gantt bar spanning from Dec 2007 to Dec 2008]														
2	Full Power Demonstration (Unlevelled)	19 days	Fri 1/12/07	Wed 2/7/07	[Gantt bar from Dec 2007 to Jan 2008]														
11	100 Hour Test	55 days	Fri 1/12/07	Thu 3/29/07	[Gantt bar from Dec 2007 to Feb 2008]														
21	2000 Hour Test (Phase 1 - B15)	200 days	Thu 3/29/07	Wed 1/2/08	[Gantt bar from Mar 2007 to Dec 2008]														
31	CELL COMPLETION	13 days	Fri 1/12/07	Tue 1/30/07	[Gantt bar from Dec 2007 to Jan 2008]														
32	Cells 11-14 Assembly & Test	13 days	Fri 1/12/07	Tue 1/30/07	[Gantt bar from Dec 2007 to Jan 2008]														
41	VERNIER CELL	97 days	Fri 1/12/07	Mon 5/28/07	[Gantt bar from Dec 2007 to Jun 2008]														
54	BUCK REGULATOR CELL	95 days	Mon 4/2/07	Fri 8/10/07	[Gantt bar from Apr 2007 to Aug 2008]														
73	TOOLING	25 days	Fri 1/12/07	Thu 2/15/07	[Gantt bar from Dec 2007 to Jan 2008]														
75	PACKAGED UNIT FOR ESB INSTALLATION	71 days?	Fri 1/12/07	Fri 4/20/07	[Gantt bar from Dec 2007 to Feb 2008]														
76	Package Assembly	71 days?	Fri 1/12/07	Fri 4/20/07	[Gantt bar from Dec 2007 to Feb 2008]														
84	Site Preparation	60 days	Fri 1/12/07	Thu 4/5/07	[Gantt bar from Dec 2007 to Feb 2008]														
89	Safety Reviews & Documentation	25 days	Fri 1/12/07	Thu 2/15/07	[Gantt bar from Dec 2007 to Jan 2008]														
94	Control System Integration	55 days	Fri 1/12/07	Thu 3/29/07	[Gantt bar from Dec 2007 to Feb 2008]														

Note – Preliminary to show remaining tasks, not optimized.

V. Summary

- Original schedule aiming for HV demonstration by end FY06 and Vernier demonstration by end CY06 not met due to:
 - *Initial delays in parts deliveries (IGBTs)*
 - *Design and implementation of safety features*
 - *Safety documents, reviews, authorization to proceed*
 - *Charger design delayed so implemented alternate commercial unit system.*
 - *Noise problem in DCB limited to 40 kV (fixed).*
 - *Protection diode problem failure (fixed).*
- Subsequently made tests up to 60 kV at low power prior to year end and to 80 kV in January 07
 - *Blanking pulse added to CPLD to eliminate noise trips (fixed).*
 - *Additional problem encountered at 80 kV with noise in opto-isolators (being fixed).*
 - *HV measurements painstakingly slow*

Summary-2

- **Next Steps:**
 - *Continue debugging to 120 kV at low power*
 - *Perform short power test (100 hrs) with full charger supply, load*
 - *Modify design to include new capacitor discharge switches, begin 2000 h test.*
 - *In parallel Complete Vernier, Buck Regulator Boards. When ready install, test.*
 - *Complete Full Power 2000 h test on Resistive Load*
 - *In parallel, prepare End Station infrastructure*
 - *Install tested unit in air-water cooled enclosure (parts on hand)*
 - *Move to End Station and install on 10 MW klystron load.*

VI. Acknowledgment

- The key players in development of the Marx are:
 - *Project Engineer, G. Leyh, Power Conversion Dept*
 - *Associates: Piotr Blum and Alfred Vicalal*
 - *Diagnostic Controller design: J. Olsen, Controls Dept*
 - *Vernier Board design: Craig Burkhart*
 - *2nd Level Vernier design: E. Cook, LLNL*
 - *150 kW Air cooled Resistive Load: C. Brooksby LLNL, detailed design and R. Cassel & Co., construction*
 - *150 kW Charger system: A. deLira, design & R. Cassel & Co., design & construction*