

# Large Size Avalanche Mode RPCs for CMS

**Yanlin Ye, Yong Ban, Sijin Qian, Yajun Mao**  
**School of Physics, Peking University**



The Compact Muon Solenoid Experiment

## CMS Bulletin

CERN, CH-1211 GENEVA 23, Switzerland




Bulletins are available on  
CMS internal information server:

<http://cmsdoc.cern.ch/cms.html>


Number 06-01  
13 March 2006

Feb. 2006, RE1/3  
installed on  
CMS

## Moving Forward !



YE+1 yoke equipped with CSC/RPC packages (inner ring) and RE1/3 RPC's (outer ring).



The ME1/3 CSC's now cover the RPC outer ring and hence complete the first Muon station on YE+1.



Beijing, Feb.4-

7,2007



# Outline

---

- I. The Task**
- II. The R&D and prototyping**
- III. production and  
Installation**
- IV. Summary**

# I. The Task


**FW-RPC: A “high priority” problem  
for CMS in 1996.**



The Compact Muon Solenoid Experiment

**CMS Bulletin**

CERN, CH-1211, GENEVA 23, Switzerland



---

Date of publication: 06-09-96

Number 96-01

CMS internal information servers: <http://cmsdoc.cern.ch/cms.html> and <ftp://cmsdoc.cern.ch>


---

**LETTER FROM THE SPOKESPERSON :**



the forward region. The natural  $P_t$  cut-off due to ranging out in the calorimeters is only  $\approx 1$  GeV in the forward region as opposed to  $\approx 3$  GeV in the barrel region. This means that the single rate in the forward region is two to three orders of magnitude higher than in the barrel, dominated by real muons from  $\pi/K$  decays associated to beam-beam collisions. The only way to cut down this rate in the first level trigger is to measure  $P_t$  online and apply a high  $P_t$  cut. To achieve this difficult task Cathode Strip Chambers must be complemented by pad detectors with  $r-\phi$  segmentation such as RPCs. Design, funding and construction of the forward RPCs remains a very high priority for CMS. An important milestone for the muon system is the definition of the RPC parameters in December 96.

# LHC-CMS Detecotr



**PKU Task**



Fig. 1.1: Three-dimensional view of the CMS detector.

# The End-cap RPC System

Responsibility  
of China:

RE1/2 and  
RE1/3

144 chambers



## 1999.4. MoU

¼ of Barrel RPC (RB1) and ¼ of FW RPC (RE1/2-3)

	station	size	total area	# gaps	gap area
RB1	120	5.2m <sup>2</sup>	624 m <sup>2</sup>	480	1248 m <sup>2</sup>
RE1/2-3	144	~2.0 m <sup>2</sup>	280 m <sup>2</sup>	532	560 m <sup>2</sup>

production 120%.

**In-kind Contribution: 700 kCHF**

**M&O contribution: 250 kCHF**



# Achievable MoU deliverables

Ref.	Institutes	Achievable MoU Deliverables: 4,365 kCHF	Assigned
1.2.05	China	Magnet : Endcap Yokes : Carts Weldments (In-kind contribution , cf. 10.8 and Annex 9.1)	1,215
5.1.2	IHEP	Muon Detector : Barrel Drifttubes : Electronics Assembly and test of the high-voltage and de-coupling boards and interconnecting cables for all DT chambers (800 kCHF instead of 350 kCHF)	800
5.1.3	IHEP	Mechanical Supports for MB1 and MB4 (instead of 5.1.1: I-beams for 1,000 kCHF)	350
5.3.1	IHEP	Muon Detector : Endcap CSC : Detectors and Components Prototyping, tooling, assembly, testing and transport to CERN of the ME 1/2, and ME 1/3 chambers. Critical tooling, chamber parts and electronics will be provided to IHEP from US_CMS	1,500
5.4.3	PU	Muon Detector : Barrel RPC : Mechanical Structure and Supports Production of mechanical frames, assembly of the mechanical frames to the bakelite gaps, installation of tested electronics boards and test of the complete MB1 RPC chambers (100 kCHF instead of 350 kCHF)	350
5.5.3	PU	Muon Detector : Forward RPC : Mechanical Structure and Supports Production of mechanical frames, assembly of the mechanical frames to the bakelite gaps, installation of tested electronics boards and test of the complete ME1/2 and ME1/3 RPC chambers	150
<b>Total Achievable Funding</b>			<b>4,365</b>

# Cost to completion: additional deliverables

<b>Ref.</b>	<b>Institutes</b>	<b>Cost to Completion: Additional Deliverables for 700 kCHF</b>	<b>Assigned</b>
<b>9.2.06</b>	<b>IHEP</b>	<b>UX Steel Floor Plates</b>	<b>500</b>
<b>5.5.3</b>	<b>PU</b>	<b>Honeycomb Panels for Forward RPCs: RE1/2 a</b>	<b>200</b>
		<b>Total Additional Funding</b>	<b>700</b>

**M. Della Negra, Beijing, 10 April 2003**



## II. The R&D and Prototyping

### Requirements

Large area (a few m<sup>2</sup>);

Avalanche mode, counting rate > 1 kHz/cm<sup>2</sup>

Resistive plate: resistivity 10<sup>10~11</sup> Ω.cm

Surface Roughness < 0.3 μ m

cluster size < 2 strips (15mm strip)

Efficiency > 95% for a HV range wider than 1000V

Time resolution < 2ns,

Electronic noise < 2 mV;

Radiation stability > 5 years

Assembly thickness < 40 mm.

# 1st Prototype with Chinese Bakelite [NIM A459(2001)513]

Size: 50 X 58 X 2 mm<sup>3</sup>

Bulk material: phenolic resin with  $5 \times 10^{12} \Omega \cdot \text{cm}$  resistivity


Surface: melamine film with an average surface roughness  
of  $0.16 \pm 0.08 \mu \text{m}$

Gas gap: 2 mm  $\pm 10 \mu \text{m}$

Graphite coating: about  $100 \text{ k} \Omega \cdot \text{cm}^2$

Strips: 32 strips, 1.5 cm wide each



$$R_a = \frac{1}{l_s} \int_0^{l_s} |y| dx$$



RPC 流光模式与雪崩模式的比较

性能	流光模式	雪崩模式
输出信号幅度	几百 $mV$ (不需放大)	几 $mV$ (需放大)
探测效率	$\geq 95\%$	$\geq 95\%$
正常工作的计数	$100 \text{ Hz/cm}^2$	$1 \text{ KHz/cm}^2$
时间分辨本领	几 $ns$	几 $ns$
工作电压	较高	较低


# 1999, PKU-RPC-1, test at CERN



30-Jul-99  
10:46:46

1 .1  $\mu$ s  
2.00 mV

2 .1  $\mu$ s  
1.00 V




1 2 mV DC  
2 1 V DC  
3 .5 V 500  
4 .5 V 500

Store to Flpy  
Size 1440K Free 1388K  
Directory LECROY\_1.DIR 2 GS/s  
STOPPED

30-Jul-99  
9:48:58

1 .1  $\mu$ s  
2.00 mV

2 .1  $\mu$ s  
1.00 V








1 2 mV DC  
2 1 V DC  
3 .5 V 500  
4 .5 V 500

2 DC -0.92 V  
H'off 1 evts 2 GS/s  
STOPPED



## muon beam test system GIF at CERN





**For the Chinese made double gape  
avalanche mode RPC:**


**Counting rate  $\sim 400 \text{ s}^{-1}\text{cm}^{-2}$**

**time resolution  $< 2 \text{ ns}$**




**efficiency  $\sim 100 \%$**


- Ying J, Ye YL, Ban Y, et al., *Beam test results of a resistive plate chamber made of Chinese bakelites*, Nucl. Inst. and Meth. A, 459 (3) 513-522, 2001
- Ying J, Ye YL, Ban Y, et al., *Study of an avalanche-mode resistive plate chamber*, J. Phys. G, 26 (8) 1291-1298, 2000

# PKU-RPC2: Full size RE1/2, Italian bakelite a resistivity of $5 \times 10^{10} \Omega \cdot \text{cm}$ . can work at $1\text{kHz}/\text{cm}^2$



HEP&NP,  
2005,29(2):175-170









## **PKU-RPC3: Study of new assembly technique with honeycomb panel**

**Due to the change of the space available, CMS require to reduce the total thickness of the FW-RPC from 40 mm to  $< 30$  mm.**

**The solution with honeycomb panel had been studied and accepted. The thickness of 28 mm was achieved.**

RE 1/2


Present  
= BASELINE (SC)



- Decouple cabling from RE1/2 installation
- Easier maintenance RE1/2
- Faster installation
- Overlap covers all buses



2002.08. The final prototype was tested and approved, and demonstrated by CMS for two months.





# III. Production and Installation



**A new workshop at PKU was established for the production of materials and for the preassembly with the model gas-gaps.**




2007-2-6



ILC Workshop, Beijing, Feb.4-7,2007









# Another workshop was established at CERN for final assembly and testing


实验室内部：各种装配测试台等



十层探测器宇宙线测试数据获取系统



制备、完善了各种模具、升降车、储存架等。



气体室过压20毫巴测试装置、冷却系统过压20大气压测试装置

2007-

shop, l  
7,20

25



# Gas leakage and spacer tests





2007-2-6



ILC Workshop, Beijing, Feb.4-  
7,2007

26

# HV test



2007-2-6

ILC Workshop, Beijing, Feb.4-  
7,2007

27




# Assembly for various components

- ❖ Co-axial signal cable preparation (96 pieces, 192 ferrules) (1 day) → 0.7
- ❖ Honeycomb panel modification (2 panels and 1 Al bar) (0.5 day) → 0.3
- ❖ 40-pin flat cable preparation (6 pieces, 12 connectors) (2 hours) → 1.5
- ❖ Screen box modification (cutting 8 big holes and 1 HV port) (2 h.) → 0.5
- ❖ L-shape gap fixation bracket preparation (1.5 hour) → 1
- ❖ Mylar sheet preparation (2 pieces) (1.5 hour) → 1
- ❖ Gas pipe bending (6 types of shape) (1 hour) → 0.5
- ❖ FEB cooling plate modification and pre-assembly (1 hour) →
- ❖ Read-out strips preparation (testing any short circuit, etc.) (1 h.) → 0.5
- ❖ Soldering PCB strips on copper ground sheet (6 pieces) (1 h.) →
- ❖ Multiple-hole gas gap locator preparation (6 pieces) (1 hour) →

# Co-axial signal cable preparation



Co-ax cable  
Preparation  
stripping  
cables  
machine  
chamb



Co-ax cables with ferrules

then soldered on


co-ax




LCW

7,2007

# Honeycomb panel modification



2007-2-6




o, Beijing  
7,2007

30



# 40-pin flat cable preparation











# ● cosmic test results: efficiency and cluster size



Storage frame



## ● Schedule in 2005



2006年:



安装54个RE1/3到+z CMS端部铁基座上 (Orange arrow)

开始进行整体探测器的运行调试 (Pink arrow)


2007-2-6

ILC Workshop, Beijing, Feb. 4-7, 2007

7,2007



**2005.12.19 18 RE1/2 installed at -z direction**



2007-2-6

7,2007

34

Feb. 2006, RE1/3  
installed on  
CMS



The Compact Muon Solenoid Experiment

## CMS Bulletin

CERN, CH-1211 GENEVA 23, Switzerland




Bulletins are available on  
CMS internal information server:


<http://cmsdoc.cern.ch/cms.html>

Number 06-01  
13 March 2006

## Moving Forward !



YE+1 yoke equipped with CSC/RPC packages  
(inner ring) and RE1/3 RPC's (outer ring).



The ME1/3 CSC's now cover the RPC outer ring and  
hence complete the first Muon station on YE+1.



**PKU-RPC will join the first  
run of LHC-CMS scheduled  
by the end of this year!!**





# Summary

- The large size avalanche mode RPC made of the Chinese bakelite can be used for a counting rate  $< 400 \text{ Hz/cm}^2$
- The assembly with Honeycomb panel is a good solution for the “thin” RPC.
- Experiences with detector R&D, assembly and mass production have been accumulated and are valuable for future development and applications