



CCLRC
Technology

4m Undulator Design Concepts

Amanda J Brummitt

CCLRC RAL

On behalf of the HeLiCal Collaboration

On axis field	0.9 T
Peak to peak variation	<1%
Pitch	11.5 mm
Nominal Current	<300 A
Nom current as % of Short Sample	80%
S/C wire	Nb Tn 0.4mm dia. SC:Cu ratio 0.9:1
Winding Cross Section	7 wires wide x 8 high
Number of magnets per module	2 (powered separately)
Length of magnetic field	2 x 1.74 m

Pole	Iron (BS080A15) with a square section groove
Beam/winding tube	Copper (6.35od x 0.56wall) with a non polished bore.
Beam Stay Clear	4mm Diameter
Central Beam pipe connection	Plain butt joint
Beam pipe connection at ends	Tapered 1:10 out to 10mm dia

No Beam Collimators or Beam Pipe Vacuum pumping ports in the beam pipe

4m Module Overview

Stainless steel vacuum vessel
with Central turret

50K Al Alloy Thermal shield.
Supported from He bath


U beam
Support rod

Stainless Steel He
bath contains 100L
liq He. Supported
by 4 rods attached
to the vacuum
vessel


U Beam used to
support/align the
magnet.


Beam Tube

Magnet cooled
to 4.5K by liq
He in bath.





- Mild steel former 1.8 m long machined with 2 start helical groove.
- Beam pipe (Cu tube) soldered into bore of the former
- Superconducting ribbon wound on to the copper tube








The two magnet assemblies are joined via an Indium seal. This is held together using a 3-way clamp which is assembled before the magnets are installed into the U-beam. To prevent movement of the joint, the 4m magnet assembly is bolted to a handling beam which also ensures correct orientation of the two magnets.



The completed magnet is supported and aligned within a stiff U beam



Once installed into the U-beam the magnet itself can be aligned using the U-beam adjusters. An alignment telescope will be used to look down the bore of the magnet and ensure that it remains coaxial between the two ends within the tolerances set out in the specification.



Cryostat Cross Section


Services turret contains cryogenic cooler, 4 HTC current leads, He / N₂ pipes and Instrumentation

Vacuum vessel

50K Thermal Shield cooled by conduction from cryogenic cooler 1st stage

He bath. Precooled to 77K via N₂ cooling pipes on OD. Filled with 100L liq He from dewar. Liq He level topped up during operation from He condensing pot in turret. No external cryogenics required during operation.


Cold bore (Beam tube)



50K
Thermal
shield

36mm dia
He vent
pipe

4 off HTC
current
leads.
Cooled to
50K from
cooler 1st
stage




Cryogenic
Cooler

Liq He
Condensing
pot. Cooled to
4.5K from
cooler second
stage

He bath Top
plate

Instrumentation
Lead thro'



Two support System required –

1. U Beam within He bath (Shown)
2. He Bath within vacuum vessel

Conceptually the two systems are identical –


Adjustable in X and Y to allow the beam pipe to be centred within the vacuum vessel. Fixed at the magnet mid position to allow for thermal contractions of ~6mm at each end.


He bath supports shown. U beam supports similar but without thermal intercept.

Support rod material will be determined by heat leak and thermal contraction.

Carbon fibre Thermal contraction <0.1mm

Stain Steel Thermal contraction ~0.6mm





Tongue and groove system constrains in X but allows thermal contraction in Z.
(Similar system for U beam)


Vacuum Vessel

Thermal shield with 50 K Thermal Intercept

He Bath

Copper insert with tapered bore soldered into iron former as part of the beam tube assembly

10mm bore shielded bellows



Bellows design still being worked on, parameters are to –

- Accommodate thermal contractions of 6mm in Z and up to 0.6mm in Y.
- Minimise any steps/cavities in the beam pipe.
- 10mm ID for bellows between magnet former and He bath.
- Maximise the ID of the bellows between He bath and vacuum vessel

- Overall length of cryostat – 4m
- Beam pipe vacuum interface - TBD
- Alignment system – TBD
- Turret Services interfaces – TBD
- Beam Height - TBD
- Vacuum vessel – Girder Interface - TBD