# High Level RF



Chris Adolphsen

May 30, 2007 – GDE MAC Meeting at DESY

### ILC Main Linac RF Unit (1 of 560)



#### BCD and ACD Modulators (116 kV, 133 A, 1.6 ms, 5 Hz)

Baseline: Pulse Transformer Style Modulator Alternative: Marx Generator Modulator





#### ILC Baseline Modulator

FNAL Design in Which a Bouncer Circuit Offsets the Voltage Droop (19%) During Discharge of a Capacitor Bank



1 ms/div

0.5 ms/div

#### **Pulse Transformer Modulator Status**

- 10 units have been built, 3 by FNAL and 7 by industry (PPT with components from ABB, FUG, Poynting) thru DESY funding.
- 8 modulators are in operation.
- 10 years operation experience.
- Working towards a more cost efficient and compact design.
- FNAL building two more, one each for ILC and HINS programs – SLAC has built switching circuits with more up-to-date technology.

Transformer (red) and Lead Box (black) Containing Klystron



#### HVPS and Pulse Forming Unit



#### **Pulse Transformer Modulator Layout**



**Capacitor Banks** 



Bouncer Choke

# Waveform from the First of these Modulators

#### (Designed for 4 ms operation in support of the High Intensity Neutrino Source program)



#### XFEL Modulator Development

- Expand vendor base
  - Ordered 2 different prototypes from 2 vendors
    - Imtech-Vonk
    - Thompson
  - Delivery ~ Dec 2007



- Test in new facility in Zuethen that includes the modulator, cable, pulse transformer, klystron, interlocks and controls
- Complete evaluation, submit RFQs in 2008/2009
- Expect delivery of 30-40 modulators in 2009-2011
- For ILC, compliments Marx/Direct alternative designs

# Prototype #1 (Imtech-Vonk)

690Vac

#### Bouncer Type

- Specified by DESY
- 12kV HVPS
- Bouncer 300uH/4.6kA
- 7 stage IGCT main switch
- Digital regulation circuit
- Analog inputs/outputs
- Well known and tested principle





# Prototype #2 (Thompson)

- Pulse Step Modulator
  - 24, ~ 0.5 kV, Marx-like cells are summed to drive a 12:1 transformer
  - Bouncer circuit eliminated
  - FPGA based control
  - 2 stages for redundancy
  - Pulse width modulation for fine control
- Slew rate and pulse shape controllable
- Concept used in PS's Thales built for the W7-X experimental fusion reactor







### **Marx Generator Modulator**



# 12 kV Cell Detail





### **Diagnostic Controller Details**



#### Marx Cell Component Testing



### **Cantilever Backbone**



#### 6. Vernier Cells

#### Main Vernier Cells

- Four cells programmed to correct for up to 30% droop of main waveform
- Equivalent in action to "Bouncer" circuit of BCD
- Leaves +/- 0.5% short ramps across waveform
- Needs special timing program, under design
- Will not be implemented in first power tests
- Second Order Vernier Corrector
  - Single rackmount unit at bottom of stack to correct small ramps, in effect programmable D/A Converter
  - Timing derived from Main Vernier timing
  - Designed by LLNL; first prototype under construction
  - Will not be implemented in first power tests

# MARX Prototype



#### 120kV Output – 120 µsec width



#### 100kV Output – 1400 µsec, Leveled



### 150 kW Air-Cooled load



# MARX Plan for 2007

- Currently improving protection circuits and matching IGBTs (run at low rep rate).
- Perform short power test (100 hrs) with full charger supply, load.
- In parallel complete Vernier, Buck Regulator Boards.
- Complete full power 2000 h test with resistive load.
- Install tested unit in air-water cooled enclosure.
- Move to End Station B to power Toshiba 10 MW Multi-Beam Klystron.
- Begin work on DFM version soon (also DTI will build a Marx Modulator by next Summer through SBIR funding).

#### Stangenes Marx Generator (for NATO Radar System)





#### Baseline: 10 MW Multi-Beam Klystrons (MBKs) with ~ 65% Efficiency: Being Developed by Three Tube Companies in Collaboration with DESY



# Status of the 10 MW MBKs

- Thales: Six tubes produced some have cavity oscillation problems at full power that can be tuned out – next version has fixes for this, to be tested in June.
- CPI: One tube built and factory tested to 10 MW at short pulse. At DESY with full pulse testing, only achieved 48-55% efficiency with long pulses.
- Toshiba: One tube built and tested at DESY where it has run at full power for 750 hours with good efficiency (66%).
- These are vertically mounted tubes all three companies are currently building horizontal versions for XFEL (also needed for ILC).
- First 10 MW MBK to be acquired by SLAC/KEK this year for long-term testing.

# 2006 Test of Toshiba MBK

- June 8: Start installation
- June 14: Adjust filament setting
- June 16: Modify tube socket
- June 19: Run at 115kV, 134 A, 1.7mS, 10 Hz
- June 20: Achieve 10 MW, 1.5 ms rf pulses at 10 Hz (150 kW average output power)
- July 4-5: Test for 24 hours
- October 12: Removed from test stand
- Total time of operation on the test stand = 750 hours, 80 % at full power





# Toshiba MBK Test Data





# Horizontal MBK for XFEL

Expect the first horizontal MBK this Fall. DESY is currently working with three companies to design the klystron interface to the transformer tank



# **XFEL Klystron Program**

- New Thales tube (SN5) with modifications to be tested in June.
- Preparing for horizontal MBK test using existing (ABB) pulse transformer.
- Test HV cable connection.
- Continue investigation of phase, output power and perveance stability of MBK.
- Study breakdown rate of rf components and klystron windows as a function of waveguide pressure.
- Develop fast klystron protection against RF breakdown.





# SLAC SBK Design Group

- Erik Jongewaard (Program Manager/ME)
  - Magnet structure and RF circuit/drift tunnel design
- Daryl Sprehn (Chief EE)
  - Magic and AJdisk RF sims, 3D RF sims, egun sims
- Andy Haase (ME)
  - Couplers, Window and beam diagnostics design
- Rich Schumacher (ME)
  - Anode and device interface (supports, tank, etc.) design
- David Martin (ME)
  - Global design coord, egun and collector design
- Alex Burke (EE)
  - Michelle egun sims, Magnet magnetics sims
- Aaron Jensen (EE)
  - FLUKA beam interaction sims, 3D RF sims

### **Beam Transport and RF**

The elliptical beam is focused in a periodic permanent magnet stack that is interspersed with rf cavities



Lead shielding

Magnetically shielded from outside world

Have done:

3D Gun simulations of a 130 A, 40:1 aspect ratio elliptical beam traversing 30 period structures.

3D PIC Code simulations of rf interaction with the beam.

# **SBK Simulations**









# **Sheet Beam Program**

- Build beam tester and klystron by Summer 2008
- The beam tester will validate 3-D beam transport simulations and allow a more rapid turnaround for electron gun changes
- The klystron will be developed in parallel with little feedback from the beam tester. A rebuild of the klystron can incorporate design changes motivated by the beam tester

# **RF** Distribution Development



### ILC RF Distribution Math (for 33 MV/m Max Operation)



33 MV/m \* 9.0 mA \* 1.038 m = 308 kW (Cavity Input Power)

- × 26 Cavities
- × 1/.93 (Distribution Losses)
- × 1/.86 (LLRF Tuning Overhead)
- = 10.0 MW



### Replaced 3-Stub Tuner with Phase Shifter









V/m 300 281 244 · 206 -169 131 93.7 56.2-18.7

# Adjustability

With customizable (2 post) asymmetric shunt tees, have a tunable waveguide system that eliminates the "weak cavity" limit in the cryomodules



Adjust Input Power (P) and Cavity External Q to optimize for Gradient (G)



#### At SLAC, Developing Variable Tap-Offs Using Mode Rotation



RF Distribution System without Circulators but with Variable Tap-offs (VTOs)



SLAC is building VTOs and Hybrids and acquiring parts (including circulators) to assemble an rf distribution system for the first FNAL cryomodule









# **Gradient Optimization**

Consider uniform distribution of gradient limits  $(G_{lim})_i$  from 22 to 34 MV/m in a 26 cavity rf unit - adjust cavity Q's and/not cavity power (P) to maximize overall gradient while keeping gradient uniform (< 1e-3 rms) during bunch train

Case	Not Sorted [%]	Sorted [%]
Individual P's and Q's (VTO and Circ)	0.0	0.0
1 <i>P</i> , individual Q's (Circ but no VTO)	$2.7\pm0.4$	2.7 ± 0.4
<i>P</i> 's in pairs, Q's in pairs (VTO but no Circ)	7.2 ± 1.4	0.8 ± 0.2
1 P, Q's in pairs (no VTO, no Circ)	8.8 ± 1.3	3.3 ± 0.5
G <sub>i</sub> set to lowest G <sub>lim</sub> (no VTO, no Circ)	19.8 ± 2.0	19.8 ± 2.0

#### Optimized $1 - \langle G \rangle / \langle G_{lim} \rangle$ ; results for 100 seeds

"Sorted" means cavities are arranged in pairs of nearly equal  $G_{lim}$ The number after "±" is the rms value

Karl Bane

#### ILC Cost with Variable Tap-Offs (VTOs), Circulators and Large Gradient Spread

- Assume cavities produced with flat distribution of sustainable gradients
   (G) from 22 MV/m to 34 MV/m with <G> = 28 MV/m
- With Qeo optimized for Go = <G>, achieve flat cavity field at G with
  - Qe = Qeo \*  $\ln(2) / \ln(1 + G/Go * Qeo/Qe)$
  - Input Power = Po \* (1/4) \* (1 + G/Go \* Qeo/Qe)^2 \* (Qe/Qeo)
- Requires 6.8% more power on average per rf unit
- Maintain rf unit layout but increase linac length by 31.5/28 -1 = 12.5%
- At 31 MV/m, which is a +3-sigma variation in the mean gradient of a half rf unit, have same 16% tuning overhead as present design at 33 MV/m.
- Considering all changes, ILC cost increases by about 7%

Initially, the KEK Superconducting Test Facility (STF) will use mostly existing or off-the-shelf baseline rf components – same for the FNAL ILCTA@NML Facility.



#### **STF Phase 1 Plan**



# **STF L-Band Source at KEK**

Waveguide to Distribute Power for Coupler Testing



Pulser Unit for a Pulse Transformer Modulator



# **SLAC L-Band Test Stand**



Produce 5 MW, 1.4 msec pulses at 5 Hz with a TH2104C klystron and a SNS-type modulator
Source powers a coupler test stand and a normal-conducting ILC e+ capture cavity





#### ILC Positron Capture Cavity Prototype



# 2008-09 Overarching Goals

- Demonstrate rf system performance at the level required for the EDR
  - Design approaches finalized
  - Industrial versions built
  - Reliability measured at few 10 khr level
  - Cost and path to mass production understood
  - Potential vendors identified
- Use ILC-like rf sources in 'string tests' to power an rf unit (3 cryomodules) at FNAL and later one at KEK

#### **FY08-09 SLAC Deliverables**

- Design-for-Manufacturability Marx (start in FY07)
- 6 Modulator Production Units
- Toshiba10 MW MBKs (purchased in FY07)
- Sheet Beam Klystron (started in FY07)
- 6 Klystron Production Units
- 5 RF Distribution Systems to FNAL (1 in FY07)
- 60 Processed Couplers to FNAL (12 starting in FY07)
- Coupler Development and Prototypes
- 5 Production RF Sources Operating at SLAC (1 at FNAL)

# **RF Source Summary**

- SLAC pursuing alternate designs while XFEL concentrating more on baseline approaches.
- Marx Modulator looks promising.
- Toshiba 10 MW MBK appears robust, Thales MBK problems seem to be understood – horizontal versions being developed.
- A sheet beam klystron is being built that is more compact, lighter and likely less expensive than the MBK.
- Evaluating various rf distribution approaches to lower system cost and maximize useable gradient.
- Well developed plans for US rf program in FY08-09.