



XFEL: which ILC questions are answered?

H. Weise, for the XFEL Project Team







The European

The European X-Ray Laser Project X-Ray Free-Electron Laser

From the Idea to the TDR, and to the Project Start





Integrated X-Ray Laser Laboratory **Technical Design Report** March 2001

The Superconducting Electron-

Positron Linear Collider with an

TESL

TESLA

2001 XFEL Proposal

- 1st electron beam accelerated at TTF 1997
- 1st lasing at TTF-FEL (80-120 nm) 2000
- 1st lasing at TTF (VUV-FEL) 30 nm 2005
- 2006 13 nm and saturation many happy photon beam users
- 2007 energy upgrade to 1 GeV, i.e. 6 nm in reach





October

2002

2002 XFEL Supplement



2006 XFEL Final TDR

2003 German Science Council recommends building the XFEL

The European

X-Ray Laser Project

- **2004 Project Preparation Phase MoU between European Partners** (project preparation)
- 2006 Final TDR incl. detailed technical layout and experiments **Planning Approval**







XFEL International Project Organization



issues STI (chair: F. Sette, ESRF)

WG on Administrative and Funding issues AFI (chair: H.F. Wagner, Germany)

Bi-lateral negotiations between Germany and signature countries on funding contributions are ongoing



XFEL Schedule





XFEL Civil Construction

The requirements for all **XFEL buildings were specified** on the basis of several iterations with all involved technical groups. The process,

- starting with simple brainstorming,
- followed by detailed discussions about TTF experience,
- a long discussion about the accelerator tunnel layout
- close collaboration with professional civil engineers specialized on underground buildings

now ends in the **call for tender procedure** (June 6th, 2007) for the civil construction, and was strongly supported by Engineering Data Management tools.

A side remark / experience: Scientists liked the good old paper (pdf files), while engineers took quite some advantage of EDMS





XFEL Buildings



A great help: The **XFEL injector is basically a copy of the TTF Linac**. All the experience wrt. the technical infrastructure was an excellent starting point.











Detailed specifications allow the beginning of construction work for all XFEL buildings. The work is completely secured by the official **Planning Approval**.

Hans Weise, DESY ILC 2007, May 30, 2007



The European

X-Ray Laser Project X-Ray Free-Electr



XFEL Ground Breaking







Ground-breaking is expected for early spring 2008.

The tunnel and shaft buildings will be realized in a depth from 12 m up to 44 m below the surface. The **foundation** of the buildings will thus be situated **below the groundwater table** and the buildings will lie up to 20 m inside the groundwater.



XFEL Buildings



2000 m accelerator tunnel

3850 m electron and photon beam transport

10 halls / 9 shafts including so-called distribution shafts, i.e. the splitting of tunnels

Approx. **12-15% of ILC effort** (site depending)

Figure 7.1.3: Nomenclature for the main buildings of the XFEL facility for the two building phases, both above and below surface.





XFEL Distribution Shaft (XSE)







tiremen's lift



The European X-Ray Laser Project X-Ray Free-Electron Laser

XFEL Tunnel



The **XFEL tunnel layout** was developed in several iterations.

A **mockup** is currently under construction.

Installation procedures are under study.











XFEL Tunnel Mockup







GEMEINSCHAF

XFEL Tunnel – Draft Installation Schedule



ILC 2007, May 30, 2007















1st beam in Injector-> r1st beam in Linac-> r1st SASE(1) at 0. 2 nm-> rAll beam lines oper> e	mid 2012 mid 2013 mid 2014 end 2015	Week 52 Arrange storage areas Continue installing 2 DN 100 cold
		 water lines (supply & return): 60 m/w (12 m/d) Continue installing cooling tower & high pressure water lines: 60 m/w (12 m/d) Continue pulling 10 kV cables on left side: 210 rm/w Continue pulling pulse cables on left side: 210 rm/w Continue pulling cables
240 m 480 m XSE	720 m 960 m 1200 m 1440 m 1680 m 1920 m 216	oo m XS1















XFEL Accelerator Components

RF Gun + 1 single acc.module

25 units (4 acc. modules each)

Rapid start-up scenario for 17.5 GeV

101 Accelerator Modules

(1) x 4 x 8 x 23.6 = 500 MeV

(2+1) x 4 x 8 x 23.6 = 1.5 + spare -> 2 GeV

(20+1) x 4 x 8 x 23.6 = 15.1 + spare -> 17.5 GeV

module installation from 3/2012 until 7/2012 at a rate of 1 unit / day all modules to be tested at AMTF between mid 2010 and mid 2012

cold-mass delivery at a rate of 1/week; 1st cold-mass delivered Q3/2009
1st cavity string components Q3/2009
1st module spring 2010
i.e. all accelerator components ready to order end of 2008; actual R&D status supports this





XFEL Accelerator Module Test Facility



TDR version of the AMTF. After some iterations (costs, practicability) the final version to be built until 2009 will look slightly different.

The XFEL requires an **Accelerator Module Test** of all 101 individual modules. The test rate is 1 module/week corresponding to the envisaged assembly rate. In order to be most efficient, the **vertical test** of bunches of cavities is integrated. Other issues are **waveguides and cold magnets**.









There are at least two well established 'sources' for an **industrial cavity production** guaranteeing the required rate of 8 to 10 cavities per week over two years. **At the companies, new infrastructure is required** but the effort is well understood.

Cavity treatment will be done in industry. In order to prepare this, two companies will do the first electro-polishing of 12 9-cell cavities each in 2007.

The **quality check** will be done in terms of a vertical test on the XFEL/DESY site. The **tested cavities will be given to industry** for string/module assembly.



Cavity Strings

While the XFEL will use 100 cavity strings of 8 cavities each,



the set of the

The **technology transfer** to industry is done for the XFEL.

Minor differences in the module design have basically no impact.

The XFEL foresees two parallel lines (companies) for string assembly.



The European

X-Ray Laser Project



RF Main Power Couplers

While the XFEL will use 800 RF main power couplers of type TTF III,

the ILC design is based on the same coupler type, but needs 15,000.



Also here the **technology transfer** to industry is done for the XFEL (LAL Orsay).

At the end, **several companies** should be qualified to build a larger number of couplers.

The XFEL foresees at least two parallel lines (companies) for coupler production.

Coupler conditioning might be still done at the labs, the transfer to industry requires setting-up complete RF stations. Not a principle problem....



Damping of Higher Order Modes (HOMs)







Slow and Fast Frequency Tuner



On the first glance XFEL and ILC tuner look completely different. But **critical parts** like motor, gear box, and eventually piezos (fast tuner) **can be identical**.

- The slow tuner compensates for drifts; 400 kHz range, 1 Hz resolution.
- The fast tuner compensates the Lorentz-Force detuning during the RF pulse.







Accelerator Module (Cryomodule)





Accelerator Module (Cryomodule)

The XFEL accelerator module is based on the 3rd cryomodule generation tested at the TESLA Test Facility and designed by INFN.

Already 10 cryomodules have been built and commissioned for the TTF Linac.

Module 6 and Module 7 (repl. ACC3) were just recently installed at TTF/FLASH.

Additional cryostats will be available end of this year:

- Module 8 (most likely ACC7)
- Module 9 (FNAL ass. kit)
- Module 3**
 (spare ACC1, sched. 2008)
 2 2 cold messes in 2009
- 2-3 cold masses in 2008



The same principle design is used for XFEL and ILC.

Minor modifications (quads, BPM, nbr. of cavities, overall length) should have almost no impact on industrialization.

Open issue: vibration sensitivity in the ILC case. The XFEL requirements are fulfilled.





Accelerator Module (Cryomodule)





High Power RF System







High Power RF System



XFEL has 32 cav. per klystron, ILC 26.

Due to the higher gradient, the 3.9 MW for the XFEL at the cavities becomes 7.6 MW. This leaves approx. 15% each for wave guide losses and regulation reserve.

The XFEL will install 25 klystrons in the tunnel while ILC wants to put the klystrons & modulators in the **2nd tunnel**.





Low Level RF Control

The XFEL LLRF requirements are driven by the injector, its' bunch compressors, and the demand for high stability of the photon intensity. The RF system needs **0.01% amplitude and 0.01 deg phase stability!!!** Successful tests were performed at TTF/FLASH.

The **ILC numbers:** 0.35% amplitude and 0.07 deg phase stability (correlated).



The **operational requirements** are probably different but similar to handle. Here the number of spare RF stations as well as the aimed uptime defines the 'rules of the game'.



XFEL: which ILC questions are answered?

- how to build a 100 accelerator module linac using TESLA Technology
- how to industrialize the SCRF on a 5% ILC scale
- how to extrapolate from TTF / FLASH by a factor of 20 Remark: ILC eq. 20 XFEL
- how to start and organize an international project based on in-kind contributions







The European

X-Ray Laser Project