Ralf Diener Peter Schade Klaus Dehmelt



The ILC TPC Large Prototype : status and plans









- Infrastructure
- Fieldcage
- Fieldstrip Foil
- Time Schedule







bmb+f - Förderschwerpunkt

Elementarteilchenphysik

Großgeräte der physikalischen Grundlagenforschung



- 1. Introduction
- 2. Infrastructure
- 3. Magnet
- 4. Hodoscope and Trigger

5.Fieldcage a) Drawings b) Wall c) Field


6. Schedule

Ralf Diener, Hamburg University



Introduction

- Previous R&D done with small prototypes
- Now a Large Prototype is being build that will be used by many groups
- Common infrastructure
 - fieldcage and infrastructure (gas system, lifting table etc.)
 - 1T magnet and testbeam area
 - modular endplate
 - DAQ and readout electronics
 - trigger, Si hodoscope etc.
 - Readout modules with different techniques from R&D groups worldwide
 - Testbeam starts mid 2008: until then a working setup has to be ready



116



- 1. Introduction
- 2. Infrastructure
- 3. Magnet
- 4. Hodoscope and Trigger

5.Fieldcage a) Drawings b) Wall c) Field

6. Schedule





Infrastructure at DESY

e+

γ

DESY II

• Testbeam: electrons (1-6 GeV)

Spil Counter

e+

e-


- PCMAG:
 - magnetic field up to ~1.25T
 - installed at DESY and successfully operated
 - additional safety modifications ongoing



Lifting
 table will
 be installed



Sketch of TPC prototype in PCMAG





- 1. Introduction
- 2. Infrastructure
- 3. Magnet
- 4. Hodoscope and Trigger


5.Fieldcage a) Drawings

b) Wall


- c) Field
- 6. Schedule

PCMAG Field Map

- Production of a magnet field map:
 - measurement finished (July 07)
 - data analysis ongoing
 - plan: fieldmap finished by end of year of beginning of next year



116



Ralf Diener, Hamburg University









- The ILC Large TPC Prototype
- 1. Introduction
- 2. Infrastructure
- 3. Magnet
- 4. Hodoscope and Trigger
- 5.Fieldcage a) Drawings b) Wall c) Field


6. Schedule

Ralf Diener, Hamburg University



Surroundings: Hodoscope and Trigger

- ^{TPC} Silicon hodoscope:
 - should be "rotatable"
 - design details of support structure still under discussion



Limited readout area: 38.4 cm² 116


• Trigger (scintillators)


Si-ladder:

20µm in z

10-12µm in rø

- hardware ordered
- simple holding structure
- two perpendicular layers of slabs below the prototype







The ILC Large TPC Prototype

- 1. Introduction
- 2. Infrastructure
- 3. Magnet
- 4. Hodoscope and Trigger

5.Fieldcage a) Drawings b) Wall c) Field


6. Schedule

Ralf Diener, Hamburg University




Fieldcage Wall

- Profile of wall:
 - shielding
 - honeycomb with GRP layers
 - field strips




- Preliminary estimation of radiation length of fieldcage wall is below 2% X₀
- LP: 4.45%
 (2 walls + 72cm TDR or P5 gas)
 - Final TPC: 4.85% (2 walls + 130cm TDR or P5 gas)



Radiation Length in % of X_0 = 1.98%

116



Material	Rad length [cm]	Thickness	% of $X_{_0}$
Kapton	28.57	4x75µm = 0.0300cm	0.11
Nomex Honeycomb	1430.00	2.3cm	0.16
Copper	1.43	en ee pin ene reeen	
Epoxy	19.40	~1000µm = 0.1cm	0.52
GRP (70:30)	13.31		
some numbers are estimations!			





The ILC Large TPC


- **Prototype**
- 1. Introduction
- 2. Infrastructure
- 3. Magnet
- 4. Hodoscope and Trigger



6. Schedule



- Sample pieces with different cross sections available:
 - sufficient HV stability?
 - to test mechanical stability
 - to test manufacturing procedures



GRP (0.4mm)

1 Layer Kapton

GRP (0.4mm)

1 Layer Kapton

GRP (0.4mm)

Nomex

Nomex

GRP (0.4mm) 1 Layer Kapton



HV Tests of Fieldcage Wall

116



- 1. Introduction
- 2. Infrastructure
- 3. Magnet
- 4. Hodoscope and Trigger
- 5.Fieldcage a) Drawings b) Wall c) Field

6. Schedule


 Each sample piece tested up to 24kV (over >24h)

30cm

- All pieces passed the test without breakdown
- Test of sample with only one Kapton layer up to 30kV also successful

Ralf Diener, Hamburg University








Sample Piece of the Fieldstrip Foil




- 1. Introduction
- 2. Infrastructure
- 3. Magnet
- 4. Hodoscope and Trigger

5.Fieldcage a) Drawings b) Wall c) Field

6. Schedule



 ~100V between two strips possible in operation



IIL

Ralf Diener, Hamburg University






The ILC Large TPC **Prototype** 1. Introduction 2. Infrastructure 3. Magnet 4. Hodoscope and Trigger 5.Fieldcage a) Drawings b) Wall c) Field

6. Schedule

DESY








= Value below Accuracy Limit



Field Calculations







- 1. Introduction
- 2. Infrastructure
- 3. Magnet
- 4. Hodoscope and Trigger

5.Fieldcage a) Drawings b) Wall c) Field


6. Schedule





Field Calculation: Effect without Magnetic Field

- Maximal displacement in the central area well below 40 µm
- At the edges: up to 100 µm
- Needs to be corrected in reconstruction
 - Calculation with magnetic field on the agenda



116

