

# **Progress and Finding from EDR Kick-off Meetings**

Project Managers:  
Akira Yamamoto, Nick Walker and Marc Ross

Group Leaders Meeting,  
ILC-GDE Meeting, Fermilab, Oct. 22, 2007

# Tasks at KOM

- Review of RDR (BCD)
  - Verify design parameters and interfaces
- Discuss BCD and/or ACD
  - Unified design and/or plug-compatibility
  - Technical direction toward EDR
    - Industrialization and further basic R&D
- Develop Work Packages toward EDR

# Progress of KOMs

Technical Group	Day, (Place)	Chaired / Supported by	
Controls	8/20 ~ (ANL)	J. Carwadine (ANL)	
CFS-US	8/22 ~ (FNAL)	V. Kuchler (FNAL)	
RTML	8/27 ~ (FNAL)	P. Tenenbaum (SLAC)	
CFS-EU	9/03 ~ (CERN)	J. Baldy / J. Osborne (CERN)	
CFS-AS	9/10 ~ (KEK)	A. Enomoto (KEK)	
Cryomodulde & Cryogenics	9/12 ~ (KEK)	H. Hayano, N. Ohuchi (KEK) T. Peterson (FNAL)	
Cavities	9/19~ (DESY)	L. Lije (DESY), H. Hayano (KEK)	
E-source	9/24 ~ (SLAC)	A. Bachmann (SLAC)	
Main Linac Int.	9/27 ~ (FNAL)	C. Adolphsen / T. Shidara (SLAC)	
HLRF	10/1~ (SLAC)	R. Larsen (SLAC), S. Fukuda (KEK)	
E+source	10/8 ~ (Cockroft Inst)	J. Clarke (CCRC), J. Urakawa (KEK)	
Beam Del. Sys.	10/11~ (SLAC)	A. Seryi (SLAC)	
Damping Ring	11/5~ (Cockroft Inst)	A. Wolski (LBNL)	planned

We deeply thank RDR/EDR group leaders and chair (support) persons

# General Finding from KOMs (1)

- Design parameters to be verified:
  - Parameters lists of each component,
  - Interface between components,
- Plug-compatible concept critically important to allow:
  - Improvement of base-line design during EDR,
  - ACD with keeping plug-compatible interface,
- Complimentary R&D important
  - Learn most effective industrialization experience from XFEL
  - Further advanced/basic R&D to be complementary carried out
    - For upgrade of the BCD design based on the previous industrialization experience (with less additional demonstration)

# Technical Findings from KOMs (2)

Technical Group	Day	Finding (technical topics)
Controls & LLRF	8/20 ~	High availability control and redundancy
CFS-US	8/22 ~	ACD development
RTML	8/27 ~	Common housing/integration, beam dynamics (emit. Preservation)
CFS-EU	9/03 ~	Experience at <a href="#">LHC</a> , <a href="#">Safety</a> , IR Hall structure, exp. from <a href="#">Olympic</a>
CFS-AS	9/10 ~	<a href="#">Time scale</a> required to reach construction, exp. from <a href="#">ITER</a>
Cryomodule & Cryogenics	9/12 ~	Important <a href="#">plug-compatible</a> interface definition, <a href="#">Thermal balance</a> optimization b/w cryomodule and cryogenics, exp. at <a href="#">LHC</a> .
Cavities (process, and production)	9/19~	< E> 30 toward 35 MV/m, Process, Shape, compatibility, Industrialization ( <a href="#">XFEL</a> exp.+ ,) & further improvement (BCD/ACD)
E-source	9/24 ~	Cathode demonstration and vacuum R&D critical
Main Linac Int.	9/27 ~	Beam dynamics (HP/HOM), <a href="#">Quad.</a> alignment, <a href="#">dE/E</a> acceptable?
HLRF	10/1~	<a href="#">Marx Gen.</a> (ACD) encouraging, Effic. RF distributor, Min. remote cntl
E+source	10/8 ~	Target survivability, undulator, flux concentrater,
Beam Del. Sys.	10/11~	Crab and IR geometry, extendable <a href="#">to 1 TeV</a>
Damping Ring	11/5~	<a href="#">Expect – beam dynamics</a>

# Parameters and Interface

## Example: Cavity

Category	Item	Parameters	Notes
<b>RF properties</b>	Frequency	1.3 GHz	
	Number cels	9	
	Gradient, Q0	31.5 MV/m, 1.0 E10	In operation
		35 MV/m, 0.8 E10	In vertical test
	HOM damping	Q =	
		R/Q =	
	Short range wake	TBD	
	Temperature	2 K	In operation
<b>Phys. Properties</b>	Length	(1.36) m	
<b>(interface)</b>	Aperture	(60/80) mm	
	Alignment acc.	300 um	
	Wall thickness	2.8 mm	
	Stiffness		
	Flange/seal system	Material ?	
	Max pressure		
	Lorentz F detuning	1.00 kHz	with flat top at 35 MV/m
	...	....	

# Summary

- Design parameters and Interfaces to be well defined,
  - Plug compatible interface to be fixed,
- Industrialization and further basic R&Ds
  - Complementary efforts important
- Work packages to be established,
- Technology to be established with saving/optimizing cost, towards EDR
  - To be well discussed in parallel sessions,


# Appendix

# Cavities & Cryomodules

## Producing Cavities



4<sup>th</sup> generation  
cryomodule



Subdivision	Length (m)	Number
Cavities (9 cells + ends)	1.326	14,560
Cryomodule (9 cavities or 8 cavities + quad)	12.652	1,680
RF unit (3 cryomodules)	37.956	560
Cryo-string of 4 RF units (3 RF units)	154.3 (116.4)	71 (6)
Cryogenic unit with 10 to 16 strings	1,546 to 2,472	10
Electron (positron) linac	10,917 (10,770)	1 (1)

# Strawman CM schedule (Stanek)

