

ILD MDI/Integration WG Plan

T. Tauchi and K. Buesser

ALCPG07, 26th October, FNAL

Charge issued by the ILD Joint Steering Board:

- The MDI/working group is charged to produce a self-consistent design of the structure of the ILD detector from the viewpoint of machine-detector interface (MDI) and detector integration for the LOI that is to be submitted by October 1, 2008.
- Specifically, it covers the design of the beam pipes, magnets, iron return yoke, beam instrumentations, and their supports that require works by the detector group.
- Also, it should address general detector structure and assembly issues, where the aspects that affect the machine design will have initial priority. Beam background studies should be performed when necessary.
- The group should work closely with the machine people and the groups working on subdetectors that affect the structure of the ILD detector.
- (...)

MDI Issues



IR Design Optimization with engineering studies

- beam pipes, pumps, wakefields
- innermost radius of VTX and B-field
- outer radius of support tube and inner radius of TPC
- calorimeters, pair monitor and beam instrument

Background Estimation

- pairs v.s. B-field, (anti-)DID
- muons v.s. muon spoilers, collimation depth
- synchrotron radiations v.s. collimation depth, masks
- neutrons from pairs, extraction line and dump v.s. mask

IR of GLD and LDC



Relevant parameters for IR optimization

GLD and GLDc

LDC

Machine parameter sets	1TeV, HiLum-1		Nominal?
L^* (m)	4.5	same at GLDc	4.05
B (Tesla)	3	3.5 at GLDc	4
R_{Be} (cm)	1.5	$z < 5\text{cm}$	1.4
R_{VTX} (cm)	2.0	FPCCD	1.6
VTX angular acceptance	$ \cos < 0.95$	3 super-layers	$ \cos < 0.952$
R_{FCAL} (cm)	8	$z = 2.3\text{m}$	8
R_{BCAL} (cm)	1 and 1.8	$z = 4.3\text{m}$	1.3
QDO, FCAL, BCAL support	canti-lever 70cm Φ	W-tube	canti-lever 58cm Φ

Differences will be studied and tried to be understood.

Detector Integration Issues

Detector assembly on surface

Iron structure ;

- deformation due to B-field
- Field uniformity and Leakage magnetic field

How to support inner detectors and QD0 ($39\text{cm}\Phi$)

Opening, closing procedures, etc.

Underground hall requirements ;

- temperature, humidity stability, the gradient
- utility (power, cooling water, gases, cables etc.)
- safety for fire, earth quake

Push-pull issues such as ;

- alignment of VTX and QD0
- slow settlement ($100\mu\text{m}/\text{month}$ is tolerable ?)
- Radiation, shielding around beam line
- Cryogenics system for solenoid, QD0

Major Discussion Issues

1. Sub working groups to be organized

- IR design optimization
- Detector integration

2. Engineering studies

- Who are engineers at institutes ?
specialty and availability of FTE
- What engineering level is necessary ?
for Lol by 1 October 2008
for EDR by July 2010

3. How to share tasks ?

Roadmap to ILD - Lol

<http://ilcagenda.linearcollider.org/categoryDisplay.py?categId=129>

1. Working group activities and meetings

Phone meetings with Webex etc, and the WG mailing lists.

2. Series of ILD Workshop

1st (2.5 days), in Europe, **early January 2008**

2nd (1.5 days), TILC08, Sendai, **3-7 March 2008**

more

3. Decision of ILD Detector Parameters

in May 2008

4. ILD-Lol Submission , 1 October 2008