

# ILCTA\_NML



Thanks to Sergei Nagaitsev for use of his slides from the ILC School at Fermilab



## Purpose of ILCTA\_NML

- Provide ILC like beam for SCRF cavity tests
- Provide a facility for use by ILC collaborators
  - *Crab cavities*
  - *Diagnostics*
  - *Personnel training*
  - *Accelerator R&D*

## Controls Focus at ILCTA\_NML

- Create a stable and robust controls system for SCRF and associated components R&D
  - *Provide automatic procedures for cavity and cryomodule testing*
  - *Provide an infrastructure that can readily integrate components developed at collaborating institutions*
- Provide a venue for ILC Controls & LLRF R&D

## Opportunities for Controls R&D

- **Timing systems**
  - *RF Phase and Distribution*
  - *Data correlation*
  - *Clock System Development*
- **High Availability Platform for Beam Instrumentation**
  - *BPMs*
- **Beam Based Feedback**
- **Cavity Data Management**
- **Automation**

# S2 Task Force

Phase	Completion date	Description
0	2005	TTF/FLASH, not final cavity design, type 3 cryomodule, not full gradient, has beam but work is needed to have regular ILC bunch structure, roughly 2 RF units.
1	2008	1 cryomodule, not final cavity design, type 3 cryomodule (and/or) STF type cryomodule, not full gradient, no beam
1.1	2009	1 RF unit, not all final cavity design, not all type 4 cryomodules, not full gradient, beam not needed for tests, but should be built so it and the LLRF are debugged for the next step
1.2	2010	1 RF unit (replacing cryomodules of phase 1.1), final cavity design, full gradient, type 4 cryomodules, with beam
1.3	2011	1 RF unit (replacing cryomodules of phase 1.2), final cavity design, full gradient, type DFM cryomodules, with beam
1.4	2011	Tunnel mockup above or below ground. 1 RF unit perhaps built with parts taken from earlier tests. Includes RTML and e+ transport, no beam
2	2013	Several RF units at one site (of the final ILC?) as a system test of final designs from multiple manufacturers. Need for beam depends on design changes made after phase 1.4.
3	2013	XFEL
4	2018	First 2.5 km of ILC

## ILC basic design parameters

Center-of-mass energy range	GeV	200–500
Peak luminosity <sup>1</sup>	cm <sup>-2</sup> s <sup>-1</sup>	2×10 <sup>34</sup>
Beam current	mA	9.0
Pulse rate	Hz	5.0
Pulse length (beam)	ms	~1
Number of bunches per pulse		1000–5400
Charge per bunch	nC	1.6–3.2
Accelerating gradient <sup>1</sup>	MV/m	31.5
RF pulse length	ms	1.6
Beam power (per beam) <sup>1</sup>	MW	10.8
Typical beam size at IP <sup>1</sup> ( <i>h</i> × <i>v</i> )	nm	640×5.7
Total AC Power consumption <sup>1</sup>	MW	230

<sup>1</sup>) at 500 GeV center-of-mass energy



- Bunch length at IP (rms): 0.3 mm or 1 ps or 0.5° (1.3 GHz)

## RTML bunch compressor (key

Parameter	Nominal BC1 Value	Nominal BC2 Value
Initial energy	5 GeV	4.88 GeV
Initial energy spread	0.15%	2.5%
Initial bunch length	9 mm	1.0 mm
RF voltage	448 MV	11.4 GV
RF phase	-105°	-27.6°
Wiggler $R_{56}$	-376 mm	-54 mm
Final energy	4.88 GeV	15.0 GeV
Final energy spread	2.5%	1.5%
Final bunch length	1.0 mm	0.3 mm




## IP offset defines the time jitter of the collision point



$1 \text{ ps} \approx 0.3 \text{ mm} \approx 0.5^\circ$


# One ILC RF Unit



## ILCTA Plans

- Effort is Funding limited → phased approach
- Cryomodule delivery
  - 1<sup>st</sup> (Type 3+) cryomodule being assembled now from “kit” of DESY
  - 2<sup>nd</sup> (Type 3+) CM – 2008 built with U.S. processed cavities
  - 3<sup>rd</sup> (ILC Type 4) CM – 2009 all U.S. components
  - Replace all three CMs with ILC Type 4+ in FY2010
- FY07: Start as a Cryomodule Test Stand
- FY08: move A0 photoinjector, start civil construction for new bldg
- FY09: 1<sup>st</sup> beam operation, 2-3 CM, low rep rate operations
- FY10: replace all 3 CM with ILC type CM
- FY11: install new refrigerator, ILC RF Unit operations
- Collaboration: DESY, INFN, ANL, Cockroft, NIU, Rochester, KEK


- The A0 Photo Injector built in collaboration with DESY as part of the TESLA collaboration ( essentially a copy of TTFI)
- In operation since late 90's
- Two klystron-based RF systems power the RF Gun & Capture Cavity
- Built a second capture cavity (CCII) using high gradient DESY cavity
- A0 RF assets and CCII will be moved to NML in 2008



**RF Gun prior to solenoid installation**



**Capture Cavity and beamline**



**Capture Cavity-II**

# Scope of LLRF Projects


- **Vertical Test Stand**
  - *Cavity testing with automation - analog LLRF (TD/Jlab)*
- **Horizontal Test Stands**
  - *Dressed cavity testing - DESY/FNAL LLRF controller(Simcon)*
    - **Simcon is a 10 channel input VME controller developed for DESY**
- **High Intensity Neutrino Source HINS**
  - *325 MHz, Fast Ferrite Vector Modulator -, LBNL/SNS//FNAL*
- **Coupler Conditioning Stand**
  - *1.3 GHz and 3.9 GHz - rack and stack -> Simcon*
- **NML - Full RF Unit Test - no beam**
  - *3 Cryomodules with 24 cavities - Simcon followed by FNAL design (MFC Module)*
- **NML - Photo Injector Source - beam to test string**
  - *Beam based calibration, beam loading, phase reference line - Simcon*

## Our Path to Meet these Goals

- **Evolve the 10 channel DESY Simcon system**
  - *Higher Intermediate Frequency development*
  - *Fermilab is producing a next version Simcon card to improve noise and bandwidth performance*
    - **Status: close to production**
- **Develop a Multi-Channel Field Control Module (MFC)**
  - *33 ADC channels, FPGA, DSP, 4 DAC channels*
  - *High density, low cost, low power and is based on VXI*
  - *Status: Front-end testing complete, close to production*
- **Develop the analog RF sections**
  - *96 channel receivers*
  - *Transmitter*
  - *Master Oscillator*
  - *Phase Reference Distribution with pulsed reference line*



# Prototype Master Oscillator

1300 MHz low noise DRO: 10MHz VCXO: Programmable frequency outputs



# Prototype LO Gen/Down-converter


## 1313 MHz Local Oscillator




2nd harmonic -69dBc



# CC2 Results with 13 MHz IF



250 kHz IF




13MHz IF

# Piezo-electric Control of CC2

The Piezo-electric actuator counteracts the Lorentz force to maintain the cavity on resonance

Cavity field @ 25 MV/m


Piezo Drive -green  
 Cavity Probe - Cyan  
 Reflected Power - Magenta






# ILC

International Linear Collider

## ESECON 10 channel LLRF controller







- Crosstalk on ADC2 when ADC1 input is 2V pk-to-pk , 62.5MHz.
  - Histogram is average of 10 65K samples, individual sigma is 0.9
- Controls & LLRF EDR Kick-off Meeting, Aug 20-22, 2007

## 10 channel LLRF controller measurements

*This plot is still preliminary*

ADC phase noise at zero crossing.  $f_s=78.125\text{MHz}$ ,  $f_{in}=62.5\text{MHz}$





- **Uses FNAL hardware:**
  - ESECON 10 channel LLRF controller.
  - Master oscillator.
  - Up/Down converters.
  - Timing.
  - Modified DOOCS server and GUIs running on Linux-VME.
- **After few hours running, (system has not been optimized yet)**
  - Amplitude regulation better than 0.1% rms.
  - Phase regulation better than 0.05° rms.
- **Potential for optimization:**
  - RF noises.
  - Control strategy.
  - Digital filter.

# Conclusions

- **For a single RF unit:**
  - *Need a bunch compressor to resolve 0.05-degrees or 100-fs. Bunch length of 1-ps should work, 10-ps will not.*
  - *Can not run beam close to zero-crossing because of energy spread induced by rf slope and low injection energy.*
  - *Need also to measured the incoming bunch-to-bunch energy jitter so this calls for dispersive section (a compressor) before the CM*
- **For two RF units:**
  - *Need two rf units or, at least, two rf systems powering two cryomodules*
  - *Does not require bunch arrival jitter measurements.*
  - *Can run beam at zero-crossing*