

### ACD Down-Select Criteria and Time Scales for HLRF

#### ML-KOM FNAL September 27、2007

S. Fukuda, KEK & Ray Larsen, SLAC For the ILC HLRF Collaboration

# HLRF Collaboration

- Spokesperson & Asia HLRF Technical System Lead: S. Fukuda, KEK
- Americas HLRF TS Lead: R. Larsen, SLAC
- Contributors:
  - DESY: W. Bialowons, S. Choroba
- KEK: M. Akemoto, H. Hayano, T. Shidara
- FNAL: B. Chase, C. Jensen, J. Reid, M. Champion, O. Nezhevenko, H. Pfeffer, D. Wolff
- SLAC: C. Adolphsen, R. Cassel, C. Corvin, C. Nantista, M. Neubauer





Many slides are based on the Ray's talk in DESY, June 14, 2007. More detailed discussion will be performed at HLRF KOM held in Oct.1-2, 2007

- I. EDR Working Definition
- II. Proposed HLRF Work Packages
- III. Example Work Package
- IV. Industrialization Assumptions
- V. HLRF Factory Model Assumptions
- VI. Conclusions



#### I. EDR Working Definition

- EDR should be completed in two years, i.e. 2010(?).
- Detailed technical and cost plans are to be considerably more mature than RDR.
- Schedule, new cost estimate, funding profile are clarified.
- We should provide solid basis for international funding requests, implying
  - <u>Technology down-selects recommendations</u> in hand
  - <u>Industry based cost</u> estimates in hand to compare with estimates



#### • Management Level Tasks

- 1. Develop Work Packages for R&D
- 2. Develop specifications as basis for bid packages
- 3. Identify industrial vendors for advanced prototypes (Design for Manufacture, DFM)
- 4. Procure pre-production prototypes
- 5. Complete EDR documentation
- 6. Recommend technology down-selection



- R&D Tasks (in parallel)
  - 1. Complete Alternate Conceptual Design prototypes
  - 2. Complete DFM designs, specifications, bid packages
  - 3. Evaluate industrial DFM prototypes

## II. Proposed Work Packages (WP's)

- Prepare Separate WP's for Modulator, Klystron, Distribution
  - Common WP's for BCD and ACD in the three regions
    - How to establish the regional collaboration?
- Common WPs are made by Project Manager.
- Real WP is deeply related by DOE budget profile in USA, while other region (ex. Japan) has a different style. Especially treatment of human resource is quite different.
- Example (Next slide)





Leve1-3 System Maneger

Mo		WPMo	dubtor		WP KLYSTRON					
	WP:Base Line	WP:MARX	WPCont /Interbc k	WPMod Industrial ization	WPBase Line Klystron	MAG	WP RBK	WP SBK	WP: Super MBK	
EU-DESY-XFEL		С				С				
	SLAC		C	C	C <b>(</b> US)				C	
US-DOE	FNAL									
OQ DOF	LLNL		MoU							
	UNI						С	С		
JAPAN	KEK				C(ASIA)					С
JAFAN	UNI									
KOREA	POHAN									
	UNI									

Green shows the contribution supported by some budgets, and C Shows the central contribution for the WP's technology\_

September 27, 2007

# Proposed Work Packages (WP's)-Cont.

- Prepare Separate WP's for Modulator, Klystron, Distribution
  - Develop DFM design, build prototype, execute test program How to establish the regional collaboration?
  - Develop specifications for bid packages
  - Ideally each region lets bid for evaluation unit or units, shares costs, testing experience

NML(FNAL)/ SLAC/ STF(KEK)/ XFEL(DESY)

- Note: These could be different designs!
- Procure, test, apply to L-Band test programs
- Modify bid packages for pre-production quantity procurement



- Charger system, Controls-Interlock system also WP candidates for delivery of pre-tested integrated systems
  - Could also be part of modulator, klystron systems respectively



	EDR goa descripti		Milestone	Start date	Finish date	Proposer / requester	Possible benefit	Possible risk	Impact on whom	Tests needed to allow decision	Tests after decision	Expected deadline
Suggested entries							Cost, improved design, better performance		ILC Area or technical group name	demonstration, high- power test, integrated systems test, beam test, life-time test or		relative to EDR (assume 2010)
HLRF												
Modulators												
	Marx Mod	dulator	Completion of 2000 hour test	Aug-07	Dec 2007	HLRF TS	Cost saving, higher reliability, space in tunnel		CF&S, installation		Built and go to DFM	end 2007
			DFM design	Aug-07	Mar 2008	HLRF TS	Reconfiguration to fit tunnel, cost, mass production	Fallback to	CF&S, installation	(partly in-house): Hope	Built and test more, interregional	end 2009
	Baseline		Mass production of XFEL and FNAL effort	now	end 2009	HLRF TS	Industrialized	Added cost, DFM changes being introduced	CF&S		Mass production	end 2009

# Work Package Table (Lutz table) -2

Suggested entries HLRF	EDR goal/task description	Milestone	Start date	Finish date	Proposer / requester	Possible benefit Cost, improved design, better performance	Possible risk	Impact on whom ILC Area or technical group name	Tests needed to allow decision demonstration, high- power test, integrated systems test, beam test, life-time test or	decision	Expected deadline relative to EDR (assume 2010)
Klystron											
	Sheet beam	First prototype test	now	1-Jul-08	HLRF TS	Cost saving, space in tunnel		CF&S, installation		Built and go to DFM	
		DFM design and construction	Jul-08	end 2009	HLRF TS	· · · · · · · · · · · · · · · · · · ·	Fallback to BCD choice	CF&S, installation	Built in three regions	Long-time test on test stands	end 2010
	Baseline	XFEL horizontal tubes 1000h test	now	1 lon 08	HLRF TS	Industrialized version qualified, fit to tunnel	Added cost, DFM changes being introduced	CF&S		Mass production	
		KEK and SLAC vertical tubes tests	2007/12/1 (SLAC)	1-Jaii-00	HLRF TS						
			2009/4/1 (KEK) ?(FNAL)		HLRF TS				Performance demonstration for ILC Spec	Mass production	end 2010

September 27, 2007



	EDR goal/task description	Milestone	Start date	Finish date	Proposer / requester		Possible risk	•	Tests needed to allow decision demonstration, high-	decision	deadline relative to
Cummo et e d						Cost, improved		ILC Area or	power test, integrated		EDR
Suggested entries						design, better performance		technical group name	systems test, beam test, life-time test or		(assume 2010)
HLRF						performance		group name			2010)
RF distribution											
	Non-circulator distribution	test at FNAL and KEK	now	Mar 2008	HLRF TS			CF&S, installation, LLRF	Operation (with beam?)		
		test at FNAL	now	Mar 2008	HLRF TS		RF breakkdown, Fallback to BCD choice	CF&S, installation, LLRF	Operation (with beam?)		
	Integrated design	test with Type 4 cryomodule	now	Mar 2009	HLRF TS						



	EDR goal/task description	Milestone	Start date	Finish date	Proposer / requester	Possible benefit	Possible risk	Impact on whom	Tests needed to allow decision		Expected deadline
Suggested entries						Cost, improved design, better performance			demonstration, high- power test, integrated systems test, beam test, life-time test or		relative to EDR (assume 2010)
HLRF											
Mod	ulators										
	Marx Modulator (Lower voltage)	Next of High Voltage Marx (KEK)	Marx Collabora- tion		KEK	Cost saving, higher reliability, space in tunnel	Fallback to BCD choice	CF&S, installation		Built and go to DFM	end 2011
Kly	stron										
	Super MBK	Show feasibility	Now 1/6 model		KEK	High Reliability Cost saving, space in tunnel		CF&S, installation	Complete 2000 hours	Built and go to DFM	end 2011



- All major system components will be provided by industry
- Industrialization has at least two meanings:
  - 1. Development & deployment of industry process for new designs of an exotic nature, e.g. SCRF structures, Sheet Beam Klystron, etc.
  - 2. Identification & qualification of vendors for new designs of non-exotic nature, e.g. Modulator, Charging System, Controls & Interlock Protection System

## General Procurement Strategy

- ILC is developing and will <u>own</u> designs from ACD process
- Specifications will be developed for "Build to Spec" procurement
- Vendors may choose to offer any design that meets specifications including ACD designs
- Owning designs important for long term future:
  - Modulators, Distribution have virtually no follow-on business so future procurements could be problematical
  - Klystrons have significant follow-on business but much smaller; owning a design is excellent insurance against future vendor ability to deliver (e.g. PEPII experience)
- HLRF cost models assumed procurement split 50-50 between 2 vendors. (Actual ratios would vary.)

# V. HLRF Factory Model Assumptions

- Factory Models developed for Modulators, Klystrons and Distribution for cost modeling in 2006:
  - Factories to provide fully tested units essentially ready for final prep and installation to tunnels
  - Factories to be provided with necessary test equipment, support personnel
  - ILC inspectors at factory sign off on testing before shipment allowed
  - Delivery to on-site staging area for nominal inspection that no damage occurred in shipping, plus final prep before releasing to installation

#### HLRF Factory Models 2

• Some Details:

ilr

İİİ

- All components to be built to specifications (electrical power, cooling, mechanical form factor, drive requirements, test procedures)
- Modulator factory to be provided with fully instrumented test stations, test loads
- Klystron factory to be provided with klystron test stations, RF driver system, water loads
- Integrated Distribution systems to be delivered packaged for quick final assembly, mounting on cryo-module in staging area for cold tuning prior to moving to tunnel



#### **VI.** Conclusions

- EDR is window of opportunity for strong interregional growth in ILC HLRF
  - HLRF has strong Alternate R&D program to improve costs, availability
  - Strong inter-region contributions can be advanced through shared Work Packages
  - WP's for major HLRF components R&D, industrialization proposed for discussion
  - Early collaboration agreements & commitments necessary for EDR success