## Cold L-Band Cavity BPM Status – updated version 8/10/2007 –


BPM Team: Nathan Eddy – AD Andrei Lunin – TD (Kevin O'Brien – AD) Eric Pirtle – AD Gennady Romanov – TD Nikolay Solyak – TD Linda Valerio – AD Manfred Wendt – AD



- Cold L-Band cavity BPM for an CM with < 1  $\mu$ m resolution.
- Waveguide-loaded pillbox with slot coupling.
- Dimensioning for  $f_{010}$  and  $f_{110}$  symmetric to  $f_{RF}$ ,  $f_{RF} = 1.3$  GHz,  $f_{010} \approx 1.1$  GHz,  $f_{110} \approx 1.5$  GHz.
- Dipole- and monopole ports, no reference cavity for intensity signal normalization and signal phase (sign).
- Q<sub>load</sub> ≈ 600 (~10 % cross-talk @300 ns bunch-to-bunch spacing).
- Minimization of the X-Y cross-talk (dimple tuning).
- Simple (cleanable) mechanics.
- EM-simulations for optimizing all dimensions/tolerances.
- Prototype testing / risk analysis to be ready for CM installation.









ilr

116




9/27/2007

**ILC GDE KOM** 



## **Cryogenic Tests**






3 cryo temperature cycles: ~30-45 min. cool-down from RT to ~80 K ~ 60 min. warm-up form 80 K to RT How many cycles do we need?!

1/10/2007 10:33 1/10/2007 10:48 1/10/2007 11:02





1/10/2007 9:36


1/10/2007 9:21 1/10/2007 9:50 1/10/2007 10:04 1/10/2007 10:19

ilc













- New, unproven component requires:
  - Clean-room procedures
  - Assembly, mounting and alignment procedures
  - Integration to quad package and cryomodule
  - Cabling (RF-cables, temperature sensors & cables)
- Risk levels:
  - FATAL: Slot window or UHV feedthrough failure damages one or more cavities. Cryomodule becomes unusable!
    - Brazing procedures, temperature cycles, leakage tests
    - Cleaning
  - Malfunction: Vacuum and cleanliness O.K. Issues with tolerances, tuning, cabling, etc. makes the BPM in parts or totally not functioning.
    - Manufacturing, tolerances
    - Shrinking, tuning





. .

8/7/07	Feedback from brazing company received. Fabrication process defined.
8/17/07	Begin fabrication of waveguide solder pieces.
8/20/07	Final waveguide specs provided to MSD. Place order for additional ceramics.
9/5/07	Final drawing for approval.
9/12/07	All drawings complete, approved and send to machine shop for fabrication.
9/13/07	Order ceramics, missing purchase parts. Address test fixture needs and tuning requirements.
10/19/07	All parts for 1 <sup>st</sup> BPM assembly machined and sent out for brazing.
11/7/07	1 <sup>st</sup> partially brazed BPM assembly delivered to lab.
11/14/07	Tests completed and send back for final brazing. Parts for two more assy's machined and send for brazing. Parts for 4 <sup>th</sup> assy ready for TD (not brazed).
10/30/07	One final, two partial BPM assemblies delivered to lab.
12/14/07	Tests on partial BPM assemblies completed, sent to final brazing.
1/5/08	2 <sup>nd</sup> and 3 <sup>rd</sup> final brazed BPM assemblies delivered to lab.
1/31/08	Three tested cavity BPM assemblies available.

:lr

IIL



- Installation in a "warm" environment for beam tests:
  - SLAC ESA
  - KEK ATF II
- "Cold" installation into the 2<sup>nd</sup> NML type 3+ cryomodule
- Scaling the design for smaller apertures?!