

Remote Handling




Vinod K. Bharadwaj SLAC October 9th, 2007



IC Positron Source Layout





October 9th, 2007 Daresbury – Positron Kick-Off Meeting




- Projected ILC running mode
 - 9 month run + 3 month shutdowns
- Target stations designed with 2 year lifetime
 - Replace target station every shutdown
 - If target fails then
 - EITHER a "hot" spare
 - OR fast replacement
- Radiation levels ~ 100 rem/hour immediately after beam shutoff
 - Remote handling needed
- Target hall deep underground
 - Vertical target extraction/replacement

Activation Calculations / DESY-Z







Helical Undulator

e ⁻ drive beam energy, GeV	150
Undulator K-value	0.92
Undulator period, cm	1.15
Undulator-target distance, m	500

	larg	jet			
	Material	Ti6Al4V			
	Thickness	0.4 X ₀			
	AM	D			
	(z = 0)	6 T			
$B_0 (z = 20 \text{ cm})$		0.5 T			
	(z = 0)	1 ÷ 24 mm			
ø	(z = 20 cm)	46 mm			

SW Structure

Aperture	46 mm			
Number of cells	11			
Ave. gradient	14.5 MeV/m			

A. Ushakov (DESY Zeuthen)

Positron Source Collaboration Meeting

ANL, 18 September 2007 3 / 15


ir

Daresbury – Positron Kick-Off Meeting





Source Activation 88 kW Photon Beam. K = 1. λ = 1 cm




Daresbury – Positron Kick-Off Meeting

Time Evolution



Time Evolution of Activity and Equivalent Dose Rate at 1 m from the Source Read KW Photon Beam. K = 1. $\lambda = 1$ cm



Nuclei	Α	T _{1/2} , h	A ₅₀₀₀ , GBq	E _γ , keV (Intensity, %)	Nuclei	Α	T _{1/2} , h	D _{+1w} , mSv/h
Sc	47	80.4	1416.4	159.4 (68.3)	Sc	46	2011.9	153.7
Ti	45	3.1	961.2	719.6 (0.15)	Sc	47	80.4	5.7
Sc	46	2011.9	544.5	1120.5 (99.99)	Sc	48	43.7	2.6
Sc	44	3.9	198.3	1157.0 (99.9)	V	48	389.7	2.1

A. Ushakov (DESY Zeuthen)

Positron Source Collaboration Meeting


ANL, 18 September 2007 13 / 15

Daresbury – Positron Kick-Off Meeting

ANL – Activation Calculations

ilr









Cu/Fe Activations



Comparison Copper and Iron





Fig.6 total dose (short life+ long life) drop trend in a week




In Target Remote Handling



Estimated 53 hour replacement time





M. Woodward, RAL



TRIUMF – ISAC FACILITY





Paper presented at PAC'99, XVIII Particle Accelerator Conference New York, March 29 -- April 2

TRI-PP-99-11 April 1999

A 500 MeV-100µA PROTON TARGET FOR THE ISAC RADIOACTIVE ION BEAM FACILITY


<u>Pierre Bricault</u>, Marik Dombsky, Paul Schmor, Guy Stanford, Ian Thorson and Jaroslav Welz TRIUMF, 4004 Wesbrook Mall, Vancouver, BC, Canada






IC Target Hall/Remote Handling








Target station deep underground Excavation costs volume dependent

Mini-hall concept



ilc Target Hall/Remote Handling



ORNL – RH Expertise



- Remote handling concept developed by RAL with input from SLAC. RAL stopped working on RH due to lack of money
- Approached ORNL to see if they could help
 - Yes, they have the expertise, probably as good as anywhere
 - Yes, they would like to help
 - Just have to arrange for funding, in the works but not final
- <u>Nuclear Science and Technology Division (Tom Burgess</u> Fuels, Isotopes, and Nuclear Materials/Remote System Group)

• Help from JPARC?


Remote Systems Group

Robotics and Remote Handling

- Specializes in development and application of advanced robotics, remote processes and handling technology for hazardous environments in:
 - nuclear fission
 - fusion

. . .

- accelerators
- radiochemical processing
- environmental restoration
- space exploration
- military defense



Chnology Div

Daresbury – Positror




Target Remote Handling Design Comments (by Tom Burgess, ORNL)

- Maximize hands-on access, minimize remote handling
 - Are utility and seal connections at top hands-on accessible?
 - What are shutdown rad levels?
- Shield rad-sensitive components to extent possible
- Assess lifetime of irradiated components (e.g., fluid seals, insulation, and other organics good to ~ 10⁸ rad TID at best)
- Identify all remote maintenance / replacement / adjustment tasks and assess viability
- Modularize target module design based on component lifetimes, maintenance requirements and capabilities
- Any rad contamination expected?








Target Remote Handling Design Comments



- Develop conceptual target design including remote handling equipment and facility support features
- Transferring target module to a cask and moving it to a hot cell on the surface may be cost effective
- Remote handling R&D, mock-ups, required will be more evident once a concept is further developed
- R&D items ?
 - Ferro-fluidic shaft seal is a potential issue – shaft speed, mag fields, radiation
 - Rotating water seal life another possible issue



Target Remote Handling Design Comments



- Pillow vacuum seal proven? Full atmosphere dp or secondary vacuum? remotely replaceable?
- What are radiation / activation levels downstream and upstream beam line and components?
- Beam line vacuum valves replaceable / necessary?

