




Report from GDE




Barry Barish
Caltech / GDE
25-Sept-07



The GDE Plan and Schedule

2005 2006 2007 2008 2009 2010






Parameters for the ILC


- E_{cm} adjustable from 200 – 500 GeV
- Luminosity $\rightarrow \int L dt = 500 \text{ fb}^{-1}$ in 4 years
- Ability to scan between 200 and 500 GeV
- Energy stability and precision below 0.1%
- Electron polarization of at least 80%
- **The machine must be upgradeable to 1 TeV**



Designing a Linear Collider




**Superconducting RF
Main Linac**





RDR ILC Schematic

- 11km SC linacs operating at 31.5 MV/m for 500 GeV
- Centralized injector
 - Circular damping rings for electrons and positrons
 - Undulator-based positron source
- Single IR with 14 mrad crossing angle
- Dual tunnel configuration for safety and availability





RDR Design Parameters

Max. Center-of-mass energy	500	GeV
Peak Luminosity	$\sim 2 \times 10^{34}$	1/cm ² s
Beam Current	9.0	mA
Repetition rate	5	Hz
Average accelerating gradient	31.5	MV/m
Beam pulse length	0.95	ms
Total Site Length	31	km
Total AC Power Consumption	~ 230	MW



RDR Design & “Value” Costs

The reference design was “frozen” as of 1-Dec-06 for the purpose of producing the RDR, including costs.

It is important to recognize this is a snapshot and the design will continue to evolve, due to results of the R&D, accelerator studies and value engineering

The value costs have already been reviewed twice

- 3 day “internal review” in Dec
- ILCSC MAC review in Jan

Σ Value = 6.62 B ILC Units

Summary

RDR “Value” Costs

Total Value Cost (FY07)

4.80 B ILC Units Shared

+

1.82 B Units Site Specific

+

14.1 K person-years

(“explicit” labor = 24.0 M person-hrs
@ 1,700 hrs/yr)

1 ILC Unit = \$ 1 (2007)




Assessment of the RDR

- **Reviews (5 major international reviews + regional)**
 - **The Design:** “The MAC applauds that considerable evolution of the design was achieved ... the performance driven baseline configuration was successfully converted into a cost conscious design.”
 - **The R&D Plan:** “The committee endorses the approach of collecting R&D items as proposed by the collaborators, categorizing them, prioritizing them, and seeking contact with funding agencies to provide guidelines for funding.
 - **International Cost Review (Orsay):** Supports the costing methodology; considered the costing conservative in that they identify opportunities for cost savings; etc.




RDR Complete

- Reference Design Report (4 volumes)




Executive
Summary



Physics
at the
ILC



Accelerator




Detectors



RDR Complete

- Companion Document (printed & website in October)



Gateway Document for broad circulation, including translations




Prepare to Propose ILC Construction

- **ILC Engineering Design**
 - We have a solid design concept in the reference design, but it is immature and needs engineering designs, value engineering, supporting R&D and industrialization.
- **GDE has been reorganized around a GDE Project Management Office to reach this goal**
 - Marc Ross, Nick Walker and Akira Yamamoto
 - Central management being given the authority to set priorities and direct the work
 - Resources for the engineering design and associated R&D appears feasible (FALC will concur on work packages)
 - Investments will be made toward Industrialization and siting
 - Anticipate LHC results in about 2010. We plan to be ready whenever the physics motivation is in place!




GDE EDR Organizational Structures





ILC Work Package Agreement





Supporting R&D & Regional Programs

- **Global R&D**


- Organized around task forces to achieve milestones linked to EDR schedule
- S0 task force - globally coordinated program to demonstrate gradient for EDR by 2009
- S2 task force – RF unit test and string tests by construction
- S3 task force – Electron Cloud tests to establish mitigation and verify one damping ring is sufficient.

- **Regional Preparations**

- Siting preparations – prepare to bid to host
- Developing regional expertise on SCRF
- Regionally based infrastructure and facilities
- Industrialization




Technically Driven Timeline






Reference Design and Plan

Producing Cavities






Cavity Shape

Obtaining Gradient





Cavity Gradient - Results



KEK single cell results:

2005 – just learning


2006 – standard recipe

2007 – add final 3 μm fresh acid EP

Note: multi-cells are harder than singles



Module Test – Results





Cost Benefit: S0 Gradient R&D


- **Optimistic scenario with final batch + tightloop**
 - **Costs 36 MILCU for the R&D**
 - **Gives highest confidence about the gradient distribution**
- **This needs to be compared to:**
 - **A reduction of the average gradient for the ILC from design of 31.5 to 28 MV/m**
 - **~ 600 MILCU**



Cryomodules



TESLA cryomodule



**4th generation
prototype ILC
cryomodule**



S2 String Tests

- **Build 1 RF unit (3 cryomodules + 1 Klystron)**
 - **What gradient spread can be handled by LLRF system?**
- **Test with and without beam loading.**
 - **For heating due to high frequency high order modes**
 - **Amplitude and phase stability.**
 - **Static and dynamic heat loads.**
- **Purpose is to test**
 - **Reliability; Dark current; Degradation or other weaknesses**
- **Second phase string test needed before construction to verify modules for the ILC.**



S2 String Tests

- **Risk with no string tests → Build ~1.5 BILCU of cryomodules, then discover a design flaw.**
 - **Schedule/Cost risk -- fixing them could take years and cost > 20% of the original cost.**
 - **Categorize as medium risk (25%) → Risk*Cost ~75 MILCU, plus schedule loss (years).**
 - **Risk would be higher 50-100% if not for the Tesla Test Facility.**
- **The planned string tests (One RF Unit) ~ \$50 MILCU.**



The Main Linac

Subdivision	Length (m)	Number
Cavities (9 cells + ends)	1.326	14,560
Cryomodule (9 cavities or 8 cavities + quad)	12.652	1,680
RF unit (3 cryomodules)	37.956	560
Cryo-string of 4 RF units (3 RF units)	154.3 (116.4)	71 (6)
Cryogenic unit with 10 to 16 strings	1,546 to 2,472	10
Electron (positron) linac	10,917 (10,770)	1 (1)

- **Developing capability to construct in all three regions**
 - **Facilities developed regionally**
 - **Industrialization; assembly; testing**




Electron Cloud Mitigation

- **Low Emittance Damping Ring**
 - Ensure the e- cloud won't blow up the e+ beam emittance.
 - Baseline -- Two positron damping rings – alternate bunches.
 - RDR – Change to one damping ring; move to central injectors; share tunnel
 - Assumed mitigation of electron cloud successful
- **R&D Program**
 - Simulations (cheap and encouraged making change)
 - Test vacuum pipe coatings, grooved chambers, and clearing electrodes effect on ecloud buildup
 - Do above in ILC style wigglers with low emittance beam to minimize the extrapolation to the ILC.



E Cloud – Simulation Results



SLAC




Cost Benefit: S3 Electron Cloud R&D

- **R&D for Electron Cloud**
 - High risk (~50%) that we must build a second e+ damping ring at a cost of 200 MILCU. (Cost risk = 100 MILCU)
 - KEK-B and/or CESR R&D test program will involve dedicated use of the whole ring. The scale of R&D cost ~ 20-30 MILCU.



Main Linac Double Tunnel



- Three RF/cable penetrations every rf unit
- Safety crossovers every 500 m
- 34 kV power distribution



Conventional Facilities

**72.5 km tunnels ~ 100-150 meters
underground**


13 major shafts \geq 9 meter diameter

**443 K cu. m. underground excavation:
caverns, alcoves, halls**


**92 surface “buildings”, 52.7 K sq. meters
= 567 K sq-ft total**



Reference Design and Plan




Making Positrons



6km
Damping
Ring




10MW
Klystrons



Beam Delivery and Interaction Point




Technically Driven Timeline








Civil Construction Timeline





On-surface Detector Assembly

CMS approach




CMS assembly approach:

- Assembled on the surface in parallel with underground work
- Allows pre-commissioning before lowering
- Lowering using dedicated heavy lifting equipment
- Potential for big time saving
- Reduces size of required underground hall



Technically Driven Timeline



Siting Plan being Developed

Site Prep


Site Select

All regions require ~ 5 yrs



Preconstruction Plan: Fermilab

Central Area fits inside the Fermilab boundary




~ Boundary of Fermilab



Site Characterization of the Central Area can be done



Technically Driven Timeline




Siting Plan being Developed

Site Prep

Site Select

All regions ~ 5 yrs

R & D -- Industrialization




Construction Schedule

Cryomodule Production

RF System Tests




Technically Driven Timeline







Detector Concepts



LDC




SiD



GLD

© Rev. Henri



4th



Detector Performance Goals

- ILC detector performance requirements and comparison to the LHC detectors:

- Inner vertex layer ~ 3-6 times closer to IP
- Vertex pixel size ~ 30 times smaller
- Vertex detector layer ~ 30 times thinner

Impact param resolution $\Delta d = 5 [\mu\text{m}] \oplus 10 [\mu\text{m}] / (p[\text{GeV}] \sin 3/2\theta)$

- Material in the tracker ~ 30 times less
- Track momentum resolution ~ 10 times better

Momentum resolution $\Delta p / p^2 = 5 \times 10^{-5} [\text{GeV}^{-1}]$ central region
 $\Delta p / p^2 = 3 \times 10^{-5} [\text{GeV}^{-1}]$ forward region

- Granularity of EM calorimeter ~ 200 times better

Jet energy resolution $\Delta E_{\text{jet}} / E_{\text{jet}} = 0.3 / \sqrt{E_{\text{jet}}}$

Forward Hermeticity down to $\theta = 5-10 [\text{mrad}]$




Concept: one IR - two detectors

may be accessible during run

The concept is evolving and details being worked out


accessible during run

Platform for electronic and services (~10*8*8m). Shielded (~0.5m of concrete) from five sides. Moves with detector. Also provide vibration isolation.





Technically Driven Timeline





Conclusions

- The ILC design is proceeding toward an engineering design (EDR) in 2010.
 - Be ready to propose construction when LHC results justify!
- R&D program is being globally coordinated to determine gradient, electron cloud, industrialization, mass production.
 - Overall priorities are being set for risk reduction
 - There are regional programs to develop SCRF expertise and prepare to bid to host
- Detector R&D/design also very important to be able to fully exploit the ILC (e.g. spatial & energy resolution)
 - Appointment of Research Director - S Yamada for better coordination, better regional balance
 - LOIs in one year