

# Scintillator-ECAL beam tests

*Satoru Uozumi, Kobe University  
for Daniel Jeans, Miho Nishiyama  
and all the ScECAL group*

1. DESY Beam Test (Mar 2007) ... First test of ScECAL
2. KEK Beam Test (Nov 2007) ... To establish extruded scintillator strip
3. FNAL Beam Test (Sep 2008) ... Final test with larger prototype and various type & energy of beams



# strip scintillator calorimeter

sampling calorimeter

active material: scintillator

absorber: W/Fe/Pb

designed for PFA: fine segmentation

scintillator strips  $\sim 1 \times 4 \text{ cm}^2$


orthogonal layers

each strip read out by MPPC  
photon counting device




built and tested small prototype

first test for scintillator + MPPC


check suitability for ILC ECAL





exposed to 1-6 GeV  $e^+$  beam  
at DESY 03/07



# Detector setup, scintillator types



MPPCs  
(1600 pixels)



3 types of scintillator strips:

Kuraray (Megastrip)

- WLSF readout
- direct readout (simpler)

KNU/Korea (separate strips)

- extruded scintillator (**inexpensive**)
- WLSF readout

CALICE readout electronics (LAL-Orsay) borrowed from DESY CALICE A-HCAL group






produced 3 half-modules (13 layers each)  
with different scintillator types

tested 3 configurations

Kuraray (fibre) + Kuraray (direct)



Kuraray (direct) + Kuraray (fibre)

Extruded (fibre) + Kuraray (fibre)





Compare performance of 3 configurations

# Beam line instrumentation



# MIP calibration


Strip being calibrated



Trigger only

Red strips have  
non-pedestal signal

Blue strips have  
only pedestal signal




fit to Gaussian-convoluted Landau

# MIP response temperature dependence

MPPC gain changes with temperature

example: 18 strips in one layer



18.5 20.5  
temperature

consistent for all channels  
apply common correction



**MIP response uniformity:**  
detailed scan across single strip


extruded strips show significant  
non-uniformity

Response for MIP




MPPC





Kuraray fibre





Extruded fibre




Kuraray direct




# light cross-talk between adjacent strips



Mega-strip structure: strips not perfectly isolated




look at signal when MIP hits adjacent strips




# light xtalk: different configurations


CALICE ScECAL preliminary



CALICE ScECAL preliminary



CALICE ScECAL preliminary



much less light cross-talk  
in extruded strips




runs with tungsten plates

6 GeV e<sup>+</sup>, center injection

x projection →

y projection →



range of e<sup>+</sup> beam momentum: 1-→6 GeV/c


scanned front face of detector

apply calibration constants  
temperature correction  
cross-talk correction


look at different detector regions

quarter regions – most uniform

central region – least uniform, least leakage





### CALICE ScECAL preliminary



energy response

reconstruct total energy  
deposited in calorimeter





linear response

no strong effect of  
MPPC saturation  
has been seen



# Energy resolution of 3 configurations



resolution of configurations similar in quarter regions

at centre of detector, extruded+fibre much worse:  
strip uniformity important in this region

# Conclusion of the DESY Beam Test

Analysis of DESY testbeam data in good shape

In uniform regions, detector works well  
sufficient energy resolution for ILC ECAL ( $\sigma/E \sim 14\%/ \sqrt{E} \oplus 2\%$ )

Non-uniformity and small light yield of extruded strips significantly degrades performance.

## In progress...

Some further data analysis (MPPC saturation correction...)

Detailed simulation


Proceed to publication

# At the last DESY Beam Test...

Extruded scintillator strips show


- Low light yield
- Large non-uniformity

Response  
for MIP




Uniformity of 3 different types of scintillators


**Kuraray**



**Kuraray**






**Extruded**



Beam position (mm)

Signal (ADC counts)

# Why the extruded scintillator showed such low light yield and non-uniformity?



fiber – MPPC bad matching

- Some extruded scintillator strips have a bigger hole.
- Sometimes the hole isn't correctly centered.
- Some extruded scintillator strips have leakage points.

# KEK Beam Test

(Nov-2007 at KEK Fuji electron beamline)



- Extruded scintillator R&D is very important for reduction of scintillator production cost.
- Need to perform deeper study of improved extruded scintillator strips by 2D scanning with MIPs.
- Evaluate light yield, position dependence, strip-by-strip variation, and compare various extruded strips with Kuraray strips.





# KEK Fuji Beam-Line


- Electron beam-line from bremsstrahlung photons of KEKB
- Beam spot size:  $\sim 3 \text{ cm} \times 4 \text{ cm}$
- Beam energy : 1-4 GeV
- Rate: 15Hz @ 3 GeV



# Setup

Beam  
 $e^-$

Setup of side view




## Semiconductor Tracker (ATLAS TGC)

$12\text{cm} \times 6\text{cm}$

Resolution

vertical :  $23\mu\text{m}$

horizontal:  $580\mu\text{m}$



Trigger counters


Scintillator  
Fiber Tracker

scintillator


Movable  
stage

Scintillator  
strips

Veto counter




# Scintillator Assembly




# Scintillator Strips

- 8 layers with different types of strips
- 4 strips per one layer were read out.



type	Method	Read-out	Cover	Thickness (mm)	
A1	Extruded	Fiber	TiO <sub>2</sub>	3	No fiber
A2					good matching
B1			big fiber hole		
B2			matched hole		
C		Direct	TiO <sub>2</sub>		
D	Kuraray	Direct	Reflector	2	
E				3	
F		Fiber		reference	





# Extruded scintillator strip with a fiber hole

(A,B)

Type : A

covered with TiO<sub>2</sub>

**A1 : fiber - MPPC bad matching**



**A2 : fiber - MPPC good matching**

Type : B

covered with KIMOTO reflector film

**B1 : bigger hole**


**B2 : matched hole**






# Response for MIP

All collected events  
MIP events



# Uniformity




# Conclusion of the KEK Beam Test

- Result shows acceptable performance of the extruded scintillator strips.
  - Type of reflector and position matching between fiber and MPPC are very important.
  - Extruded strip without fiber is not useful, since attenuation length is so short.
- More detailed analysis will follow.
  - Comparison of absolute light yield
  - Bias voltage dependence
- Feedbacks are provided to KNU colleagues.

Quality of the extruded scintillator will be improved for FNAL BT.


# The FNAL beam test in Sep 2008

- Establish the Scintillator-strip ECAL technology
  - Test linearity of the ScECAL with high energy beam.
  - Evaluate all the necessary performances
    - using various beams ( $\pi, K, e, \mu, \dots$ ) with wider energy range
- Combined test with the Analog HCAL
- Test  $\pi^0 \rightarrow 2\gamma$  reconstruction (hopefully)
- Measure hadron shower to test simulation model



- The 2<sup>nd</sup> prototype will be 4 times larger than the DESY BT module.  
(20 x 20 cm, ~30 layers)
- Fully adopt the extruded scintillators.
- Expect > 2000 readout channels.

# Schedule toward the FNAL BT





# Conclusion


- Scintillator-ECAL R&D is ongoing in good shape.
- The DESY beam test proves performance of ScECAL and gave lots of experiences to us.


Analysis of the data is in almost a final phase.

- The result of KEK beam test told us how to improve performance of extruded scintillator strips.
- At the FNAL beam test, various tests will be done to technically establish the ScECAL.

# Backups


# Trigger & Veto counter event selection






# Energy resolution in different detector regions (fibre+direct, with absorber)

**fibre + direct: energy resolution**







**fibre + direct: 3 GeV positrons**



clear evidence of lateral shower leakage in outer two regions


# energy per strip @ 6 GeV




# longitudinal shower profiles

quite smooth, a couple of smallish discontinuities  
reason still under investigation

CALICE ScECAL preliminary



CALICE ScECAL preliminary





# Energy resolution

quarter regions

central region

stoch. term(%) const term(%)

stoch. term(%) const term(%)

fibre+direct:

13.98 +- 0.07

1.96 +- 0.12

13.39 +- 0.05

2.57 +- 0.07

direct+fibre:

13.83 +- 0.07

2.58 +- 0.09

13.70 +- 0.06

3.39 +- 0.05

extruded+fibre:

14.61 +- 0.08

2.35 +- 0.12

14.52 +- 0.09

7.26 +- 0.05

contribution  
from shower leakage





non-uniformity

# Tracking detector alignment





determine drift velocity and relative positions of 4 drift chambers  
each chamber measures x,y position

chamber 0 1 2 3

x





y



before  
(after)  
alignment

hit residual/mm


# Energy response uniformity, direct+fibres, 3 GeV



scanned 1/3 detector

can alternate orientation to minimise this effect

# extruded+fibre @ 3 GeV: energy response vs. position




2-3 times more variation that  
direct+fibre configuration

extruded strips are less uniform

# Simulation studies

simulation shows 4% lateral energy leakage, 1% longitudinal leakage  
(central beam injection)



simulate a larger detector  
(2x larger in each direction)

resolution of 1<sup>st</sup> configuration  
(real data)

simulation of our detector  
26 layers x 9x9cm<sup>2</sup>


simulation of larger detector  
52 layers x 18x18 cm<sup>2</sup>:  
no constant term!

shower leakage causes constant  
term of around 2.6%

measure xtalk across each strip boundary

correction of cross-talk

in each layer, define matrix with measured xtalk probabilities ( $\sim 10\%$ )



use this matrix to unfold the cross-talk



# Comparison of Kuraray scintillator strips and KNU extruded

## Kuraray


- Casted and machined
- High accuracy for the hole size and position
- Expensive

## KNU Extruded

- Extrusion
- Simultaneously the fiber hole is made and scintillator strip.
- Can be covered with  $\text{TiO}_2$  at the same time.
- Cheap
- Low accuracy for the fiber hole size and the position

# Extruder

The pictures were taken  
at Misung Chemical Company,  
Korea.



# Response for MIP


## Variation of strip by strip

Extruded scintillator strip + reflector film  
good matching

All collected events  
MIP events



Number of events (log scale)



Signal (ADC counts)


These plots show the variation of strip by strip is big.

# Uniformity

## Variation of strip by strip

Extruded scintillator strip + reflector film  
good matching

Signal (ADC counts)



Beam position (mm)

These plots show the uniformity of these strips is not so big.  
However light yields are not same.