

Detail plan of S1-Global

H. Hayano (KEK), 11172008

Proposal of S1-Global mission




Mission of the S1-global

The mission of the S1-Global is to facilitate the international collaborative work on the production and operation of cryomodules in the framework of ILC-GDE and to aim at operating at least one cryomodule with an average accelerating gradient of 31.5MV/m. Specific goals of the S1-global include the following:

- (1) **To advance the implementation of the 'plug-compatibility concept'** for the cavity packages, by installing up to 8 cavities from laboratories across the world into a common module, and by operating them with pulsed RF power at a cryogenic temperature of 2K.
- (2) **To examine the engineering designs of cavity packages** from participating parties by assembling them into a common module and by following through the alignment procedures.
- (3) **To demonstrate that the specifications on the heat loads** for the cavities and the cryomodules can be met as per RDR.
- (4) **To conduct comparative studies of performance of cavities** from the participating parties, in particular, in the area of Lorentz detuning and its compensation in a common setting.
- (5) **To attempt to attain an average accelerating gradient of 31.5MV/m** in a pulsed RF operation at 5 Hz with 1 ms flat-top length, 0.07% rms amplitude variation and 0.35 degree rms phase variation.

S1-Global cryomodule


General Design of Cryomodules




- Module C: 2 FNAL cavities and 2 DESY cavities, Module A: 4 KEK Tesla-like cavities
- The total length=14778mm
 - Module-C = 5800 mm, Module-A = 5515 mm
 - Vacuum bellows to 2K cold box = 795 + 100 mm, Vacuum bellows between modules = 932 + 100 mm
 - Connection to 2K cold box = 905 + 28 mm, End cap = 572 + 28 mm

S1-Global cryomodule

Cryomodule C (INFN design and fabrication)



two VTO for 4 cavities
from SLAC? (Chris Adolphsen)



S1-Global experiment preparation

1 module assembly

module C:INFN cryostat + FNAL cavities + DESY cavities

module A:KEK cryostat + KEK cavities

installation of coupler cold window, connection of cavities & bellows & gate valves, cavity rotation alignment, pumping down, hung on GRP, alignment of cavities, He pipes connection, sensors connection, super-insulator shield installation, slide into cryostat.

2 installation in tunnel

connection of modules, cryogenics, vacuum port with pumps, wire stretch of WPM, cryostat alignment, coupler warm window, wave-guide connection.

3 coupler RF process at room temperature

RF process from narrow pulse to full pulse

4 cool down to 2K

5 coupler + cavity RF process at 2K

6 cryomodule performance measurement


Assembly of cavities in Clean room




dressed cavity as received



input coupler (cold window) installation



**after installation
(jigs to mount support pillar of rail system)**



**gate valve and beam pipe bellows
installation**


Assembly of cavities into cryomodule (1)



4 cavities connection



taking out from clean room



tuner, WPM installation



alignment



hanging up to GRP



He supply pipe welding

Assembly of cavities into cryomodule (2)



**Temp sensor, 5K shield,
thermal anchor installation**



wrap Super-Insulator



hang cold-mass



pull down onto slider



dismount support post



slide into cryostat

Cryomodule installation in Tunnel



crane down into tunnel



module connection



coupler warm window installation





ready for coupler RF process





cryogenics connection

Examples of cool down, warm up



cryogenics operation plan (weekly)



weekday, day time cryogenics operation: 8:30 – 19:00

experiment: 13:00 – 19:00 (6 hours)

Experiment time assignment

Assume June 1, 2010 start;

room temp. coupler process: 4 weeks (two cavity/week)

cool down process: ~1 week

2K coupler & cavity process: 4 weeks (two cavity/week)

regular maintenance and inspection of cryogenics: 4 weeks (August)

re-cool down process: ~1 week

September 8, 2010 experiment start until December 24, 2010;

2K experiment: 16 weeks (16 weeks x 4 days x 6 hours = 384 hours)

**48 hours / cavity, including heat load, HLRF, LLRF,
vector sum operation**

It is very tight, need efficient, prioritized exp. program


Experiment Item candidates



- (1) Gradient reach (vector sum)**
- (2) amplitude & phase control (vector sum)**
- (3) Heat load measurements**
- (4) Each Cavity fundamentals(Q , E_{acc} , f_0 , tuner, etc..)**
- (5) Lorentz detuning (each cavity)**
- (6) Piezo compensation (each cavity)**
- (7) Mechanical vibration meas. (each cavity)**
- (8) power distribution study etc.**

Examples of measurement


Achieved Eacc,max



RF process of cavity and coupler

Lorentz detuning measurement


LD compensation study




$K = -0.5 \text{ Hz}/(\text{MV/m})^2$
Flat-top Lorentz detuning

Compensation by Piezo (1) ; higher Tension


Eacc = 18. MV/m
Piezo / OFF



Eacc = 18. MV/m
Piezo / ON
300 Hz, 500 V, - 700 μsec



S1 Global overall Plan



End of slides