

Marx Modulator Status Report

C. Burkhart
SLAC Power Conversion Dept.
for the Marx Team
April 24. 2008



Presentation Overview

- Marx Development Program
- P1-Prototype Development Status
- Vernier Regulator Development Status
- Cost Estimate Review


Marx Development Program

- Prototype (P1) Modulator
 - Demonstrate efficacy of Marx topology for ILC Klystron modulator application (thru FY08-Q3)
 - Power 10 MW klystron for ESB life/performance testing (start FY08-Q4)
- 2nd Generation Prototype (P2) (FY09 & 10)
 - Modify to conform to revised tunnel design
 - Improve manufacturability
 - Improve reliability/availability

P1-Prototype Status

- Operated at Full Voltage (120 kV), Current (140 A) and Pulse Length (1.6 ms) with Coarse Flattening
 - 16 Cell at 11 kV, 11 prompt and 5 delayed
 - Load variations $\rightarrow >150$ A
 - Vernier Regulator for 0.5% regulation under development
- Operated at Near Full Power (135 kW)
 - Maximum of ≥ 100 kW, limited by 11 kV source and load
- Operated at Full PRF (5 Hz)
- Operated for Several Days without Intervention
- BUT Have Not Achieved All Simultaneously

Marx Output with Coarse Flattening



Voltage: 20 kV/div

Current: 50 A/div

Energy: 4.5 kJ/div




P1-Prototype Development Challenges

- (Too) High Voltage Stress on IGBTs, Scale Back to Improve Robustness to a Suitable Level of this Application
 - $V_{OP} / V_{(BR)CES} \sim 0.67$
 - Small/No snubbers or MOVs
 - Over Voltage protection active: device turn-on delay
- Extended Operation to Evaluate “Subtle” Effects
- Fault Testing: Simulate Klystron Arc
- Prime Power/Load Limitations/Failures
- Control System Upgrades: EPICs Support
- Packaging for ESB Operation
- Vernier Regulator

Marx Water Load & Charger



Marx Waveforms & Control Screen




April 24, 2008

Marx Status Update

R. Larsen 8

ESB Enclosure




Vernier Regulator

- 16-Cell “Mini-Marx”, 1.2 kV Cells
- Multiple Erections of Marx to Generate a Series of Voltage “Ramps” to Offset Droop (Sawtooth) in Coarse Pulse Flattening
- 2nd Generation Cells Successfully Operated, 5-cell Stack
- 3rd Generation Cell Design Complete
- Motherboard/Aux Board Designs Nearly Complete

5-Cell Vernier Test Set-up



5-cell Vernier Output




Cost Estimate Revisited

- Bulk of original components, costs remain unchanged since model shown at Snowmass '05.
 - Same architecture of cells, housing
 - Major cost drivers (IGBT's, capacitors) ~same
- 2008 adjustments
 - Charger Supply
 - Earlier estimate assumed bulk regulator at 12 kV built onto single cell; did not include distribution or phase load balancing
 - New estimate made for 6-Pack high availability power distribution (R. Cassel) added \$60K per modulator
 - Cell voltage reduction
 - Originally designed to run at 12 kV per cell, insufficient margin for protection
 - Now operating at 11 kV/cell, which means should add ~8% to cost for same level of cell redundancy
 - Results shown in next slide.

Snowmass '05 Updated

■ Unit 1 (K\$) ■ Prod LC1 (K\$) ■ Prod LC2 (K\$)



Marx Cost Summary

Including 8-Pack Charger & AC Distribution, Extra Cell

Rev. 042408

Item	Cost Basis	M&S	Labor	Total k\$/\$	Profit 15%	Total Cost
MARX Modulator						
<i>Main Unit</i>	M&S Quotes, Labor Eng. Estimate			(*1.08)		
Marx Cells		131.0	10.0			
Modular Enclosures		8.4				
Overall Enclosure		2.5				
Cooling Main Unit		4.0				
Internal Wire/cable		1.6				
Diagnostic Cntrlrs		6.0				
PLC Controls		2.0				
Cntrl Sys Interface		0.5				
Other labor			15.0			
Subtotal Main Unit		156.0				
Protection Units		1.5				
Charging Supply	Cassel HA System w/ distribution	67.2				
Miscellaneous		10.9	5.0			
Subtotal, Misc		79.6				
Subtotal Prod.Unit 1		235.6	30.0			
Total Cost Full Unit 1 (k\$)				286.8	43.0	329.9
Avg Cost 572 Units ¹	Conservative LC (95% M&S, 95% Labor)			248.8	37.3	286.1
¹ Includes 20% ED&I in LC	Aggressive LC (90% M&S, 85% Labor)			174.4	26.2	200.6

Marx Program Summary

- P1-Prototype Nearing Completion (FY08-Q3)
- Integrate P1 into L-band Facility (FY08-Q4)
Initiate Life Testing of Marx and MBK
- Complete Vernier Regulator and Integrate into P1 (FY08-Q3/4)
- Nth Unit Cost Re-examined: \$200k - 290k,
~30% Increase from Snowmass '05 Estimate
- P2-Prototype Development FY09-10

The Marx Team

Past, Present, (Future?)

- D. Anderson
- P. Bellomo
- P. Blum
- C. Brooksby (LLNL)
- C. Burkhardt
- R. Cassel
- R. Chestnut
- E. Cook (LLNL)
- A. de Lira
- R. Larsen
- G. Leyh
- D. Moreno
- M. Nguyen
- J. Olsen
- P. Shen
- A. Vicerat