



# GDE Program for the ILC Technical Design Phase

Marc Ross for:  
Akira Yamamoto, Nick Walker  
GDE Project Managers

Presentation to the 'ILCDR08' Workshop, Cornell

Risk Reduction (Cost, schedule, technical)  
and  
Cost Reduction through R&D and design work



## GDE TDP Overall Goal or Mission:

- **Develop an 'ILC Project Proposal' by mid-2012**
  - A complete and updated technical description
  - Results from critical R&D programs
  - One or more models for a Project Implementation Plan that include in-kind contribution schemes
  - An updated and robust VALUE estimate and construction schedule



## This talk:

- **Our purpose**
- **Goals for:**
  - Accelerator Systems
  - CF / S
  - Project Implementation Plan
- **Schedule**
- **Organization**
- **Reviews and Meetings**
- **2008 R & D highlights - SCRF**



## TD Phases

### **Phase 1 (July 2010)**

- **Critical R & D**
- **Evaluate the potential for cost reduction**
- **Re-baseline to prepare for technical design**

### **Phase 2 (late 2012)**

- **consolidate the new baseline reference design**
- **detailed technical design studies**
- **updated VALUE estimate and construction schedule.**
- **critical R&D and technology demonstration milestones will be concluded.**
- **detailed development of the Project Implementation Plan.**



# RDR baseline and Risk

- **In most cases the RDR baseline choices were forward-looking and dependent on successful R&D during the TDP**
  - (remember Snowmass questions and RDR ‘white papers’?)
  - EC, gradient, beam delivery precision control etc demonstrations are expected during TDP
- **In some cases, RDR baseline choices were more conservative and should be revisited during TDP1**
  - single tunnel, Marx modulator etc
  - ‘alternate concepts’ → which, if promising, may have significant impact on design, risk, cost and R&D
- **(All choices are to be revisited as part of the TDP1 re-baselining process)**
  - focus on those connected with ongoing R&D
- **Our goal is to define the R&D effort to achieve greatest impact on risk-reduction**
  - guided by RDR; baseline and Value estimate



# ILC DR08 Workshop

## Themes:

- **CesrTA Kick-off and Low Emittance tuning:**
  - EC Growth and Instability Studies
  - Development of low emittance tuning techniques (target  $\varepsilon_y < 20\text{pm}$ )
  - Development of x-ray beam size monitor to characterize ultra low emittance beams (1-D camera array)
- **Technical R & D and design effort**
  - aimed at risk reduction (technical) and cost reduction (design)
  - Assess state-of-the-art EC modeling, mitigation, understanding
- **(previous DR meeting at KEK 12.2007)**



# Accelerator Test Facilities

- **CesrTA - Control and mitigation of electron cloud effects**
  - Global collaboration led by Cornell:
    - KEK: support for wiggler vacuum chamber, implementation of beam size monitors
    - UK (Cockroft): coordination and simulation
    - CERN: integration with proton accelerator electron cloud R & D
  - Strategy → action on a broad front
    - Test: vacuum chamber coatings, design, instrumentation and surface modeling
    - Test: beam dynamics simulations
  
- **ATF / ATF2 – control and monitoring of precision beams**
  - Global Collaboration led by KEK and SLAC:
    - Based loosely on the ATF collaboration MOU
    - Strong participation from all regions; a rough model of an in-kind ILC-like project
  - Strategy:
    - Test demagnification optics, tuning process and instrumentation with the ultra-low emittance ATF beam
      - (2 pm-rad vertical normalized emittance)



# Test Facility Milestones

Test Facility	Deliverable	Date
<i>Optics and stabilisation demonstrations:</i>		
ATF	Generation of 1 pm-rad low emittance beam	2009
ATF-2	Demonstration of compact Final Focus optics (design demagnification, resulting in a nominal 35 nm beam size at focal point).	2010
	Demonstration of prototype SC and PM final doublet magnets	2012
	Stabilisation of 35 nm beam over various time scales.	2012
<i>Linac high-gradient operation and system demonstrations:</i>		
TTF/FLASH	Full 9 mA, 1 GeV, high-repetition rate operation	2009
STF & ILCTA-NML	Cavity-string test within one cryomodule (S1 and S1-global)	2010
	Cryomodule-string test with one RF Unit with beam (S2)	2012
<i>Electron cloud mitigation studies:</i>		
CESR-TA	Re-configuration (re-build) of CESR as low-emittance e-cloud test facility. First measurements of e-cloud build-up using instrumented sections in dipoles and drifts sections (large emittance).	2008
	Achieve lower emittance beams. Measurements of e-cloud build up in wiggler chambers.	2009
	Characterisation of e-cloud build-up and instability thresholds as a function of low vertical emittance ( $\leq 20$ pm)	2010





## GDE CF/S Workshop (Dubna June 2008)

- The RDR represents a consensus design, which reconciled inputs from our constituent accelerator designers / engineers
- We believe a more cost-effective design, based on the RDR, is possible and mandated by a need to 'optimize' the ILC design
  - sacrifices may be necessary - Value Engineering


### PM Assumptions:

- There exists a 'minimal design' that satisfies all scope requirements and facilitates cost comparisons for 'optional' features
  - Not a trivial concept due to design optimization and consolidation already in RDR
- The shallow machine is more cost-effective because of reduced underground volume – (XFEL, Dubna site...) but:
  - Effective reliability strategy for single tunnel layout NOT done for RDR – due to time / resource limitations
- The process can be done within the 'consensus – building' context established for RDR
  - Our community must buy-in and participate

# Integrated Central Campus Proposals.

- Dubna group C/D report
- (A) 6.4 km damping rings rotated by 90 degrees from 'standard' orientation. DR are located in the same horizontal plane as the BDS but displaced laterally by ~200 m. It is assumed this is sufficient to be clear of IR facilities. In this configuration, injection and extraction from both rings is in the same long straight section.
- (B) BDS layout in RDR shows horizontal offset of ~2 m in straight tunnel and location of (high powered) tune-up dump. Total length of 2×2.2 km is compatible with (D) through (I), i.e. injector systems sharing the same tunnel. Energy upgrade to 1 TeV does not require injector systems to be moved.
- (C) Shorter ('minimum') 500 GeV version of the BDS showing offset and beam dump line location. On the e- linac (e+ injector) side this does not shorten the distance to the end of the linac as the e+ injector beamline components requires the same length as in (B). On the e+ linac, e- injector side the linac could be moved closer to the IR by 600 m. Upgrading to 1TeV is more complex than in (B)
- (D) The iron walls in the BDS should be downstream of the injector systems and part of the PPS zone shielding that allows their operation while there is access to the IR. The booster to DR transport is shown as a 200 m long S shape. This contains the energy compressors and spin rotators and RTML systems, some older studies showed possible lattices for this geometry.
- (E) 5 GeV SC linacs on both sides.
- (F) ~400 or 500 MeV pre-injectors for e+ and full injector for e-.
- (G) e+ Target and capture systems. Shared with possible single or few bunch 'auxiliary source'. Nothing on other side.
- (H) Drift for gamma beam and dogleg for e- main beam. The dogleg should match up with later dogleg in the BDS. This is the region where one might insert a compact S-band e-injector for the auxiliary source (KAS replacement).
- (I) Location of 100 m long undulator at the end of the e- .

# Integrated Central Campus Proposals.





# Minimum Machine Definition

- **Physics scope (WWS document)**
  - 200-500 GeV centre-of-mass energy range
  - $2 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$
  - polarized electrons
- **Identify cost-driving requirements and criteria**
  - Push back on them to acceptable minimum
  - CFS will be primary target
    - Underground volume and construction
    - Process cooling water
- **Definition document due late 2008**
  - Led by Project Manager Nick Walker (DESY) and ILC Integration Scientist Ewan Paterson (SLAC)



## Minimum Machine Design Plan

- This document will represent one of the primary deliverables for TD Phase 1 in 2008, as described in the TD Phase R&D Plan Release 2.
- The specification document will form the basis of the 'minimum machine studies' in 2009, which are intended to provide quantitative input into the planned review and re-baseline of the machine at the end of TD Phase 1.



# Minimum Machine Design

1. General layout considerations (“Integration”) whereby the goal is to reduce overall underground volume by more integrated use of tunnels, shafts and vaults.
2. Technical component specifications, for example water cooling parameters which should be less conservatively defined for individual sub-systems.
3. Accelerator performance specifications, for example reducing the number of individually powered magnets (“stringing”), relaxing alignment stability requirements and environmental specifications (temperature stability).



# CF / S Strategy

- **RDR: Deep Rock, twin tunnel configuration**
  - strong similarities → each region developed the same design
- **Value Engineering:**
  - understand the cost drivers; review and evaluate the technical criteria that define them
    - underground volume
    - tunnel dimensions; second tunnel
    - stability and etc

## Goal:

- Devise practical, ‘minimum’, technical criteria
- Strategy (must be site-independent):
  - **Develop contrasting machine configurations**
    - *for example: shallow site (Dubna); single tunnel (XFEL), etc*
- Implement comparison and analysis process between these and the RDR baseline
- Update site specifications; recommend further technical development and R & D

– **for example: Use of long HV cables to power linac RF sources**



# Project Implementation Plan (PIP)

- **The PIP will be developed in several stages during the TD Phases:**
  - Review existing examples of PIPs and develop and define the elements of the ILC PIP (2009)
  - Begin to develop the models for globally distributed mass-production of the SCRF (and other where suitable) components as part of an ‘in-kind’ project implementation scenario (2010)
  - Develop cost models for the SCRF based on the above, which will provide the framework for the SCRF technical groups when estimating their costs during TD Phase 2 (2012)
  - Develop the other identified elements of the PIP (2012)
- **The PIP will be published as part of the primary deliverables of the TD Phase in 2012.**
  - May be the most-read part of the TD report





# Project Implementation

- **The suggestion of ‘how’ the work should be done**
  - (RDR / TDR rebaseline describes what and how much)
  - may include: Governance, CF / S siting process, and procurement models
- **How will the plan be linked to present activities?**
  - R&D must promote workable project plans
    - example: Plug-compatibility of cryomodule components
  - CF / S design work should support development of cost-effective designs in various site configurations to strongly encourage all interested parties
    - example activity: adapt single tunnel linac design to deep and shallow sites → without accepting large performance or cost penalty
    - (now planning – of course we cannot prepare for \*any\* and all possible sites in parallel)
  - should consider seam-less transition models following TDP completion and proposal submission
    - example: updated Value estimate format must smoothly re-map onto a real project plan



## Connection between Plan and updated Value estimate

- **the Plan includes a schedule**
- **It also includes labor/procurement and management models**
- **the Value estimate will depend on these models**
- **Plan will be developed in concert with oversight groups**
  - funding agencies (FALC)
  - ICFA (ILCSC)
  - institutional managers

# TD Phase 1 Schedule

Published in:  
*ILC Research and  
Development Plan  
for the Technical Design  
Phase*

Release 2, June 2008  
(next release 6 months)

Near term effort on  
these activities



Value engineering



Value engineering



Global Project Plan



High Gradient



Cryomodule test



Systems Test



Electron Cloud



Precision beam control



		calendar year		
		2008	2009	2010
<b>Tech. Design Phase I</b>				
Siting				
	Shallow site option impact studies			
	Definition of uniform site specs.			
Collider Design Work				
	Definition of minimum machine			
	Minimum machine & cost-reduction studies			
	Review TDP-II baseline			
	<b>Publish TDP-I interim report</b>			★
Project Implementation Plan				
	Review and define elements of PIP			
	Develop mass-production scenarios (models)			
	Develop detailed cost models			
SCRF Critical R&D				
	CM Plug compatibility interface specifications			
	S0 50% yield at 35 MV/m			
	Re-evaluate choice of baseline gradient			
	S1-Global (31.5MV/m cryomodule @ KEK)			
	S2 RF unit test at KEK			
	S1 demonstration (FNAL)			
	S2 RF unit at FNAL			
	9mA full-beam loading at TTF/FLASH (DESY)			
	Demonstration of Marx modulator			
	Demonstration of cost-reduced RF distribution			
Other critical R&D				
	DR CsrTA program (electron-cloud)			
	DR fast-kicker demonstration			
	BDS ATF-2 demagnification demonstration			
	Electron source cathode charge limit demonstration			
	Positron source undulator prototype			
	Positron source capture device feasibility studies			
	RTML (bunch compressor) phase stability demo			



## TDP Organization supports this goal

- **Technical Area Groups to communicate, coordinate and monitor global R&D**
  - R&D emphasis strengthened following early 08 replan – longer TD Phase
- **Individuals, Institutions, National and Regional groups support ‘in-kind’ R&D because of overlap with existing or planned projects and infrastructure development goals**
- **TDP Cost Management and Tech. Area Leaders to propose strategic ‘baseline choices’**
  - 2009 activity
  - consensus development required



# Release of the ILC Technical Design Phase R & D Plan

- June 6, 2008
- **The plan includes an outline of our**
  - strategy
  - work plan
  - schedule
  - deliverables
  - resources
  - constituency
- **very useful for management, reviews, funding agencies, ...**
- **Next review and release: December 08**





# R & D Plan Contents

<b><u>1</u></b>	<b><u>Purpose of this Document</u></b> .....	<b>1</b>
<b><u>2</u></b>	<b><u>Overview of the Technical Design Phase</u></b> .....	<b>2</b>
<b><u>3</u></b>	<b><u>Overview of Critical R&amp;D</u></b> .....	<b>5</b>
3.1	<u>Superconducting RF Technology (SCRF)</u> .....	5
3.2	<u>Beam Test Facilities</u> .....	10
3.3	<u>Other critical (risk-mitigating) R&amp;D</u> .....	11
<b><u>4</u></b>	<b><u>Machine Design and Cost-Reduction Activities</u></b> .....	<b>13</b>
4.1	<u>Conventional Facilities and Siting and Global Systems</u> .....	14
4.2	<u>Accelerator Systems</u> .....	17
<b><u>5</u></b>	<b><u>Cost and Schedule Planning and the Project Implementation Plan</u></b> .....	<b>18</b>
<b><u>6</u></b>	<b><u>Global Coordination</u></b> .....	<b>19</b>
6.1	<u>Inter-regional R&amp;D Coordination</u> .....	20
<b><u>Appendix A:</u></b>	<b><u>Summary of Estimate Global Resources</u></b> .....	<b>21</b>
<b><u>Appendix B:</u></b>	<b><u>TD Phase Work Packages</u></b> .....	<b>26</b>
<b><u>Appendix C:</u></b>	<b><u>Summaries of Activities useful for ILC TD Phase R &amp; D</u></b> .....	<b>48</b>
<b><u>Appendix D:</u></b>	<b><u>Participating Institutes</u></b> .....	<b>51</b>



# TD Phase Work Packages

- **Initial 2007 concept:**
  - a management compendium of all required activities for EDR preparation
  - would have been workable; but required effective prioritization process
- **2008 practicality:**
  - a workable, supportable structure reflecting established programs and priorities
  - amendments to be made as needed
    - for example with the 09 re-baselining
- **See R & D plan**

# Global Resource base 2007-2010: SRF

		FTE-Years					total M&S							
		Cavities	Cryomodule	HLRF	Cryogenics	ML Integ.	total FTE-Years	Cavities	Cryomodule	HLRF	Cryogenics	ML Integ.	total M&S	
Americas	Canada	18					18	1050					1050	k\$
	USA	73	24	68	5	14	183	9169	3960	5909	134	362	19535	k\$
Asia	China	12	8	8	4	1	33	1371	1371	1371	686	137	4936	k\$
	India	24	12				36	1560	900				2460	k\$
	Japan	45	6	11	4	5	72	19867	4125	4036	1607	9992	39627	k\$
	Korea	13		5			18	1619		264			1883	k\$
Europe	EU (CERN)				1	4	5					190	190	k\$
	France	94					94	14785					14785	k\$
	Germany	51	10	7	7	9	83	2506	531			35	3071	k\$
	Italy	38	8		1	1	48	1738	235				1973	k\$
	Russia	2	20				22	20					20	k\$
	Spain		3				3		13				13	k\$
		<b>370</b>	<b>90</b>	<b>99</b>	<b>21</b>	<b>34</b>	<b>615</b>	<b>53685</b>	<b>11136</b>	<b>11581</b>	<b>2427</b>	<b>10715</b>	<b>89542</b>	

plan lists contributions  
in native currency

- Notes:

- XFEL project specifically excluded where possible
  - → Estimate 65% of France FTE / 80% France M&S is XFEL project-related
  - Other EU does not include XFEL
  - DESY XFEL R&D ~ 155 FTE 2007-2009
- EU funding includes: CERN, European Commission Research Framework Programme 7/ 6 (5 contracts), National funding agencies (IN2P3, STFC, INFN, BMBF,...)
  - ILC project-specific and Generic R&D
- Japanese effort is labeled 'generic'; but largely supports ILC
  - Japanese FTE includes scientific and top-level engineering staff only
- Currency conversion based on 01.01.2008



# Global Resource base 2007-2010: Accelerator Systems

		FTE-Years							total M&S							
		Elec. Source	Posi. Source	Damping Rings	RTML	Beam Delivery	Simulations	total FTE-years	Elec. Source	Posi. Source	Damping Rings	RTML	Beam Delivery	Simulations	total M&S	
Americas	Canada			5				5			20				20	k\$
	USA	11	8	28	1	48	16	113	617	144	7174	3	3847	190	11975	k\$
Asia	China			12	4	20	2	38		69	686	14	27	14	809	k\$
	Japan	2	7	16		23	4	52			6447		3348		9795	k\$
	Korea			2	2	4	3	12			28	28	217	28	301	k\$
Europe	EU (CERN)			2		1	4	7			10		3	13	26	k\$
	France		11		5	12		27		573			9		582	k\$
	Germany		22	3		4	4	33		47	10		53	20	129	k\$
	Italy			17				17			441				441	k\$
	Spain					2		2								k\$
	Sweden				2	2		3								k\$
	UK		10	11		85		106		70	124		3069		3263	k\$
		13	57	97	14	201	33	415	617	903	14939	44	10574	264	27342	

- **Notes:**

- Test facilities account for ~80%
  - ATF2 effort regionally balanced
- UK effort greatly reduced
  - 2009 and 2010 ~ 20% of total
  - Non ILC-specific 09 and 10 R&D (instrumentation etc) not included
- Positron Source includes R&D on Compton 'alternate'
- Currency conversion based on 01.01.2008



# The GDE TDP Program:

- **Has a broad inter-regional basis**
- **US 'ART' contribution is consistent with plan and significant**
  - But not dominant, overall
- **Is based on a multi-lateral collaboration →**
  - Not centralized
- **Relies on 'in-kind' R & D contributions from partner labs and regions**
  - ILC project-specific
  - Other project-specific
  - Generic R & D
- **Has adequate resources for TDP1**
- **Will require increased project-specific design resources for TDP2**



# TDP External / Internal Reviews

## Reviews by:

- **Project Advisory Committee**

- J. – E. Augustin, Chair
- reports to ILCSC
- October 19-20, 2008
- includes detector group review (50 / 50?)
- will involve project managers (tbc)

- **Accelerator Advisory Panel**

- Bill Willis, Chair
- reports to Project Director, Barry Barish
- April 2009 (tbc);
- facilitated through ongoing, 'embedded', interaction between Panel and TDP Managers
- 10 to 15 reviewers (?)
- will involve Group Leaders and their support



# GDE Meetings

- **4 AAP reviews:**
  - Interim TDP1 (April 2009)
  - Final TDP1 (in preparation for the July TDP1 result)
  - Interim TDP2
  - Final TDP2
    - Integrated with GDE plenary meetings semi-annually
- **One GDE / LCWS collaboration-wide meeting / year**
  - DESY 2007
  - Chicago 2008
  - request broad attendance
- **Additional thematic meetings**
  - of course.



# GDE Communication

- **Accelerator Advisory Panel process is presented in the 'ILC Newsline Director's Corner'**
- ***Please watch this column – key policy is described in it: for example***
  - Project Advisory Committee – the other review body
  - Dubna meeting
  - Minimum machine
- **Monthly communication:**
  - a summary of monthly meetings →
  - Accelerator Systems, SRF, CF / S and Global, Cost Management Group and others
  - Notification through GDE-wide (400 member) mailing list
- **The mailing list is important, and only Maxine Hronek uses it**
  - please help keep it updated.



# ILC 2008 R&D: High Gradient:


## Motivation:

- large potential impact on the cost of the ILC.
- RDR gradient choice is 35 MV/m in vertical test
- *present average: 31.5 MV/m*

## Strategy:


- 1: research cause of gradient limits
  - a) field emission,    b) localized quench,    c) high cryo losses
- 2: develop countermeasures (JLab, KEK, DESY, Saclay)
  - a) final rinses    b) precision imaging/repair    c) baking
- 3: verify counter measures
- 4: integrate statistics

# Field Emission (reduced w/final ethanol rinse) → Localized quench



- *Note reduced number of field emission ‘Eonset’ entries in lower plot*
  - results from 15 cavities (DESY - Zanon)
  - some cavities tested many times
- *Gradient limits now dominated by localized quench →*
  - Thermal (DESY/FNAL/JLAB) / imaging (KEK) diagnostics very promising
  - *May be able to identify flaws after electro-polishing - before vertical test*

*Identification of flaws using precision imaging:*




- *validate with thermal mapping*
- *28 MV/m threshold may be possible?*





## 6th cavity production – rf results

- excellent + promising first results including first Plansee nine-cell (AC115)
- Z141 as first cavity with surfaces damages after fabrication under investigation



### •06.2008 :

- new batch of cavities (Accel - ACxxx) – 5 tested
- industrial bulk electro-polish
- first DESY - Accel results with ethanol rinse to suppress field emission
- Accel Average: 36.2 MV/m

<b>Americas</b>	US FY06 (actual)	US FY07 (actual)	US FY08	US FY09	US FY10	<b>TDP-T Totals (to June 2010)</b>	US FY11	US FY12
Cavity orders	22	12		10	10	<b>52</b>	10	10
Total 'process and test' cycles		40	5	45	30	<b>113</b>	30	30
<b>Asia</b>	JFY06 (actual)	JFY07 (actual)	JFY08	JFY09	JFY10		JFY11	JFY12
Cavity orders	8	7	8	25	15	<b>44</b>	39	39
Total 'process and test' cycles		21	40	75	45	<b>147</b>	117	117
<b>Europe</b>	CY06 (actual)	CY07 (actual)	CY08	CY09	CY10		CY11	CY12
Cavity orders	60	8		834		<b>902</b>		
Total 'process and test' cycles		14	18	26	30	<b>73</b>	380	406
<b>Global totals</b>								
<b>Global totals - cavity fabrication</b>	<b>90</b>	<b>27</b>	<b>8</b>	<b>869</b>	<b>25</b>	<b>997</b>	<b>49</b>	<b>49</b>
<b>Global totals - cavity tests</b>		<b>75</b>	<b>65</b>	<b>135</b>	<b>175</b>	<b>333</b>	<b>501</b>	<b>501</b>

## Cavities and Cavity testing: 2006 – 2012

- ❖ Results from Europe (DESY) - with strong expertise, mature infrastructure and mature industrial suppliers - dominate
- ❖ Americas (FNAL/ANL) and Asia infrastructure coming online now (many  $\sigma$  tests < 20 MV/m)
- ❖ Global plan has reduced emphasis on blind, cyclic processing; more emphasis on developing diagnostics and countermeasures



# Cryomodule Test – checking global 'plug compatibility'

## Goal:

- R&D on the Cryomodule facilitates the development of a detailed ILC Project Implementation Plan
  - including an achievable project schedule and plan for competitive industrialization in all regions.
- assume ILC will require a flexible design *based on modular sub-components*.

## Strategy:

- provide framework for technical and industrial development
  - Specify engineering interfaces between Cryomodule sub-components
    - and if possible within them

## Plan:

- Assemble and test a high-performance (31.5 MV/m average) cryomodule at KEK using components from each region (TDP 1)
  - 2 cavities from US, 2 from EU, 4 from Asia



# SCRF Linac Systems Test – DESY/FLASH

## Goal:

- Demonstrate precision accelerator control in nominal ILC conditions
  - high gradient, full beam loading: 31MV/m, 9 mA, 5Hz
  - Achieve nominal performance specifications in realistic conditions → energy spread, stability etc
- Test higher order mode absorbers, cryo system, instrumentation...

## Strategy:

- DESY – FLASH/TTF is the *only* suitable test facility available during TDP1
  - scale, beam parameters, instrumentation etc
  - testing also supports ongoing DESY projects / programs

## Status:

- DESY – led, KEK, FNAL are part of the team started March 2008
- To be complete by March 2009.
- Systems development in all 3 regions in TDP2 (DESY, FNAL, KEK)