



# HCAL task


Felix Sefkow



EUDET ExtSC Meeting  
September 1, 2008




# Topics



- HCAL mechanics
- HCAL calibration system
- HCAL electronics integration
- Personnel and finances



# Mechanics




- Goal: a realistic absorber structure for tests of novel readout techniques
- Realistic: compact and scalable
- No full cubic metre needed, but should be extendible
- Started only recently, after filling engineering position at DESY
- Realistic implies link with detector concepts, here ILD


# ILD detector

-Mechanical concept-

*Slides from K.Kschioneck*



- TESLA/ ILD detector:  
Similar absorber structure
- TESLA concept existed:  
learning from TESLA concept



- Height/ length of barrel: 5.6 m/ 4.6 m
- Weight of one module:  $\approx 14$  t
- Weight of HCAL:  $\approx 450$  t
- Weight of HCAL + chambers + ECAL:  $\approx 790$  t

# Calorimeter module



- ⇒ Side panel: 3 mm thickness
- ⇒ Screw size: M6

## Advantage


- Slim support structure (small amount of  $\phi$ -cracks)

## Disadvantages

- Uncertainties regarding stability
- High tolerance requirements (e.g. holes for screws, flatness of absorber plates)




# HCAL module




Horizontal hanging

Maximum deformation: 0.09 mm




Vertical hanging

Maximum deformation: 0.35 mm






Module standing

Maximum deformation: 0.7 mm





# Barrel -16 modules-



stainless steel 1.4404

standing

support 4

brass CuZn38Pb2

support 4

Max. deformation [mm]:



18.5

2.9


6.35

# Barrel -8 modules-

-with staggered spacer/ gap 7 mm-



stainless steel 1.4404  
standing support 4



brass CuZn38Pb2  
support 4

Max. deformation [mm]:


42

2.64

5.78




# HCAL module -with staggered spacer/ gap 7 mm-




Horizontal hanging

Maximum deformation: 0.7 mm



Vertical hanging

Maximum deformation: 0.4 mm



Module standing


Maximum deformation: 0.6 mm

# Effects of changed parameter

	displacement	stress
Bigger side panel (3 mm → 5 mm):	↓	↓
Spacer no → yes	↓	↓
From steel to brass:	↑	↑
Smaller gap (14 mm → 7 mm):	↑	↓
Pointing yes → no	↑	↑

: big change  
: moderate change  
: small change

# Next step: Proof of Principle



Building of a model: 4 x 5 absorber plates with side panel

- 2 x with welded connection for the side panel
- 2 x with screwed connection for the side panel


Learning something about:

- side panel connection
- connection between modules

- *Verify calculations*
- *Tolerances at realistic cost*
  - *incl. machining*
- *Cassette integration*
- *Ready Sep 09*



# Calibration system



- Goal: scalable system addressing the needs we determine in the ongoing test beam experiment
- Many procedures developed during last year's analysis, but not finally proven yet
- Stability of saturation still an issue -> need dynamic range
- Two approaches: optical or electrical signal distribution
  - Central driver plus fibres, or one LED / tile
- LED on board looks promising, further optimization in the hands of Wuppertal group
- Differences inside the active gap, but same external interfaces



# Multichannel LED driver for the AHCAL prototype

1. Introduction
2. Technical details
3. Deliverable definition






# Introduction


## New calibration system

- EUDET prototype significantly more compact
- New ideas for the calibration system for SiPM photodetectors
- **Fixed light amplitude** - low amplitude for gain calibration (DESY)
- **Tuneable** calibration light in the range 0 to 50-100 MIP (as in existing prototype) – for gain and efficiency monitoring (Prague)
- 1 LED above each tile
- A simplified optical system: one LED -> a fibre above 1 row of scintillator tiles (~ 60 tiles)



# Deliverable 2007 – single channel LED prototype (ILC-DET-2007-024)


Inductor ~ 30 nH




*Ivo Polák, Milan Janata*

- Double sided PCB
- 2 quasi-resonant (QRLED) drivers
- 2 PIN photodiode preamp
- Rate generator 1 Hz to 10 kHz
- Voltage regulators
- Amplitude control
- V-calib and T-calib interface


# PIN PD response to UV LED



- Tunable LED pulse amplitude
- Pulse width  $\sim 2$  ns
- At higher LED current - afterpulsing
- Needs adjustment to different LED types
- Being investigated
- Plane inductor  $\rightarrow$  toroidal inductor (less sensitivity to external interference, produces less radiation)
- No other changes in the design needed



30.6.2008



J. Cvach, Multichannel LED

16




# Toroidal inductor soldered

Compare the  
thickness of  
PCB and of  
the inductor



Toroid will be  
made in the  
PCB volume  
– no  
additional  
space needed




# We consider 2 scenarios of calibration system for EUDET AHCAL

1. **Fiber emitting light** for one row of tiles, QRled driver sitting outside of module (endcap) → development of the light distribution system (**our main effort in 2008**)

2. **QRled driver** is sitting at HBU above the **scintillator**

QR driver + LED

24\*3cm<sup>2</sup> area needed at the main PCB









# Light distribution system

- Side-emitting fibres  
Thin fibres (~1mm) needed, unknown parameters, not common → *FiberTech (SLS600 series)*
- 'Notched' fibres  
Making notches on fibres requires a specialized firm → *Safibra comp.*
- Focusing LED light into fibre → *Optical lab of the CU Prague*

**Notched fibres appear promising:**


- Response over 2.2m length drops linearly by 40%, RMS ~ 14%
- Light output from notched fibers > 2.7 times higher

Jan Smolík, Jaroslav Zálešák J. Cvach




# How we understand the „Deliverable at the month 33 : Multichannel LED driver“

- 1 PCB with the communication module  $\mu$ C, power regulator, 4-6 channels of QRLED driver
- The communication module communicate with the PC via CAN bus or USB
- The communication module communicates with the analog part via SPI (GPIO?)
- LED pulse width is  $\sim 5$  ns is fixed, the tunable amplitude in range up to 50-100 MIPs is controlled by the V-calib signal



# What should be done?

- Communication module is ready → the final design of PCB for the digital part starts in July
- Optimization of the QRLed driver (tests of the linearity, adjustment for another LED type) - July
- Design of PCB for the analog part will be done in August
- PCB production – September
- In parallel – innovation of the optical system
- PCB tests – October, Report – November
- Time schedule is tough but no principal problems encountered




**View of the calibration electronics with the digital part (left) and analog part with LEDs (right)**



# Next prototype: Architecture


FE

the future ...



*Slides from M.Reinecke*

## 1st EUDET Prototype (1st step)




Commercial DIF, new mezzan.  
(CALIB, POWER), 1HBU (later: 6)





# HCAL Base Unit (HBU0)

FE





# HBUO Status

FE

- Integration concept fixed
- Schematic (Mentor Graphics CAD) finished
- Layout is waiting for tile geometry information
- Critical parts (connectors) ordered.
- Layout is complex (1-2months), PCB manufacturing and assembly: 1-2months => realization in 2008 already critical!

Design progress is interrupted due to missing tile information.

HBU schematic top layer


Developer	<AC> 王德成 (Wang Decheng)	Project	欧洲核子研究中心 (CERN)
Entered by	<S> CR DESY 王德成 (Wang Decheng)	Schema	欧洲核子研究中心 (CERN)
Layout	<S> CR DESY 王德成 (Wang Decheng)	DESIGN	王德成 (Wang Decheng)
Changed in sch	<S> CR DESY 王德成 (Wang Decheng)	DESIGN	王德成 (Wang Decheng)
Last Change	2007-09-15 15:59	DESIGN	王德成 (Wang Decheng)
Date of publication	2007-09-15 15:59	DESIGN	王德成 (Wang Decheng)



# HBU Interconnection (Flexleads)

FE

- Two types of Flexleads (for Signals, Power) have been designed (CAD)
- Flexleads allow  $\pm 100\mu\text{m}$  displacement of connecting modules
- Magnet-field tests have proven connector suitability up to 5T
- Flexleads can be ordered now!



**Flexlead CAD Layout**



# DIF Status

FE


-Based on commercial FPGA  
(Spartan3-1500) board

-Command list and  
DIF state diagram  
in preparation

-VHDL code generation soon  
(prototype firmware for  
USB access in 2008)

Firmware status of ECAL/DHCAL?  
Reference documents for LDA-DIF  
interface (also: DAQ group)?  
Firmware development needs closer  
coordination.

Command	Function and Parameters	Change DIF State?
power_on	turn slab power on / off (maybe partly?)	no
reset_DIF	reset of DIF electronics (not: slab)	yes
reset_slab	reset of slab (ASICs). Not: DIF	yes
reset_BCID	synchronize data taking by resetting bunch counter	no
sleep	puts DIF and slab into SLEEP state (powered down)	yes
sync	synchronization LDA all DIFs	yes
idle	puts DIF into idle state (DIF power on, slab power on minimum)	yes



**DIF state diagram**




# CALIB Status

FE

## „AHCAL Calibration System“ (UV-LED and Charge Injection)



- Concept fixed, schematic finished
- $\mu$ Controller software dev. ongoing (good progress)
- Layout (CAD) starts now, expected to be finished: End of September.
- Module should be available: November/December 08





## „AHCAL Slab Power Regulators“


- Regulator setup fixed, schematic finished
- Suitable for ILC-like power cycling
- Layout and production probably in 2009  
(module can be replaced initially by bench-top power supplies)






# AHCAL Slab Interface (Mech.)

FE



Not in scale!!

Next HBU0



- Mechanical proposal (cassette, interface to DIF) has been set up for the AHCAL prototype (HBU0, DIF as commercial board).
- The necessary mechanical parts are currently designed within CAD tool => production within 2008




# Conclusions

FE

- AHCAL technical prototype (TP) does not cover a full slab, but ~150 channels (2 HBUOs, tile-prototypes).
- Eudet module (detector layer) requires HBU redesign. A full slab (and detector layer) is expected for summer/autumn 2009.
- timeline for TP is defined by HBUO (tile geometry missing).
- development of the modules CALIB and DIF (firmware) in 2008 possible. But for HBUO we need the tile information to proceed.




# Next milestones



- Calibration multi-channel prototype 9/2008
  - Optical version: in production
  - Electronics version: late 08/early 09, but already integrated
- HCAL production readiness review 12/2008
  - paperwork
- Mechanical design 12/2008
  - Converging, in phase with ILD
- Outlook: HCAL integration prototype in 9/09




# Resources



- DESY
  - Engineering position filled 10/07 , 27 ppm -> end 09
  - Spending of committed funds started
    - Electronics ~ 20k in 2008
    - Mechanics ~ 40k in 2008
- UHAM
  - Only travel money for test beam support and meetings
  - Transferred to DESY, because PhD position largely not filled
- UPASCR Prague
  - See information from Cvach, peak spending slightly later, no problem



# Conclusion



- Schedule is tight
  - No wonder, as everyone else is slowing down
- Electronics integration suffering from too close link to users
  - standardized interface under intensive discussion
- Calibration: two solutions
- Mechanics late due to late recruiting, but catching up
  - Additional manpower entering now, after completion of test beam set-up and HERA dismantling