



Science & Technology Facilities Council

Technology

undulator manufacture and measurement

James Rochford

On behalf of the Helical collaboration

STFC Technology

•Introduction

- Undulator specification

•Prototype design, manufacture, testing

- 4m Module design
- Magnet Testing and integration
- Assembly of 4m module
- First tests of the final prototype

•Current status

- Where we are at the moment
- Plans for the coming months


Following a pretty extensive R&D programme and modelling study the following specification was developed for the undulators:

| | | |
|--------------------------|-----------------------|---------------|
| Undulator Period | | 11.5 mm |
| Field on Axis | | 0.86 T |
| Peak field homogeneity | <1% | |
| Winding bore | | >6mm |
| Undulator Length | | 147 m |
| Nominal current | | 215A |
| Critical current | | ~270A |
| Manufacturing tolerances | | |
| | winding concentricity | 20um |
| | winding tolerances | 100um |
| | straightness | 100um |
| NbTi wire Cu:Sc ratio | 0.9 | |
| Winding blocck | | 9 layers |
| | | 7 wire ribbon |

This defines the shortest period undulator we could build with a realistic operating margin.


4m Prototype

- 150m of undulator
- Module length
 - Vacuum considerations <4m
 - Collimation <4m
 - Magnet R&D 2m section realistic
- Minimise number of modules
 - 2 magnet sections per module




Cryogenic system


- Magnets Bath cooled
- Re condensing system
- utilising a thermo siphon





Magnet manufacture



Magnet testing





Field maps along the length of the undulator




Consistency of logging system

Sine wave pitch of - 11.492mm



Particle Trajectories analysis - SPECTRA within expectations




Quench testing both magnets deliver nominal field

4m module assembly

4 meter module assembly




Straightness
250um



Alignment scope

Axis
alignment 1mm



Mag 2 connection


Mag 1 connection



Current leads

Condensing pot


HTS leads



First run of complete system early Sept.



Successful cool down and fill



The 1st cool down was successful

Filled system successfully

Siphon operation seems good

However had serious problem

Large heat leak evident

Rapid boil off of liquid

Loss of vacuum in magnet bore (Beam tube)

Liquid helium leak into magnet bore

System not stable enough to put current into the magnets

System had to be warmed

Upon warming

Found no leaks at 300K all $<10e-10$ into magnet bore


Found very small leaks between He vessel

–insulating vacuum $<1e-8$ – copper conflate seals

Clear we had a cryogenic leak !

Had to remove magnets

Complete strip down of the prototype



Cryogenic leak testing

Created a large open Liquid nitrogen bath


To immerse magnets whilst leak testing

Initially found a leak at the indium seal between magnets


Fixed this by modifying the clamp arrangement

Much more worryingly seem to have a leak through

the magnet structure, on magnet 1 and magnet 2



Current status



Suspected leak path

The leak is strange

Not at a normal interface

Seems to be through the magnet torturous path through resin along copper bore to point where the magnets join

Have some ideas on how to fix this

There is a possibility that the bore tube has ruptured somewhere, this is really bad news! but the delay times in the leak response indicate the solder leak is much more probable

Leak rate $2e-4$
 level on magnet 1


Leak rate $2e-7$
 level on magnet 2

Further tests

Tests are hard to perform

Difficult to localise leak seen on magnet 2 may just be presence of leak on magnet 1 close by

More tests planned to try to isolate leaks



Confirm leaks

Confident we can fix the leak with sty cast
Will check this by cooling with LN2 as for leak tests described earlier
Repeat prototype build with an additional step
Once the magnets are integrated in the vac vessel
We will cool using the LN2 circuit and leak check
prior to connecting the turret
If ok we will proceed with the build

Finish Rebuild of prototype

Hopefully by Christmas

Next cool down

Power magnets to nominal current
This will probably be in the new year

Stability tests

Warm up

Bore heater tests
More quench tests of magnet 2