


TPC Status



K.Fujii and R.Settles on behalf of LC-TPC

LCTPC MOA to R&D/design a TPC: Status August 2008

Americas

BNL ✓
Carleton ✓
Montreal req
Victoria ✓
Triumf ✓
Cornell ✓
Indiana ✓
LBNL prom
Louisiana Tech req

Observer groups

Iowa State
MIT
Purdue
Yale
TU Munich
UMM Krakow
Bucharest

11/09/2008

Asia

Tsinghua ✓
CDC:
Hiroshima req
KEK ✓
JAX Kanagawa req
Kinki U ✓
Nagasaki InstAS req
Saga ✓
Kogakuin ✓
Tokyo UA&T req
U Tokyo req
Minadano SU-IIT req

Signatures 24
Promised 3
Requested 11
New groups welcome

Ron Settles MPI-Munich/DESY
LCTPC planning for the LOI

Europe

Brussels ✓
LAL Orsay req
IPN Orsay req
CEA Saclay ✓
Aachen ✓
Bonn ✓
DESY ✓
EUDET ✓
U Hamburg ✓
Freiburg req
Karlsruhe req
MPI-Munich ✓
Rostock ✓
Siegen prom
NIKHEF ✓
Novosibirsk ✓
St. Petersburg prom
Lund ✓
CERN ✓

Addendum 2008 to the LCTPC MOA: R&D organization

Overview

The status as of November 2008 about R&D responsibilities, structures and plans are outlined in this document. All issues for the TPC performance within the linear collider framework have been described at several reviews since 2001, most recently for the WWS R&D review in LC Note LC-DET-2007-005 at <http://flcweb01.desy.de/lcnotes/>. The names of LCTPC members will be updated at <https://wiki.lepp.cornell.edu/wws/bin/view/Projects/TrackLCTPCcollab>.

TPC Section of the LoI

Questions for LCTPC

LCTPC issues for the LOI

1. Performance goals

- R&D plans/options/risks
- How was the subdetector optimized?
(e.g., using resolution, costing?)

2. Sensitivity to backgrounds

3. Calibration and alignment schemes

4. Engineering model for LOI and simulation


- Size, weight, support, dead areas
- Endplate, electronics, power
- Fieldcage, chamber gas

5. Push-pull ability

6. \sqrt{s} coverage

TPC Section of the LoI


Status: Draft 15 being circulated in LCPTC

- Motivation: rationale for TPC
- Design Issues
 - Performance goals 4T→3.5T translation
 - Endcaps: MPGD readout planes
 - Readout electronics
 - Field cage
 - BG issues: pattern recognition, E/B distortion
 - Alignment (push-pull)
- R&D
 - LCTPC collaboration
 -  SP/LP status/results to be inserted
 - Endcap drawings to be updated

LCTPC performance goals

R&D plans/options

Present goals based on results from small prototypes using cosmics or beams at KEK, DESY, CERN. Three options left →



11/09/2008

Ron Settles, MPI Munich/DESY
LCTPC Meeting Sendai


Examples of Prototype TPCs

- Carleton, Aachen, Cornell/Purdue, Desy(n.s.) for B=0or1T studies
- Saclay, Victoria, Desy (fit in 2-5T magnets)
- Karlsruhe, MPI/Asia, Aachen built test TPCs for magnets (not shown) other groups built small special-study chambers


Munich 0
 Beijing BILCW07 Tracking Review
 LCTPC Design, R&D Issues

5 February 2007


MicroMEGAS TPC with resistive anode Carleton TPC (M. Dixit et al., 2007)



Silicon Pixel Readout for a TPC




Important Milestone LP1 Beam Tests




Micromegas module tests done in Nov./Dec. 2008
GEM module tests about to start

Micromegas Module Tests


- Two modules, with and without resistive anode, exposed to beam
- New modules with different resistive anodes being fabricated and tested
- Analysis meeting held on Feb.11 at DESY
 - Data now on GRID



LP1 with
a Micromegas Module
and AFTER
in the PCMAG




Cosmic Ray Events



Beam Position

~7.7degrees


Beam Events



GEM Module Status

- 4 GEM modules fabricated at Saga Univ. The 1st one shipped from KEK and the other three shipped from Saga, all of them now at DESY.
- The 1st GEM module had been tested at the KEK cryo-hall with the ALTRO DAQ (1 RCU mounting 2 FECs, each carrying 8 ALTRO chips), all of them now being tested at DESY.

KEK Cryo-hall Test



RCU

FEC



Test Box

A hall for
checking
source


ALTRO DAQ from Lund




Sample Sr90 Events at KEK



Package from Japan



PCB from Tsinghua





3 spare GEMs
3 Gate GEMS

Everything now at DESY

Standalone Test at DESY

A GEM module with local DAQ

The moment we found
the first Cosmic ray event
at DESY



FADC dist. of each pad(x)
row(y).

Trigger counter

GEM module with test box

YATTAH !!

Standalone Test at DESY

A GEM module with local DAQ




YATTAH !!

How cosmic ray data look

2 FECs available for local DAQ -> 8 connectors = 16 layers of 16 pad series

Offline quick monitor

Each hist. corresponds to a ADC-vs-time plot (flash ADC dist.) for each pad (~1x5 mm²)
you would reconstruct a track in your brain easily




What we are testing before installation.

GEM is OK? can be known from HV vs current
Cosmic ray data from ALTRO DAQ

We don't use a Gate GEM this time.
How a GEM module fits into EP
!! Insulator is facing the drift region !!
!! There is 1cm GAP
between the GEM surface and the dummy surface
--> apply 7th grid V to recover this difference


Bunch of tiny connectors
grounding connectors (receptacles) are
mounted on all unused connectors
10 HV connectors
2 for a segment of GEM x 2 segments x 2 layers
2 for a GATE (unused this time)



Exercise of module installation

Klaus and Volker prepared a nice setup for our exercise

We started exercise of installation with dummy module.



We also did practice with a real module.

We made sure this module's alive after practice!

put GEM module into "LP1"

flip module right way

pull back to right position



Schedule

Feb	2 Mon	LP1	GEM module
	3 Tue	PCMAG cooling	
	4 Wed		GEM arrival
	5 Thr	Stand-off replace	Standalone setup with local DAQ
	6 Fri		channel mapping
	7 Sat		noise study
	8 Sun		gain check/HV set
	9 Mon	close EP+	cosmic ray test
	10 Tue	cathode meas.	install 1st GEM to LP1
	11 Wed	LP1 move to testbeam	EUDET/ALTRO elec. Arrive
	12 Thr		local test of
	13 Fri		2nd/3rd/4th module setup @LP1
	14 Sat		
	15 Sun		
	16 Mon	take Beam data	
	17 Tue	w/ 1st Module	ALTRO/FEC tuning shaping...
	18 Wed		drift distance
	19 Thr		phi angle
	20 Fri		
	21 Sat		install 2nd/3rd module
	22 Sun		
	23 Mon	take Beam data	
	24 Tue	w/ 3modules	
	25 Wed		
	26 Thr		
	27 Fri	w/ TDC electronics	replace elec. Of 1 module
	28 Sat		
Mar	1 Sun		
	2 Mon	take Beam data	back to ALTRO electronics
	3 Tue	w/ 0 Tesla	
	4 Wed		
	5 Thr		
	6 Fri		
	7 Sat		
	8 Sun		
	9 Mon		

We are only a few days behind schedule

- The ALTRO DAQ being setup by Lund people. Hopefully be ready by the end of this week.
- 3 GEM modules to be installed in LP1 very soon.
- The 1st beam the end of this week?