



Test Facilities Part 2


Nick Walker

PAC Review – 10.05.2009



(Other) Test Facilities


- TTF2/FLASH (DESY)
 - “String Test” SCRF linac technology
 - Specifically: 9mA full beam-loading experiment
- ATF (KEK)
 - Ultra-low emittance Damping Ring
 - Fast (inj/extr) kicker test-bed
 - Fast-ion instability studies
 - Source for...
- ATF2 (KEK)
 - New facility (commissioning since end 2008)
 - BDS Final Focus optics (tuning)
 - Instrumentation / Diagnostics







(Other) Test Facilities

- **ITF2/FLASH (DESY)**
 - “String Test” SCRF linac technology
 - Specifically: 9mA full beam-loading experiment
- **ATF (KEK)**
 - Ultra-low emittance Damping Ring
 - Fast (inj/extr) kicker test-bed
 - Source for ...
- **ATF2 (KEK)**
 - New facility (commissioning since end 2008)
 - BDS Final Focus optics (tuning)
 - Instrumentation / Diagnostics






ATF2 – model of ILC BDS



ATF International Collaboration



ATF2 project meeting, 15-18 December 2008



Primary ILC Objectives

- Achieve 35nm vertical beam size at IP (focus) 2010
 - **Demonstration of Raimondi/Seryi compact optics**
 - **Development of beam-based tuning algorithms**


- Demonstration of stability 2012
 - **Maintain 35nm for “long period of time”**
 - **Actively stabilise beam centroid to <2nm**
 - Fast feedback systems
 - Active (mechanical) component stabilisation (laser systems)

- Tests of prototype ILC final-doublet technology 2012

- Rich programme (large international participation)
 - **Laser-based diagnostics**
 - **nm BPM development**
 - ...



ATF2 schedule



First beam to beam-dump
😊



Highlights of recent runs


- December 2008
 - large IP beta optics, semi-ballistic trajectory
 - Establish beam to beam dump, minimize losses, Radiation inspection
 - First tests of hardware and tuning software (FS)
 - BSM commissioning & background characterization
- Jan 2009
 - fast kicker study
 - Replace QM7 to one with larger aperture (possible source of EXT ϵ growth)
- Feb-Mar 2009
 - Large (8cm beta*), all magnets ON
 - Commission laser wire mode of BSM
 - Tuning tools (fp beam size tuning, beam-based alignment...)
- April 2009 run
 - Optics verification for $\sim 1\mu\text{m}$ beam (large, 1cm β^*) / IP wire scanners
 - Commission interferometer mode of BSM



ILC-CLIC Collaboration

ATF2 is an excellent example of cross-collaboration between ILC and CLIC

Many R&D programmes are equally applicable to both projects



- Low- β proposal
- by CLIC colleagues
 - Rogelio Tomas et al
- Explore & push the limits of optics
- Large aperture QF1 may be necessary

case	Max. tuning time	Success	$\langle\sigma_y\rangle$
$\beta_y=0.1\text{mm}$	5.5 days	100%	43nm
$\beta_y=0.05\text{mm}$	8 days	90%	33nm
$\beta_y=0.025\text{mm}$	10 days	80%	26nm

including multipoles


$\beta_y=0.025\text{mm}$	10 days	70%	29nm
--------------------------	---------	-----	------



TTF2/FLASH “9mA Experiment”



9mA Experiments in TTF/FLASH



		XFEL X-Ray Free-Electron Laser	ilc	FLASH design	FLASH experiment
Bunch charge	nC	1	3.2	1	3
# bunches		3250*	2625	7200*	2400
Pulse length	μ s	650	970	800	800
Current	mA	5	9	9	9



The (International) Team

• FLASH Experts (DESY)

- Siggi Schreiber
 - Bart Faartz
 - Lars Froehlich
 - Florian Loehl
 - Holger Schlarb
 - Nina Golubeva
 - Vladimir Balandin - optics calculations
 - Valeri Ayvazyan -
 - Mariusz Grecki
 - Waldemar Koprek - LLRF set-up and tuning (mostly gun)
 - Jacek Sekutowicz - HOM absorber measurements
 - Stefan Simrock
 - Kay Rehlich
 - Kay Wittenburg
 - Dirk Noelle
 - Nick Walker
 - Katya Honkavaara
 - Mikhail Krasilnikov
- laser/gun injector set-up
 - general set-up
 - TPS installation / commissioning, BLM calibration
 - optics matching & emittance
 - optics & steering
 - optics calculations
 - LLRF set-up and tuning
 - LLRF set-up and tuning
 - LLRF (general)
 - controls (DAQ)
 - diagnostics
 - diagnostics (BPM)
 - overall coordination
 - planning
 - RF gun modelling

~40 subscribers to
tff9mA mailing list
(not all shown here)

***RF/LLRF collaborators:
DESY, KEK, FNAL, SLAC***

• ANL

- John Carwardine
 - Xiaowei Dong
- LLRF / overall coordination
 - data analysis, optics modeling

• FNAL

- Brian Chase
 - Gustavo Cancelo
 - Michael Davidsaver
 - Jinhao Ruan
- LLRF (experiment & data analysis)
 - LLRF (experiment & data analysis)
 - DAQ applications programming
 - laser setup

• KEK


- Shinichiro Michizono
 - Toshihiro Matsumoto
- LLRF (experiment & data analysis)
 - LLRF (experiment & data analysis)

• SLAC

- Chris Adolphsen
 - Tom Himel
 - Shilun Pei
- LLRF (experiment & data analysis)
 - Planning & scope
 - LLRF (experiment & data analysis)

• SACLAY

- Abdallah Hamdi
- TPS installation / commissioning





String Test: goals from R&D Plan

Integration Tests

- The highest priority goal is to demonstrate beam phase and energy stability at nominal current
- Important because of their potential cost impact:
 - **demonstrate operation of a nominal section or RF-unit**
 - **determine the required power overhead**
 - **to measure dark current and x-ray emission**
 - **and to check for heating from higher order modes**
- Needed to understand linac subsystem performance:
 - **develop RF fault recognition and recovery procedures**
 - **evaluate cavity quench rates and coupler breakdowns**
 - **test component reliability**
 - **tunnel mock up to explore installation, maintenance, and repair**




Primary objectives of 9mA program

- Long-pulse high beam-loading (9mA) demonstration
 - **800 μ s pulse with 2400 bunches (3MHz)**
 - **3nC per bunch**
 - **Beam energy $700 \text{ MeV} \leq E_{\text{beam}} \leq 1 \text{ GeV}$**
- Primary goals
 - **Demonstration of beam energy stability**
 - Over extended period
 - **Characterisation of energy stability limitations**
 - Operations close to gradient limits
 - **Quantification of control overhead**
 - Minimum required klystron overhead for LLRF control
 - **HOM absorber studies (cryo-load)**
 - ...
- Major operational challenge for FLASH !
 - **Pushes many current operational limits**

Primarily a
LLRF
experiment



Extrapolating to ILC gradients



- 1/2 cryomodule could be running close to ILC gradients with ILC beam
- Opportunity to study:
 - Lorentz-force detuning + piezo compensation near ILC gradients
 - rf overhead near ILC gradients
 - rf distribution system near ILC cavity powers

- Broadly, we get information on operating cavities with full beam loading, eg
 - Piezo compensation of LFD
 - Running high gradient cavities close to quench
 - Vector Sum field regulation



Comparison of gradient-related operational issues

	RDR	ACC4-6
Nominal maximum operating gradient over all cavities in RF unit	31.5MV/m	~27MV/m
Spread in nominal maximum operating gradients	31.5MV/m +/-0	21-32MV/m (4 cavities at 32MV/m)
Number of cavities operating at 31.5MV/m or above	26 of 26	4 of 24
Cavity quench limits	All: >33MV/m	Range: 21-35MV/m
LFD compensation with piezos	All cavities	ACC5,6 (16 cavities)
Operate cavities close to quench?	Yes	Yes


Schedule

- 19/05-01/06/08: 1st machine study period
– **3nC optics via by-pass (good transmission)** **complete** LLRF development & planning for
 - 08-28/09/08: 2nd machine study period
– **By-pass TPS (6 shifts)** **Complete / Aborted!** XFEL ✓
– **Longer bunch trains** FLASH ✓
ILC ✓
 - 05-18/01/09: 3rd machine study period
– **“dress rehearsal” (est. 9 shifts *tbc*)** **Low-power or no-beam studies only** almost 100% synergy
- August 17th 2009: Three week shutdown for vacuum repair
 - Two-week dedicated 9mA experiment
– **2 week run dedicated to 9mA studies**
– **Detailed experimental programme in planning**


High Beam-Loading Long Pulse Operation

September 2008

10 MeV over 550 bunches (~1%)
(~4 MeV over 1st 500)



- 450 bunches achieved with stable operation
 - Few hours of archived data
 - Currently under analysis
 - (vacuum OK)
- Long bunch trains with ~2.5 nC per bunch:
 - 550 bunches at 1MHz
 - 300 bunches at 500KHz
 - 890 MeV linac energy
- All modules (RF) running with 800us flat-top and 1GeV total gradient
- Increase from 450 to 550 bunches eventually caused vacuum incident
 - The "straw that broke the camels back!"





FLASH long-range schedule


- Shutdown for FLASH upgrade: Sept 21 – March 09
- Re-commission + machine & FEL studies: ~ 3months
- Restart operation for photon users: Summer 09
- User operation continues until end 2011
- Shutdown for FLASH-II upgrade: early 2012




FLASH Upgrade 2009/10

FLASH
Free-Electron Laser
in Hamburg

Present layout



New layout





Possible future ILC studies at FLASH

- The new RF distribution system means we no longer have an ILC-like RF unit (now 16 cavities / klystron)
 - **Not a “show stopper” for String Test demo**

- Highly desirable to continue with the major 9mA program topic areas
 - **Add: priority items not covered in 2009 run**
 - **Add: new ILC-related studies, eg RTML**
 - **Add: studies of mutual interest to ILC and XFEL**



Beam test in every region?

Stop Press

- Assuming we accept the necessity of developing infrastructure in all 3 regions for cryomodule construction, development and testing, the question remains if it is necessary to have a beam test facility in all 3 regions
 - **i.e. a linac**
- If we strictly focus ourselves on the ILC, then the answer could be no. In principle, a single test linac somewhere in the world would suffice.
- However, we must include the constraints of the world-wide situation...



Beam test in every region?

Stop Press

- The attractiveness of this accelerator technology, and the desire by regional governments to develop the technology for other applications, mandates a local expertise in the technology as an accelerator system, which clearly includes acceleration and control of the beam
 - **Education & training**
- Much of our ILC-labelled R&D is strongly based on the synergy with these other projects.
- A single 'beam test facilities' would require shipping of regional test modules (prototypes) to the region where the TF is located. This is also a cost issue.
- A decision on "where" a single TF is sited is avoided (political).



Beam Test Facilities (Summary)

⊙ Cornell



CesrTA (Cornell)
electron cloud
low emittance



DESY

TTF/FLASH ⊙
Full-beam loading
HOM...
(S2)

ATF & ATF2 (KEK)
ultra-low emittance
Final Focus optics

KEK, Japan

⊙

