



GDE Overview

Barry Barish

PAC Review– Vancouver, Canada

9-May-09



Technical Reviews

- Accelerator Advisory Panel (Willis & Elsen)
 - On-going reviews by assigned AAP members to particular systems (attend meetings, etc)
Example result: Questions regarding plug compatibility have resulted in studies, report
 - Technical Review – first one 3.5 days at TILC09 in April. Internal + 4-5 external reviewers. Yearly through TDP phase with continuity. First review: Overall coverage + focus areas
- ILCSC PAC Review:
 - 1.5 days (1 day GDE); higher level review and will use AAP review as input.



PAC Oct08 Recommendations

- General

- The PAC views very positively the recent start of common activities between the ILC and CLIC on many items such as conventional facilities, beam delivery system, detectors, physics, cost estimation, etc. This avoids unnecessary duplication of effort, and keeps the particle physics community focused on the goal of a linear collider as the next major new facility for the field.

- Accelerator

- The PAC believes that the appointment of the three Project Managers, and the formation of the Accelerator Advisory Panel (AAP) for internal advice to the GDE Director, significantly strengthen the GDE organization as it moves into the Technical Design Phase.
- The current TDP schedule, with reporting dates of 2010 and 2012, is fixed by outside constraints, and the PAC concurs with the result.
- The GDE is to be commended for its efforts to bring about worldwide collaboration among labs on SCRF, BDS, DR, etc. The ILCSC should support the international use of test facilities such as CESR/TA, TTF/FLASH, ATF2, STF, ILCTA_NML, and others.



PAC Oct08 Recommendations

Accelerator (continued)

- The PAC is very positive about the GDE concept of plug compatibility, especially for SC cavities. It notes that GDE will need to monitor the large flexibility that this concept could allow.
- The S1 test organization appears to be a success, and the PAC looks forward to hearing of progress and a schedule for S2.
- The PAC endorses research on SC cavity processing, and also notes the importance of obtaining good statistical data; this will be helped by the experience which will be obtained on the XFEL project construction.
- The flow of information on SC cavity processing and tests between labs is strongly encouraged. The same is true for information from industry, although the PAC acknowledges the difficulties that may arise in this case.
- The PAC notes with interest the recent GDE efforts on a “Minimum Machine” and cost-reduction; it welcomes the study of the single-tunnel concept, and other studies on simplifications to the accelerator facility. While cost reduction is important, the PAC notes that this may not necessarily be desirable if it leads to more risk, or precludes some future options such as eventually achieving the beam current specification or 1 TeV operation.




PAC Oct08 Recommendations

- General

- The PAC views very positively the recent start of common activities between the ILC and CLIC on many items such as conventional facilities, beam delivery system, detectors, physics, cost estimation, etc. This avoids unnecessary duplication of effort, and keeps the particle physics community focused on the goal of a linear collider as the next major new facility for the field.

- Accelerator

- The PAC believes that the appointment of the three Project Managers, and the formation of the Accelerator Advisory Panel (AAP) for internal advice to the GDE Director, significantly strengthen the GDE organization as it moves into the Technical Design Phase.
- The current TDP schedule, with reporting dates of 2010 and 2012, is fixed by outside constraints, and the PAC concurs with the result.
- The GDE is to be commended for its efforts to bring about worldwide collaboration among labs on SCRF, BDS, DR, etc. The ILCSC should support the international use of test facilities such as CESR/TA, TTF/FLASH, ATF2, STF, ILCTA_NML, and others.



Purpose of these statements:

The CLIC and ILC Collaborations agree to work together, within the framework of the CLIC / ILC Collaboration, to outline comparative statements to be used in presenting their respective projects. The Collaboration members agree to limit statements made about each other's projects to specifically agreed upon statements such as those listed below:

• **Project design**

The CLIC and ILC projects both plan to release design documents in the coming years. The CLIC Conceptual Design Report is to be published in 2010. If the CLIC technology is demonstrated to be feasible, a CLIC Technical Design will then be launched for publication in a CLIC TDR by 2015. The ILC TDR will be published in 2012. The design reports are intended to summarize the R&D and project planning at that time and will serve as indicators of project readiness. Both TDRs are intended to be submitted to governments and associated funding agencies in order to seek project approval.

• **Test facilities and system tests**

The CLIC and ILC projects both have test facilities either in operation or under construction for the purpose of demonstrating the performance of key technical components or to allow system engineering and industrialization. For each project, R&D priorities and schedules have been defined and it is anticipated that milestones and progress will be reviewed and reported on by members of the community. The XFEL project, with the same technical basis as the ILC, although at a lower accelerating gradient, and 7% of the energy of one of the ILC linacs, is a large-scale system test and demonstration of the industrialization of the ILC linac technology. The CERN-based CTF3 project is a demonstration of the CLIC two beam technology, although at a lower beam power.

• **Technology maturity and risk**

The collaborations agree that the ILC technology is presently more mature and less risky than that of CLIC. There are plans to demonstrate, by 2010, the feasibility of CLIC technology and to reduce the associated risk in the future. The ILC collaboration will focus on consolidation of the technology for global mass-production. Both collaborations consider it essential to continue to develop both technologies for the foreseeable future.

• **Costing**

Project planners from the CLIC and ILC projects are developing common methodologies and tools with the intention of enabling the development of similarly-structured project planning and costing documents for each of the two projects. The two collaborations agree to make no public statements about the comparative cost numbers of the two machines until these project planning and costing documents are complete.

Barry C. Barish
ILC-GDE Director

J-P. Delahaye
CLIC Study Leader

CLIC / ILC Collaboration

- Working Groups with joint leadership
- Accelerator Tech Areas
- Physics / Detectors
- Costing

- First progress reported last fall


- **CLIC – ILC Collaboration has two basic purposes:**
 - 1. allow a more efficient use of resources, especially engineers**
 - CFS / CES
 - Beamline components (magnets, instrumentation...)
 - 2. promote communication between the two project teams.**
 - Comparative discussions and presentations will occur
 - Good understanding of each other's technical issues is necessary
 - Communication network – at several levels – supports it
- **seven working groups which are led by conveners from both projects**



Collaboration Working Groups

	CLIC	ILC
Physics & Detectors	L.Linssen, D.Schlatter	F.Richard, S.Yamada
Beam Delivery System (BDS) & Machine Detector Interface (MDI)	D.Schulte, R.Tomas Garcia E.Tsesmelis	B.Parker, A.Seryi
Civil Engineering & Conventional Facilities	C.Hauviller, J.Osborne.	J.Osborne, V.Kuchler
Positron Generation (new 11/08)	L.Rinolfi	J.Clarke
Damping Rings (new 11/08)	Y.Papaphilipou	M.Palmer
Beam Dynamics	D.Schulte	A.Latina, K.Kubo, N.Walker
Cost & Schedule	H.Braun, K.Foraz, P. LeBrun	J.Carwardine, P.Garbincius, T.Shidara

ilc our common plans - 11/08:



- ✓ CLIC-ILC Cost & Schedule Working Group WEBEX Meetings
1400 GMT - 2nd Thursday of each month
- ✓ Keep work towards cost estimate mutually transparent
- ✓ Profit by synergies
- ✓ Understand and communicate unavoidable differences in the methodologies used for the two projects
- ✓ Construction & installation schedules for CLIC & ILC w same methodology – 6/09
- Common ILC/CLIC notes (for mid '09)
 - Tunnel safety underground compliance
defer to: Fabio Corsenego - ILC-CFS and CLIC-CES groups
 - Standardization methods to estimate cost of warm magnets including cabling and power supplies – ***Braun & Garbincius gathering materials, but international magnet fabrication experts – are just not available! - defer***
 - Description of cost risk assessment – ***Lebrun, Riddone, Lehner, Garbincius reviewed other applications, started outlining this mgt – outline soon!***

CLIC/ILC Costing Garbincius summary slide at TILC09



CLIC / ILC Collaboration

- The next step to making the most of the growing joint ILC / CLIC collaboration will be pursued at CERN next month.
 - **We will hold a one day face-to-face meeting of our GDE Executive Committee at CERN**
 - **We will have a joint meeting with between the CLIC Extended Steering Committee and the GDE Executive Committee the second day. Rolf Heuer will participate.**
 - **Our ILC communicators will meet at CERN and explore joint communications.**



PAC Oct08 Recommendations

- General

- The PAC views very positively the recent start of common activities between the ILC and CLIC on many items such as conventional facilities, beam delivery system, detectors, physics, cost estimation, etc. This avoids unnecessary duplication of effort, and keeps the particle physics community focused on the goal of a linear collider as the next major new facility for the field.

- Accelerator

- **The PAC believes that the appointment of the three Project Managers, and the formation of the Accelerator Advisory Panel (AAP) for internal advice to the GDE Director, significantly strengthen the GDE organization as it moves into the Technical Design Phase.**
- The current TDP schedule, with reporting dates of 2010 and 2012, is fixed by outside constraints, and the PAC concurs with the result.
- The GDE is to be commended for its efforts to bring about worldwide collaboration among labs on SCRF, BDS, DR, etc. The ILCSC should support the international use of test facilities such as CESR/TA, TTF/FLASH, ATF2, STF, ILCTA_NML, and others.



The Project Management

- **GDE has been reorganized around a GDE Project Management Office to reach this goal**
- **Project Managers: Marc Ross, Nick Walker and Akira Yamamoto**
 - **Central management being given the authority to set priorities and coordinate the work**
 - **Resources for the technical design and associated R&D are limited, but program goals have been keyed to our best estimate of available resources.**
 - **Anticipate LHC results by about 2012 when we plan to be ready to pursue a robust proposal to our governments**
 - **Investments are needed toward Industrialization and siting**



Project Management Plan

ILC Project Management Plan for the Engineering Design
(ED) Phase

International Linear Collider Project Management Team
M Ross, N Walker, A Yamamoto, Project Managers

Purpose

This document describes the organization and processes that will be used to complete the Engineering Design Phase of the ILC Global Design Effort.


As the project progresses, the Project Management Plan will be periodically reviewed, and subsequently revised as needed.

Release 2.0 dated 15 Oct 2007.

<http://ilcdoc.linearcollider.org/record/11980>



GDE Organization Chart





AAP on Project Planning

- “Maintaining project-style control of the work is hampered by the distributed nature of the personnel, the lack of direct control of the budget, the lack of control of the assignment and utilization of personnel and the challenge to profit from facilities with objectives that only partially overlap with those of the ILC.”
- Nevertheless, they recommend:
 - *“The AAP suggests that the following linked strategies would be helpful in sharpening the focus of the GDE effort: a) reserve, and protect, more time for the GDE Director and the troika to formulate and agree upon project objectives b) actively and visibly (to the GDE team at large) rebalance the objectives so that they are more focused on the milestone-related goals and less emphasize an ever broadening R&D program c) take active steps to create, and support broad and coherent ownership of the core goals.”*



PAC Oct08 Recommendations

- General

- The PAC views very positively the recent start of common activities between the ILC and CLIC on many items such as conventional facilities, beam delivery system, detectors, physics, cost estimation, etc. This avoids unnecessary duplication of effort, and keeps the particle physics community focused on the goal of a linear collider as the next major new facility for the field.

- Accelerator

- The PAC believes that the appointment of the three Project Managers, and the formation of the Accelerator Advisory Panel (AAP) for internal advice to the GDE Director, significantly strengthen the GDE organization as it moves into the Technical Design Phase.
- **The current TDP schedule, with reporting dates of 2010 and 2012, is fixed by outside constraints, and the PAC concurs with the result.**
- The GDE is to be commended for its efforts to bring about worldwide collaboration among labs on SCRF, BDS, DR, etc. The ILCSC should support the international use of test facilities such as CESR/TA, TTF/FLASH, ATF2, STF, ILCTA_NML, and others.



R&D Plan - Technical Design Phase



- “Living Document”
- A 60 page document with details of all R&D programs, schedules and resources.
- **New: Release 3**
- Technical Design Phase
 - Phase 1 2010 (critical R&D demonstrations; new baseline)
 - Phase 2 2012 (technical design and implementation plan → construction proposal ready)



Major Milestones for TDP 1

SCRF

- High Gradient R&D - globally coordinated program to demonstrate gradient by 2010 with 50% yield;

ATF-2 at KEK

- Demonstrate Fast Kicker performance and Final Focus Design

Electron Cloud Mitigation – (CesrTA)

- Electron Cloud tests at Cornell to establish mitigation and verify one damping ring is sufficient.

Minimum Machine Studies (Cost/Performance)

- Studies of possible cost reduction designs and strategies for consideration in a re-baseline in 2010




R&D Test Facilities Deliverables

Test Facility	Deliverable	Date
<i>Optics and stabilisation demonstrations:</i>		
ATF	Generation of 1 pm-rad low emittance beam	2009
ATF-2	Demonstration of compact Final Focus optics (design demagnification, resulting in a nominal 35 nm beam size at focal point).	2010
	Demonstration of prototype SC and PM final doublet magnets	2012
	Stabilisation of 35 nm beam over various time scales.	2012
<i>Linac high-gradient operation and system demonstrations:</i>		
TTF/FLASH	Full 9 mA, 1 GeV, high-repetition rate operation	2009
STF & ILCTA-NML	Cavity-string test within one cryomodule (S1 and S1-global)	2010
	Cryomodule-string test with one RF Unit with beam (S2)	2012
<i>Electron cloud mitigation studies:</i>		
CESR-TA	Re-configuration (re-build) of CESR as low-emittance e-cloud test facility. First measurements of e-cloud build-up using instrumented sections in dipoles and drifts sections (large emittance).	2008
	Achieve lower emittance beams. Measurements of e-cloud build up in wiggler chambers.	2009
	Characterisation of e-cloud build-up and instability thresholds as a function of low vertical emittance (≤ 20 pm)	2010




Design / Cost Reduction / PIP





Technical Design Phase and Beyond



- **The AAP points to uncertainties beyond 2012 in their conclusions:**
 - “Some aspects of the R&D for the ILC will have to continue beyond 2012.”
 - “The milestone 2012 is however timely placed. The LHC will be providing operating experience of a large facility and with some luck the first physics discoveries will emerge.”
 - “The HEP community is thus well prepared for the decision for the next facility. In a sense the construction of the ILC seems the natural evolution of that process, in which case the efforts for the ILC have to be ramped up without delay.”
 - “Nature may be less kind or science policy makers not ready for a decision on the next big HEP project. In this case the large community must be engaged to facilitate the decision for the construction of the next HEP project.”
- **We need to prepare for uncertainties in the path to the ILC after 2012**



PAC Oct08 Recommendations

- General

- The PAC views very positively the recent start of common activities between the ILC and CLIC on many items such as conventional facilities, beam delivery system, detectors, physics, cost estimation, etc. This avoids unnecessary duplication of effort, and keeps the particle physics community focused on the goal of a linear collider as the next major new facility for the field.

- Accelerator

- The PAC believes that the appointment of the three Project Managers, and the formation of the Accelerator Advisory Panel (AAP) for internal advice to the GDE Director, significantly strengthen the GDE organization as it moves into the Technical Design Phase.
- The current TDP schedule, with reporting dates of 2010 and 2012, is fixed by outside constraints, and the PAC concurs with the result.
- **The GDE is to be commended for its efforts to bring about worldwide collaboration among labs on SCRF, BDS, DR, etc. The ILCSC should support the international use of test facilities such as CESR/TA, TTF/FLASH, ATF2, STF, ILCTA_NML, and others.**



ILC R&D Facilities and Program

- The ILC facility based R&D program, integrated into R&D programs at our large collaborating laboratories have been the “engine” that has enabled us to make substantial progress, even during difficult times.

- Highlights:

SCRF

- **Beam tests at FLASH (DESY); preparations for STF and ILCTA**


ATF-2 at KEK



- **Demonstrate Fast Kicker performance and Final Focus Design**

Electron Cloud Mitigation – (CesrTA)

- **Electron Cloud tests at Cornell to establish mitigation and verify one damping ring is sufficient.**



Beam Tests



				FLASH design	FLASH experiment
Bunch charge	nC	1	3.2	1	3
# bunches		3250*	2625	7200*	2400
Pulse length	μ s	650	970	800	800
Current	mA	5	9	9	9

- DR has a flexible race track design
 - 6.4 km Circumference with >1 km straights, which contain, RF, Wigglers, Chicanes, Injection/ Extraction Systems


- There are two critical components which require a successful demonstration in TDP1
 - **Fast Inj/Ext Kickers**
 - **Suppression of e- Cloud in the e+ ring**






Fast Kicker R&D Program

- There are presently four strands to the R&D program:
 - **SLAC/LLNL**: Development of fast high-power pulsers based on MOSFET technology.
 - **SLAC/DTI**: Development of fast high-power pulsers based on DSRD (drift step recovery diode) technology.
 - **INFN-LNF**: Tests of fast kickers in DAΦNE.
 - **KEK**: Tests of fast kickers in the ATF.




Tests of MOSFET-based pulser show promising performance.



Booster: 1/3 of modified LLNL board at 300V


- 4 ea APT MOSFETs
- $I_{max}=32A$ per MOSFET
- $t_p=45$ nsec

Tests of DSRD-based pulser using board based on LLNL design (for MOSFET inductive adder). Performance is limited by board design and components.



KEK-B Clearing Electrodes

CESR reconfigured to have 12 damping wigglers located in zero dispersion regions for ultra low emittance operation.





ATF / ATF2 R&D Program and Goals

- Beam delivery system studies
 - Demonstrate ~ 50 nm beam spot by 2010
 - Stabilize final focus by 2012
- Broad international collaboration (mini-ILC) for equipment, commissioning and R&D program



ATF2 Beam Line vacuum pipe connected in October

Commissioning underway




PAC Oct08 Recommendations

Accelerator (continued)

- **The PAC is very positive about the GDE concept of plug compatibility, especially for SC cavities. It notes that GDE will need to monitor the large flexibility that this concept could allow.**
- **The S1 test organization appears to be a success, and the PAC looks forward to hearing of progress and a schedule for S2.**
- **The PAC endorses research on SC cavity processing, and also notes the importance of obtaining good statistical data; this will be helped by the experience which will be obtained on the XFEL project construction.**
- **The flow of information on SC cavity processing and tests between labs is strongly encouraged. The same is true for information from industry, although the PAC acknowledges the difficulties that may arise in this case.**
- **The PAC notes with interest the recent GDE efforts on a “Minimum Machine” and cost-reduction; it welcomes the study of the single-tunnel concept, and other studies on simplifications to the accelerator facility. While cost reduction is important, the PAC notes that this may not necessarily be desirable if it leads to more risk, or precludes some future options such as eventually achieving the beam current specification or 1 TeV operation.**



The Role of Plug Compatibility



B. Foster
Governance Talk




Cryomodule Assembly

Plug Compatible Approach

<u>Cryomodule costs (RDR)</u>	<u>fraction</u>	<u>sum</u>
Cavity Fabrication	36%	36%
Power Couplers	10%	46%
Helium Vessel Fabrication	8%	54%
Magnetic Package (Quad)	7%	61%
Tuners	7%	68%
Assembly, Testing, Transport	5%	72%

(Next 7 items – to 1% level (22%)– Vacuum vessel, shields, interconnect, processing, dressing, pipes, supports, instrumentation)

- Cavity integration and the String Test globally organized with tests to be done at KEK STF facility
 - 2 cavities from DESY and Fermilab
 - 4 cavities from KEK
 - Each half-cryomodule from INFN and KEK





PAC Oct08 Recommendations

Accelerator (continued)

- The PAC is very positive about the GDE concept of plug compatibility, especially for SC cavities. It notes that GDE will need to monitor the large flexibility that this concept could allow.
- **The S1 test organization appears to be a success, and the PAC looks forward to hearing of progress and a schedule for S2.**
- The PAC endorses research on SC cavity processing, and also notes the importance of obtaining good statistical data; this will be helped by the experience which will be obtained on the XFEL project construction.
- The flow of information on SC cavity processing and tests between labs is strongly encouraged. The same is true for information from industry, although the PAC acknowledges the difficulties that may arise in this case.
- The PAC notes with interest the recent GDE efforts on a “Minimum Machine” and cost-reduction; it welcomes the study of the single-tunnel concept, and other studies on simplifications to the accelerator facility. While cost reduction is important, the PAC notes that this may not necessarily be desirable if it leads to more risk, or precludes some future options such as eventually achieving the beam current specification or 1 TeV operation.



Global R&D Plan

Consensus in SCRF-TA

Calendar Year	2007	2008	2009	2010	2011	2012
Technical Design Phase	TDP-1			TDP-2		
Cavity Gradient R&D to reach 35 MV/m		Process Yield > 50%		Production Yield > 90%		
Cavity-string test: with 1 cryomodule			Global collab. <31.5 MV/m>			
System Test with beam 1 RF-unit (3-modulce)		FLASH (DESY)			STF2 (KEK) NML (FNAL)	

Akira Talk



PAC Oct08 Recommendations

Accelerator (continued)


- The PAC is very positive about the GDE concept of plug compatibility, especially for SC cavities. It notes that GDE will need to monitor the large flexibility that this concept could allow.
- The S1 test organization appears to be a success, and the PAC looks forward to hearing of progress and a schedule for S2.
- **The PAC endorses research on SC cavity processing, and also notes the importance of obtaining good statistical data; this will be helped by the experience which will be obtained on the XFEL project construction.**
- The flow of information on SC cavity processing and tests between labs is strongly encouraged. The same is true for information from industry, although the PAC acknowledges the difficulties that may arise in this case.
- The PAC notes with interest the recent GDE efforts on a “Minimum Machine” and cost-reduction; it welcomes the study of the single-tunnel concept, and other studies on simplifications to the accelerator facility. While cost reduction is important, the PAC notes that this may not necessarily be desirable if it leads to more risk, or precludes some future options such as eventually achieving the beam current specification or 1 TeV operation.



Figure 1.2-1: A TESLA nine-cell 1.3 GHz superconducting niobium cavity.

- Achieve high gradient (35MV/m); develop multiple vendors; make cost effective, etc
- Focus is on high gradient; production yields; cryogenic losses; radiation; system performance

Cavity Gradient



- Akira – progress and plans toward establishing cavity gradient for TDR



Diagnostics -- Optical Inspection

For visual inspection of cavity inner surface.

motor & gear for mirror


camera & lens

~600µm beads on Nb cavity



perpendicular illumination by LED & half mirror

tilted sheet illumination by Electro-Luminescence



Iwashita (Kyoto) and Hayano (KEK) et al.

Camera system (7µm/pix) in 50mm diameter pipe.


sliding mechanism of camera

DESY starting to use this system in cooperation with KEK

Thermometry for Local Hotspots




A 2-cell thermometry system for ILC 9-cell cavity was designed, built and commissioned at JLab to study defects




“Hot-spots” were detected near the equator weld of one of the cells, causing the Q-drop

JLab



Cryomodule Gradient Progress



ILC operation :

- $\langle 31.5 \rangle$ MV/m spec
- (27 MV/m achieved at DESY/FLASH)
- (29 MV/m achieved DESY test stand)

•20 % improvement required for ILC





PAC Oct08 Recommendations

Accelerator (continued)

- The PAC is very positive about the GDE concept of plug compatibility, especially for SC cavities. It notes that GDE will need to monitor the large flexibility that this concept could allow.
- The S1 test organization appears to be a success, and the PAC looks forward to hearing of progress and a schedule for S2.
- The PAC endorses research on SC cavity processing, and also notes the importance of obtaining good statistical data; this will be helped by the experience which will be obtained on the XFEL project construction.
- **The flow of information on SC cavity processing and tests between labs is strongly encouraged. The same is true for information from industry, although the PAC acknowledges the difficulties that may arise in this case.**
- The PAC notes with interest the recent GDE efforts on a “Minimum Machine” and cost-reduction; it welcomes the study of the single-tunnel concept, and other studies on simplifications to the accelerator facility. While cost reduction is important, the PAC notes that this may not necessarily be desirable if it leads to more risk, or precludes some future options such as eventually achieving the beam current specification or 1 TeV operation.

ILC Global Design Effort Project Manager visit to SCRF cavity manufacturers

February - March 2009

In early 2009 the ILC Global Design Effort Project Managers (Akira Yamamoto, Marc Ross, and Nick Walker) visited and were graciously hosted by many of the world's top superconducting RF cavity manufacturers. The objective of the visit was to:

1. Learn industrial status and possible future at cavity manufacturers.
2. Communicate the ILC GDE Technical Design Phase R&D Plan.
3. Request further industrial R&D effort, particularly to improve "field gradient" and "cost effective production" in order to prepare for the industrialization (mass production).
4. Establish close communication and a confident relationship between ILC GDE and vendors.

This web page is intended to capture the material presented to vendors and to include key references.

[Global R&D Effort of SCRF Cavity Development for the International Linear Collider](#) (pdf, 5Mb, English)

[Global R&D Effort of SCRF Cavity Development for the International Linear Collider](#) (pdf, 20Mb, Japanese)

Akira Yamamoto, Marc Ross, and Nick Walker - Project Managers for the ILC Global Design Effort, material presented to each of the SCRF cavity manufacturers.

[Superconducting RF Cavity Development for the International Linear Collider](#) (pdf, 4Mb)

Akira Yamamoto for the ILC Global Design Effort, paper presented at Applied Superconductivity Conference 2008 (ASC 2008).

[Global R&D effort for the ILC linac technology](#) (pdf, 4Mb)

Akira Yamamoto for the ILC Global Design Effort, paper presented to EPAC 2008.



Reference Design Report

[Download the full report](#)

Volume 3 - Accelerator: [Download the pdf](#) (20MB)



ILC Research and Development Plan for the Technical Design Phase

[Download the pdf](#)

(Last updated: 25 February 2009)




PAC Oct08 Recommendations

Accelerator (continued)

- The PAC is very positive about the GDE concept of plug compatibility, especially for SC cavities. It notes that GDE will need to monitor the large flexibility that this concept could allow.
- The S1 test organization appears to be a success, and the PAC looks forward to hearing of progress and a schedule for S2.
- The PAC endorses research on SC cavity processing, and also notes the importance of obtaining good statistical data; this will be helped by the experience which will be obtained on the XFEL project construction.
- The flow of information on SC cavity processing and tests between labs is strongly encouraged. The same is true for information from industry, although the PAC acknowledges the difficulties that may arise in this case.
- **The PAC notes with interest the recent GDE efforts on a “Minimum Machine” and cost-reduction; it welcomes the study of the single-tunnel concept, and other studies on simplifications to the accelerator facility. While cost reduction is important, the PAC notes that this may not necessarily be desirable if it leads to more risk, or precludes some future options such as eventually achieving the beam current specification or 1 TeV operation.**




Identified Minimum Machine Elements




See Ewan Paterson Presentation


Main Linac & Support Tunnel



- RDR (two-tunnel)
 - Access to equipment during ops
 - Reliability/availability



- Shallow sites
 - Cut and cover like solutions
 - “service tunnel” on the surface



- Single tunnel
 - European XFEL-like solution
 - availability / reliability



Additional Remarks

- Definition of the Technical Design Report
- Work toward Project Implementation Plan
- Detector LOIs and Machine Detector Interfaces



Technical Design Report

- What will it be?
 - **Cost performance optimized technical design**
 - **It will include new “value” estimate**
 - **It will include a project implementation plan**
- Who will it be for?
 - **It will be a detailed design and project plan ready for serious consideration by potential collaborating governments.**
- What it will not be?
 - **It will not be a complete engineering design with drawings, etc.**




Technical Design Report

- What about LHC results?
 - The LHC will need to be a success technically (energy, luminosity and duty cycle)
 - LHC science will need to ‘validate’ the science case.
- Who about CLIC?
 - Joint work with CLIC will help make technical, cost and readiness comparisons possible, if needed.
 - Will LHC points to a ~ 1 TeV machine?
- Will our job be done? (What happens after 2012?)
 - Continuing R&D demonstrations, ADC and industrialization
 - Funding could become more difficult, without a potential project is in sight.



Project Implementation Plan (PIP)




- Brian Foster leads the GDE governance group
 - Examining the main recent projects approved/in preparation: ALMA, FAIR, ITER, SKA, XFEL...
 - Contact made with key individuals in projects. Information gathered and presented.
 - E.g. on funding - 2 main models for funding: Host (~50%) + regional contributions (2 x~25%) or Host (~50%)+member states (n x~10%) (ITER). Balance of in-kind/cash?



IR Integration


CHALLENGES:

- Optimize IR and detector design ensuring efficient push-pull operation
- Agree on Machine-Detector division of responsibility for space, parameters and devices




LOI Process is Crucial

“PUSH – PULL” Interaction Region for two detectors



Underground Cavern Design Study



Enabling the next phase of designing a feasible system to practically switch between detectors



Summary / Conclusions

- We are on track to be able to ready to propose the ILC on a time scale of ~2012 (or before!)
 - **GDE R&D demonstrations**
 - **Cost/risk/performance optimized design concept**
 - **Detector LOIs → Machine Detector Interfaces**
 - **Re-baseline (2010)**
 - **Technical Design Report (end of 2012)**
 - **Project Implementation Plan**

 - **LHC results to motivate the project**
 - **Outreach to generate support from science community, funding agencies, etc**