

# ART and the Fermilab Program

**Bob Kephart**

## Mission:

- **Work with the GDE Americas Regional Team (ART) to develop the ILC design & gain approval of the project**


## Goals:

- Participate in the Technical Design Phase (TDP)
- Participate in Accelerator Physics, Conventional Facilities Design, and global systems work to further develop the ILC design
- Work towards GDE SRF goals
  - S0: Cavity gradient of 35 MV/m; good yield
  - S1: Cryomodules with average gradient  $> 31.5$  MV/m
  - S2: One or more ILC RF unit with ILC beam parameters
- Perform R&D and value engineering to reduce costs
- Become a trusted international partner

- **Accelerator Physics and Beam Design**
- **Conventional Facilities Systems**
- **Global Systems – Instrumentation, LLRF, Cryogenics, Controls, etc**
- **SRF Cavity and Cryomodule development**
  - Majority of effort
- **Host the Americas GDE “office”**

## New intense Proton Source at Fermilab, endorsed by HEPAP

- 2 MW of beam power over the range 60 – 120 GeV
- Simultaneous 150 kW of beam power at 8 GeV; Upgradable to 2-4 MW
- Based on 8 GeV SRF based “ILC-like” Linac (Synergy!)
- FNAL pursuing both Energy & Intensity Frontiers in parallel (ILC, Px)



# FNAL SRF Program (related)

Funded under a separate B&R and not formally part of this review

## Mission:

- **Develop SRF infrastructure at FNAL and perform R&D to master the technology for future accelerator projects (e.g. ILC or Project X)**

## Goals:

- **Master fabrication & processing of cavities & cryomodules**
- **Build SRF infrastructure that is difficult for industry to provide**
  - Large cryogenic & RF systems, cavity & cryomodule testing systems, etc.
- **Operate facilities to acquire required expertise**
- **Transfer SRF technology to U.S. industry**
- **Participate in national & international collaborative SRF R&D**

# SRF R&D Scope of Work

- Develop & Operate SRF infrastructure
  - Joint ANL/FNAL Processing Facility
  - Vertical Test Systems (VTS)
  - Cavity & Cryomodule Assembly Facility (CAF)
  - Horizontal Test Systems (HTS)
  - RF unit Beam Test Facility (ILCTA\_NML)
  - Stand-alone Cryomodule Test Stand (CTS)
- Purchase cavities (ILC only provides cryomodule parts)
- Provide infrastructure for generic SRF Material R&D
- **FNAL SRF infrastructure plan reviewed by DOE in Feb 07**
  - Focused on infrastructure for ILC 1.3 GHz elliptical cavities
  - Changing scope... now support industrialization of SRF
  - Revised U.S. HEP priorities include Project X @ FNAL and ILC on a slower time line... but large overlap of Px and ILC goals
- **DOE review of FNAL SRF program scheduled for May 18-19.**
- Related SRF programs include Project X, HINS, and 3.9 GHz R&D

- Synergy (by design)
  - e.g. ILC R&D supports Px since they employ similar cavities & CM
  - SRF efforts often share common personnel and infrastructure.
- SRF at Fermilab including SRF for ILC is managed as an integrated whole
  - Allows for rational cost sharing & efficiencies

~~X~~ means ILC used to fund this prior to FY08 Omnibus bill

Funding source	ILC B&R Beta=1	SRF B&R Beta=1	ARRA B&R Beta=1	Px RD&D Beta=0.8	HINS Spoke	3.9 GHZ
B&R KA15 -	02 02-1	02 01-2	?		02 01-1	

### Component Development

Cavity Development	<del>X</del>	X	X	X	X	X
Couplers (ILC@SLAC)	X		X	X	X	X
<b>Tuners</b>	X		X		X	X
Cavity Dressing	X		X		X	X
<b>Cryomodules</b>	X		X	X	X	X
RF CM distribution(SLAC)	X		X			

### Infrastructure Fabrication

Cavity Infrastructure	<del>X</del>	X	X		X	X
Vertical Test Systems	<del>X</del>	X	X			X
Horizontal Test System	<del>X</del>	X	X			
Cryomodule Assembly	<del>X</del>	X			X	
EP processing ANL/FNAL & JLAB	<del>X</del>	X	X			
RF unit Test Facility (NML)		X	X			
NML buildings and new cryoplant			X			
SRF materials infrastructure		X				
Spoke Resonator & 3.9 BCP@ANL		X			X	X
325 MHz VTS for Spokes					X	
Spoke Resonator HTS					X	
Cryomodule test stand		X				

### Facilities Operations

EP & BCP processing ANL	X			X	X	X
EP processing & VTS @JLAB	X			X		
Industrial EP & alternate processing			X			
Bare cavity test (VTS)	X			X		X
Cavity Dressing	X			X	X	X
Dressed cavity Test (HTS)	X			X		X
Cryomodule Assembly	X			X	X	
Cryomodule test		X		X		
RF unit test		X				
SRF materials and EP Dev.		X				
Spoke Resonator Vertical Test					X	
Spoke Resonator HTS					X	

# Accomplishments

- **Effort In FY08 obviously limited by FY08 Omnibus Bill**
- **Accelerator Physics and Beam Design**
  - Participated in the global effort to design the machine
  - Simulation of emittance preservation in RTML and Main Linac
  - Studies of kick due to RF coupler and effects on emittance
  - Single stage bunch compressor simulation
- **Conventional Facilities Systems**
  - Lead the U.S. and Global effort for CFS
  - Value engineering and cost reduction for the baseline design
  - Evaluated alternative tunnel configurations (single, shallow)
- **Global Systems**
  - Built/ installed 20 high resolution ( $<5 \mu$ ) BPM's for ATF
  - Developing new cold cavity BPM's for ILC cryomodule
  - Wire Position Monitors, BPM, Faraday cups etc for CM1 @NML
  - LLRF: 9 ma studies @ FLASH, Built HOM readout electronics
  - Contributed to global effort to design ILC cryogenic systems



# Accomplishments

- Despite funding turmoil, good progress on SRF technology at FNAL with the funds supplied by the ILC & SRF B&R in 1st quarter and other KA15 B&R funds (3.9 GHz, HINS, Project X)
- FNAL has several new SRF facilities now in full operation
  - New Vertical Test Stand; tests bare cavities (35 tests in FY08-09)
  - New Horizontal Test Stand; tests dressed cavities (5 tests in FY08)
  - Cryomodule Assembly Facility; 2 CM assembled in MP9 & ICB
- Other Infrastructure was delayed substantially by Omnibus
  - Infrastructure to dress 1.3 GHz nine-cells (1<sup>st</sup> nine-cell this month)
  - ANL/FNAL Joint EP Processing; commissioning,(10 single cell tests)
  - RF unit test facility at New Muon Lab; under construction
  - 8-12 month delays due to Omnibus and FY09 CR

# Accomplishments

- FNAL has built a variety of SRF components
  - Cavities: 48 ordered, 22 from U.S. industry
  - Cryomodules: Assembled 2 cryomodules with CAF
    - CM1 = Type III<sup>+</sup> assembled from DESY kit of parts
    - Designed/assembled a 3.9 GHz CM for DESY
    - Parts in hand for cold mass of a 2<sup>nd</sup> type III<sup>+</sup> CM... need dressed cavities
    - Type IV CM design ~ complete and ordering parts in FY09
- SRF Materials program established
  - Single-cell program for U.S. cavity vendor development
  - EP process development for ANL/FNAL joint system
  - Improved diagnostics (thermometry, optical insp)
  - Understanding reasons for poor performers (weld pits)

# Accomplishments

- Industrialization (was ILC funds → SRF funds)
  - ILC cavities built by U.S. vendors (AES, Roark/Niowave)
  - Engaging several industrial vendors in cavity surface processing
  - Engaging several U.S. vendors to produce type IV CM parts
  - Limited by funding but ARRA funds will help this a lot
- Extensive network of collaborations ( mostly SRF Technology )
  - MOU's with 18 institutions
- Host the Americas Regional office of GDE
  - FNAL personnel in key GDE positions: Ross, Kerby, Garbincius, Champion, Mitchell, Carter, Kuchler, etc
  - Offices, admin support, PM salaries, travel, etc



# ANL/FNAL Joint EP Facility

Americas

Facility being commissioned (~ 1yr Omnibus Delay)

Provides complete processing of 1.3 GHz cavities: electro-polishing, ultrasonic cleaning, high-pressure rinse, assembly

Expect significant contribution of ANL/FNAL joint facility to ILC R&D in next yr



- Practice run with 9 cell cavity
- 10 single-cell EP processes complete with excellent performance  $>30$  MV/M
- Plan 1<sup>st</sup> real attempt on 9-cell with full facility imminent





New Ultrasonic cleaning system



New High-pressure rinse system


- 35 cavity tests in FY08/FY09, where “test” = cryogenic thermal cycle
  - 9-cell & single-cell elliptical cavities, and a SSR1 HINS cavity
  - instrumentation development, variable coupler, thermometry, cavity vacuum pump system, cavity vendor development
  - Cavity tests dedicated to ANL/FNAL CPF commissioning





# Vertical Test System

Americas



1-cell thermometry



900 sensors/cell!  
but multiplexed





Two single cells



325 MHz Spoke

- **Upgrades in progress**
  - 9-cell thermometry
  - Two more vertical dewars
  - More top plates
  - Improved cryogenics
  - Increased throughput 15 → 250 tests/yr




# Horizontal Test Stand

- Tests Dressed Cavities with Pulsed RF Power
  - as they will see in a cryomodule
- Fully commissioned in FY08 and in operation
- In FY08-09:
  - Tested one 1.3 Ghz Cavity
  - Tested five dressed 9-cell 3.9 GHz cavities for DESY
- Will be used to qualify dressed 1.3 GHz cavities in 2009



# MDB Infrastructure








# Cryomodule Assembly Facility

Americas

- Goal: Assemble R&D Cryomodules
- Where: MP9 and ICB buildings
  - MP9: 2500 ft<sup>2</sup> clean room, Class 10/100
  - Cavity dressing and string assembly
  - ICB: final cryomodule assembly
- Infrastructure:
  - Clean Rooms, Assembly Fixtures
  - Clean Vacuum, gas, water & Leak Check
- DESY Cryomodule “kit” assembled



**ICB clean: Final  
Assembly fixtures installed**



**MP9 Clean Room**



**String Assembly**



**Cavity string for 1<sup>st</sup> CM**

# 1<sup>st</sup> FNAL built Cryomodules



**Cryomodule 1  
From DESY kit**



**3.9 GHz Cryomodule  
Designed/built at FNAL  
for DESY**

Not ILC funding but  
supports ILC effort

# FNAL Cryomodule 2

- Goals

- Build a cryomodule completely equipped with cavities processed in the U.S (ILC funds)
- 1<sup>st</sup> attempt to achieve ILC S1 goal of 31.5 MV/m average gradient in a CM
- Cavities equipped with INFN blade tuners

- Eight cavities are good candidates for CM 2

- Average gradient in VTS is 36.5 MV/m

- Final cavities used will be selected based on upcoming process & test results

- CAF(MP9) will be used to Dress cavities


- 1<sup>st</sup> dressed cavity this month

- Goal: Cryomodule 2 assembled late 2009

Vendor	Cavity #	Gradient (MV/m)
ACCEL	6	37.8
	8	31.7
	11	40.0
	12	37.0
	13	44*
	14	44*
AES	2	32.8
JLab	J2	30.0
Average		37.2

\* preliminary: based on last process/test result at Jefferson Lab

# RF Unit Test Facility at NML



- **Overall Plan:** Test RF units: Px, ILC S1 & S2 goals
  - ILC: 3 CM, Klystron, Modulator, LLRF
  - Move A0 Injector to provide ILC like beam
- **New Tunnel Extension:** design to allow 2nd RF unit, diagnostic beam lines, AARD facility
- **New Building:** Cryoplant, Cryomodule Test Stands

# 1<sup>st</sup> Cryomodule moving to NML



Note: NML is funded completely with SRF funds  
Nevertheless, still an important facility for ILC R&D

# RF Unit Test Facility at NML




# Progress at NML



1st Cryomodule Test fit




CM Feed Can



Large Vacuum Pump



Control Room





Capture Cavity II @ NML




He Refrigerator

- Lots of activity !
- Understand/improve EP
- New better diagnostics
- Thermometry, optical insp
- Breakthroughs in understanding!
- Pits near EB welds → cavity quench
- Can reproduce pits in small Nb samples
- Goal = Prevention!
- But... also exploring repairs
- E.g. Laser remelting of pit



Laser welding machine



Pit repaired?

Partially funded by ILC funds




# FY08-09 ILC Funding

- FY08 Omnibus Bill cut ILC funding to 25% of plan ¼ of the way through the FY
- SRF cut to 20% → All work infrastructure stopped Dec 07
- ILC/SRF workforce was dispersed (138 FTE)
- Work on ILC essentially stopped (2.5 FTE)
  - ~\$ 1 M unspent ILC M&S funds, cavity processing at JLAB and VTS at FNAL
- SRF contingency & FY08 supplemental kept JLab, NML, & cavity vendors alive
  
- In FY09: \$ 11.2 M of ILC funds to FNAL
  - Plus \$ 1.7 M to support the GDE office
  - This allowed a restart of the ILC R&D program
  - However CR Sep 08-Mar 09 → M&S limited to 60% of plan
  - Still have not received full allocation from OHEP (\$ 10. 3 M as of April)
- In FY09: \$ 22.8 M to build SRF infrastructure & perhaps ARRA funds
- Workforce has been restored to 75 FTE (but a struggle)
  - 23 FTE on ILC, 52 on SRF: Making up shortfalls with contract workers & guests
  - Expect 3.9 GHz effort to wind down this month (another 11 workers)
- FY08 omnibus/CR was very disruptive... cost us ~ 1 year in many places

# FY08-09 ILC/SRF Labor

## FTE versus Time



# Has the Program Efficiently Recovered?

- **No!** The post-omnibus ILC program is now much smaller and envisioned to be flat vs expected large growth each yr, some delays not recoverable
- **Not Yet:**
  - Had a cohesive workforce in place in Dec 08—scattered to other tasks
  - FY08 funding cuts at FNAL resulted in a significant staff reduction > 100 FTE
  - Change in Focus for US HEP program → a number of new near term projects now exist (e.g. NOvA, LBNE, Project X, Mu2e, etc)
  - It has been difficult to get our workforce back (→ hiring contract workers)
- **Issue:** Restoration of funds is not enough
  - FY08 Omnibus Bill → ILC credibility damaged; some people have not reengaged
  - Areas of overlap with possible near-term projects (SRF) much easier to sell than ILC global systems, value engineering, accelerator physics, etc.
- Nevertheless FNAL is reengaged on ILC & making progress
  - 3.9 Ghz & HINS efforts were invaluable in maintaining core of SRF workers through the “dark days” of FY08

- ILC community has good mechanisms for technically coordinating the R&D effort
- A variety of mechanisms are in place
  - International GDE meetings
    - ILC EC communicates its overall strategy for TDP
    - Labs envision their possible role
    - Good forums technical exchange of information
    - Also TTC, SRF, and PAC meetings
  - International Webex meetings
    - PM meetings ( e.g. Main Linac, Yamamoto)
    - S0 Meetings (cavity and gradient) etc
  - National meetings of ART (Mike Harrison)
    - Executive council (all U.S. institutions, often by WEBEX)
    - Quarterly/Annual Technical and Financial Progress reports
    - Annual budget planning (work closely with Mike)
  - DOE Reviews (like this one) + AAP, HEPAP, AAC, etc

- Coordination mechanisms (continued)
  - Face-to-face meetings
    - FNAL ILC Director (me) & ART Director ( Mike)
    - FNAL ILC Director & GDE Project Managers (e.g. Mark, Akira)
    - FNAL ILC Director & OHEP Program Manager (Gerry)
    - FNAL Directorate & GDE Directorate
  - Financial Coordination
    - ART Annual Financial Planning effort
    - OHEP communications to - Fermilab budget office
    - FNAL Annual Laboratory Budget presentation to OHEP
- Technical Planning OK, Financial mechanisms less than perfect
  - Often money in FNAL Fin plan does not match ART plan
  - ART Director and OHEP maintain reserves → if full ILC work force is in place, substantial M&S is not available until late in fiscal year
  - ILC funding guidance from OHEP to FNAL CFO for lab annual budget plan often does not match numbers communicated by ART Director
  - All people well intended... process is just not very smooth

- For FNAL, the ILC R&D effort is part of a broader program of SRF development intended to allow FNAL first to capture the intensity frontier (with Project X) and later to recapture the energy frontier with ILC or a muon collider
- FNAL views SRF as an enabling technology (like SC magnets) likely to be used in all future HEP accelerators
- We have worked hard to maintain an integrated plan despite the funding turmoil of the past years
  - ARRA funds will provide the opportunity to substantially advance the program compared to our vision only a year ago
- ILC and SRF R&D provides broader benefits by developing high tech workforce at labs and in industry, and trains students via university collaborations

# Collaborations (18 MOU's)

- **ANL:** EP development and cavity processing
- **Cornell:** Cavity processing & test, materials R&D
- **DESY:** 3.9 GHz, cryomodule kit, FLASH
- **KEK:** Cavity R&D, ATF II
- **MSU:** Cavity cost reduction, hydroform, TIG
- **TJNL:** EP cavity processing and test
- **INFN:** tuners, HTS, NML gun cathodes
- **Triumf:** Vendor development
- **SLAC:** RF power, klystrons, couplers
- **CERN, DESY, KEK, INFN, etc:** Type IV CM design
- **India:** CM design, cavities, infrastructure, etc
- **China:** Peking U, IHEP, cavity development
- **UC,NW,NHMFL, Cornell, DESY, KEK,etc:** Materials

# Integrated ILC-Px SRF Plan

1.3 GHz Cryomodules							
U.S. Calendar Year	2008	2009	2010	2011	2012	2013	
<b>CM1 (Type III+)</b>							
Assembly	in FY07	OMNIBUS delay	install				
Test					CM1 test@NML		
<b>CM2 (Type III+)</b>							
Cav Processing + VTS							
Dressing & HTS							
Assembly				install			
Test					S1 Demo@NML		
<b>CM3 (Type IV)</b>							
Design & Order Cav & CM Parts	OMNIBUS DELAY	Des	Order Cav & CM parts				
Cav Processing + VTS							
Dressing HTS							
Assembly					install		
Test						S1 Demo@NML	
<b>CM4 (Type IV) ARRA</b>							
Design & Order Cav & CM Parts			Order Cav & CM parts				
Cav Processing + VTS							
Dressing HTS							
Assembly						install RF unit	
Test							S1 Demo + with beam
<b>CM5 (Type IV) ARRA (CM6 follows with same pattern)</b>							
Design & Order Cav & CM Parts			Order Cav & CM parts				
Cav Processing + VTS							
Dressing HTS							
Assembly						install	
NML ext and refrig building			Design	Construction			
NML Beam					Move injector		Beam Available
10 MW RF unit test	OMNIBUS DELAY						S2 RF unit test
<b>Px <math>\beta=0.8</math> CM (Project X, INDIA)</b>							
Design & Order Cav & CM Parts		Design	Order Cav & CM parts				
Cav Processing + VTS							
Dressing HTS							
Assembly							Install @ CTS
Test							test
<b>S1 Global ( 2 Cav )</b>							
Cav Processing + VTS							
Dressing & HTS?							

## New SRF Infrastructure Construction (with ARRA)

U.S. Calendar Year	2008	2009	2010	2011	2012	2013	
Nb Scan/Dress Cavity Upgrades		Design	Procure & Install				
Add Px CM Ass'y Capacity					Design	Procure & Install	
VTS 2 & 3 Upgrade ARRA	OMNIBUS DELAY	Design	Procure	install VTS2	VTS3	Operate VTS 1-3	
HTS 2 Upgrade (ARRA)				Design	Procure & Install	Operate	
NML Beam line ARRA	OMNIBUS DELAY	Design	Procure	install		Beam Available	
NML Refrigerator ARRA	OMNIBUS DELAY	Design	Procure		install	Operate	
CM Test Stand			Design	Procure (India)	install & RF	Operate	
ANL EP + upgrades ARRA	OMNIBUS DELAY	ANL EP	Operate	Design	Procure & Install @ANL & JLAB	Operate	



	Forecast	Actual
• <b>1.7 Conventional Facilities</b>		
– Complete Water and HVAC VE	Q4	Q3
– Main Linac Tunnel Alternative	Q4	Q4
– Minimum machine CFS conceptual Design	Q4	Q4
• <b>1.10 Cavities and Cryomodules</b>		
– Complete & commission ANL/FNAL processing facility	Q2	Q2/Q3
– 1 <sup>st</sup> dressed 1.3 GHz cavity tested	Q3	Q3
– Start Testing Cryomodule 1 at NML	Q3	Q4
– All Cryomodule 2 components available (except dressed cavities)	Q4	Q2
– Complete 8 dressed cavities for CM2	Q4	Q4 ?

Despite CR, doing well on milestones. Feed can for NML test of CM1 delayed, Test CCII first at NML to commission cryogenics system. 8 dressed cavities by Sept will be tough

# Summary

- **Fermilab has an active ILC R&D program**
- **FY08 omnibus cuts were disruptive, but we are recovering**
- **Despite Funding turmoil FNAL made considerable progress**
- **Significant contributions to global GDE program**
  - **Management, Accel Physics, machine design, global systems, cryogenic design, CFS, cost estimate, etc.**
  - **Major effort on SRF development**
- **Extensive SRF Infrastructure constructed and in operation, additional infrastructure under construction with SRF funds**
  - **Supports GDE S0, S1, S2 goals for ILC**
  - **Supports U.S. Industrialization of SRF technology**
- **Designing, Building, and Testing SRF components**
  - **Cavities, cryomodules, EP processing, SRF materials work, etc**
- **Integrated ILC/SRF effort at FNAL also supports Project X**
- **We have ambitious plans for FY09 and beyond**