



**XFEL**  
X-Ray Free-Electron Laser

**FLASH**  
Free-Electron Laser  
in Hamburg

# Preparing for AAP: TTF/FLASH 9mA Experiment



John Carwardine (ANL)  
25 February 2009



# What I believe I'm supposed to cover

- The presentation addresses the topic of 'Cryomodule String Test' (formerly S2)
- 9mA program goals, accomplishments, schedule, etc
  - **Short-term: demonstrate 9mA long pulses, high gradient**
  - **Longer-term (post FLASH upgrade)**
- Address how the 9mA program overlaps with TDP-2 goals outlined in the R&D Plan v3
  - **What could be addressed at FLASH in the TDP-2 timeframe (and what could not)**
  - **Capabilities and limitations of FLASH in the context of meeting the TDP-2 goals**



# R&D Plan v3 context

## Under Section 3.1.4: Cryomodule-string test

- *In the second stage, an extended linac test system containing multiple cryomodules and powered by a single klystron and RF power distribution system will be demonstrated. This is referred to as the 'cryomodule-string test'.*
- *The test will include beam acceleration and beam handling. This has been scheduled for the end of TD Phase 2 (2012).*



# R&D Plan v3 with respect to FLASH

- *The highest priority goal [for TDP-2]*
  - *to demonstrate beam phase and energy stability at nominal current, (including a test of beam based feedbacks)*
- *Secondary goals, which are important because of their potential impact on the cost of the ILC, are to:*
  - *demonstrate operation of a nominal section or RF-unit*
  - *determine the required power overhead under practical operating conditions*
  - *to measure dark current and x-ray emission*
  - *and to check for heating from higher order modes in order to determine the dynamic cryogenic heat load with full beam current operation.*



## R&D Plan v3 ... cont

- *Finally, there are a series of studies that are needed to understand main linac subsystem performance. These include:*
  - *developing RF fault recognition and recovery procedures*
  - *evaluating cavity quench rates and coupler breakdowns*
  - *testing component reliability, performing long term testing of cryomodules, (including thermal cycling)*
  - *assembling an actual tunnel mock up to explore installation, maintenance, and repair issues.*



## Comments on the goals for the talk

---

- Some aspects are relatively straight forward, eg describing the 9mA program
  - Some aspects are more difficult to address and will need discussion with PMs and DESY
  - There is overlap with other SCRF topics and with complementary string-test programs at Fermilab and KEK.
-



# Documents to post

- There is a myriad of documentation we could post, eg
  - **Technical description of FLASH**
  - **Initial proposal for the 9mA studies, presentations to FLASH Beam Allocation Committee, etc**
  - **Mini workshop in January, plans for Sept 09 studies**
  - **Studies reports, results, analyses,...**
  - **FLASH seminar talk from Dec 08**
  - **Report on the beam dump repair**
  - **FLASH upgrade plans, schedule, XFEL schedule**
- More thought is needed on the content of the presentation before we can reduce the list to something manageable.