ATF2 commissioning in Autumn 2009

for discussion

Philip Bambade LAL & KEK

on behalf of the commissioning team

Background material used:

- 1. Personal strategy for ATF2 beam operation in 2009
 - T. Okugi, July 22, 2009 ATF2 weekly meeting

http://ilcagenda.linearcollider.org/getFile.py/access?resId=1&materialId=slides&contribId=2&sessionId=1&subContId=0&confId=365-

- 2. Schedule plan of machine studies in October to December
 - P. Bambade, Y. Kamiya et al., P. Burrows, August 12, 2009 ATF2 weekly meeting

http://ilcagenda.linearcollider.org/conferenceDisplay.py?confld=3657

3. Presentations at June 2009 ATF2 project meeting

http://ilcagenda.linearcollider.org/conferenceDisplay.py?confld=3511

Commissioning periods

December 2008

→ 3 weeks

January – June 2009

 \rightarrow 14 weeks (=1+2+4+3+3+1)

October – December 2009

 \rightarrow 7 weeks (=2+2+3) planned

2010...

~ idem

NoW...

Beam time scheduling

→ 70% fraction for ATF2 & 4 + days per week operation add. days

Individual R&D tasks→ common goal

Groups: KEK, Tokyo, Sendai, SLAC, IHEP, UK, France, Spain, CERN,...


ATF2 educational function

Several PhD & young post-doc researchers in accelerator science

New hardware systems for ATF2

22 Quadrupoles, 5 Sextupoles, 3 Bends in downstream of QM16 (IHEP, China) (SLAC) (SLAC, IHEP)

All Q- and S-magnets have cavity-type beam position monitors(QBPM, 100nm). (PAL,KNU, Korea, and SLAC, RHUL for electronics)



Shintake Monitor (beam size monitor, BSM with laser interferometer):Tokyo univ. MONALISA (nanometer alignment monitor with laser interferometer):Oxford univ. Laserwire (beam size monitor with laser beam for 1μ m beam size, 3 axies):RHUL IP intra-train feedback system with latency of less than 150ns (FONT):Oxford univ.

Magnet movers for Beam Based Alignment (BBA):SLAC

High Available Power Supply (HA-PS) system for magnets: SLAC

Priorities for December 2008 – June 2009


- Radiation inspection @ KEK → get authorization
- Fast extraction kicker R&D in Damping Ring
- ATF2 hardware commissioning (magnets & instruments)
- Shintake monitor (BSM) commissioning & study
- Initial 1st order optics measurements (methods, software)

Commissioning \rightarrow gradual $\beta_{x,y}^*$ (demagnification) reduction paced by


beam tuning

instrumentation (BSM / other)

background study




Variable β_{IP} at ATF2



ATF2 Commissioning

First commissioning by screen monitors and raw signals of BPMs




December 2008

Vertical transfer matrix (ZV1X→ QD2A)




On-going: separate beam / instrumental variations & noise

Horizontal transfer matrix (ZH1X→ QD2A)



non trivial check! Final Doublet→ not yet "Flight Simulator"

Test of beam based alignment automated software tool in "Flight Simulator"



cavity BPM fixed on F.F. quad mounted on mover


BPMs on sextupoles and quads not on movers \rightarrow in progress


Phase space in extraction line


systematic "manual" BBA on selected quads
careful dispersion + coupling measurement & correction

"Flight Simulator" and V-system tools \rightarrow $\epsilon_{v} \sim 10-30$ pm reproducibly !

DR measures ~ 6 pm ATF2 nominal = 12 pm









Emittance and β mismatch during coupling reduction

Phase space at post-IP wire-scanner

28 May 2009



Tungsten, 10 µm diameter, 40 cm behind IP



- Minimum beam size ~ 10 μm is resolved
- Must subtract measured dispersion (nominal + anomalous)

$$\epsilon_x$$
 = 1.13 \pm 0.06 nm (design = 1.2 nm)
 β_x = 13 \pm 1 cm (design = 10 cm)

- cannot resolve $\sigma_v \sim 0.35 \ \mu m$
- subtract (anomalous) dispersion

use ε_y measured in extraction line $\rightarrow \beta_v \sim 1.4$ cm (design = 1.8 cm)


→ Basic check of optical transfer from DR → IP

IP σ_y minimization at post-IP wire-scanner

(5 /20) by using FF multi-knobs (sextupole movers)
5.8μm (5.8 ,6.1 ,5.5) -> 4.1μm (3.9, 4.2, 4.1)


- -Residual vertical dispersion was dominant for the vertical beam size
- Vertical dispersion was larger than correctable range for multi-knobs
- (5/26) All sextupoles off
 - QSs scan (skew-Q for vertical dispersion correction)
 - QKs scan (skew-Q for coupling correction)
 - QF6X scan (normal-Q for horizontal dispersion correction)

Effect of wire size (10 μ m diameter) is dominant




IP σ_x with BSM "laser wire" mode established

- -First Compton signal was observed in February.
- -Beam size and emittance measurement was done in May.
 - horizontal beam size at MW1IP was 20um.
 - laser beam size 10um assumed.
 - -fitted horizontal emittance was 2.5nm.



laser wire mode optics (horizontal measurement)



Fitte-d Energy Deposit

Goals for October - December 2009

- Continue fast extraction kicker R&D in Damping Ring
- Confirm large β^* optics ($\beta_{x,y}=8,1$ cm) \rightarrow towards sub- μ m σ_y
- First signal evidence in interference mode \rightarrow BSM σ_y measurement

Sub-goals

- New BSM hardware
- Carbon wire scanner at IP with 5 μm diameter
- Cavity BPM stability and reproducible calibrations
- Strip-line BPM improved calibration & reproducibility
- Efficient optical tuning strategy in extraction line → IP spot

Additional goals preparing for 2010-2011

- New strip-line BPM electronics
- Multi-OTR fast extraction line 4D phase space diagnostics
- Tilt monitor & IP-BPM R&D
- FONT
- Background study at and near IP as function of β^* and FD alignment

Priority tasks & responsibilities for Autumn commissioning

- 1) Team up by interest to conduct shifts, prepare software, do simulations & data analyses 2) Open and flexible
 - Cavity BPM: calibration, stability, incl. S-band Aryshev, Lyapin, Okugi, Naito, Molloy...

Boogert,

- Stripline BPM: better calib., add ADCs, high pass filter Renier, Naito, Okugi,...
- BSM: new diagnostics & other hardware, LW & interference modes, beam setup <u>Kamiya</u> + Tokyo group + local KEK team,...
- Post IP C-wire: commissioning, IP waist & knob scans incl. β* determination Bolzon, Bai, Zhou, McCormick, Kuroda, Terunuma, Tokyo group...
- Orbit reconstruction, on-line BPM & lattice diagnostics Renier, Boogert, Okamoto, White...
- Dispersion correction: EXT & IP, different knobs & methods incl. sextupoles Jones, Kubo, Kuroda, Marin-Lacoma, Okugi, White, Woodley,...
- Coupling correction: EXT & IP, different knobs & methods incl. sextupoles Bolzon, Kubo, Kuroda, Okugi, Rimbault, White, Woodley,...
- Background study: BSM + near IP, dependence with FD alignment & β*
 Guler + Verderi, Okugi + Tokyo group,...
- not listed here: Fast Kicker, DR, FONT, LW, new EXT-BPM electronics + multi-OTR + tilt monitor

Collect important questions for each priority task

1) Below are only a few examples...

2) The whole group should add & improve!

TASK	QUESTIONS	STATUS
Cavity BPM	Can the stability of calibrations for a given BPM be monitored daily / weekly ?	
Strip line BPM	• High-pass filters and separate ADCs sufficient for calibrations → precision < 5 µm ?	
BSM	Can scanning be automated in ATF control system (V-system, Flight Simulator)?	
C wire & β match	 What is expected signal strength from C wire and visibility in BSM reference layer? Would automatic waist scans incorporating dispersion measurement be feasible? How Twiss par. measured at IP compare with propagated ones from EXT meas.? 	
Traj.rec.&latt. diag.	Stability of BPM scale coefficients? Precision of strip line and cavity BPMs? Magnitude of reconstructed injected beam fluctuations?	
Dispersion	• Can IP D_y be corrected to < 1 mm with EXT line "sum-knob" in β_y = 1 cm optics ? • Can vertical bumps help to fully correct D_y (i.e. both phases) in EXT ?	
Coupling	How can we automate EXT coupling corrector + wire scanning? Matching of FF horizontal dispersion for sextupole mover knobs to be orthogonal?	
Background	Max. flux of bremstrahlung gammas in BSM detector for Compton signal detection? Flux prediction from FD region GEANT4 simulation for given input halo distribution?	

→ not listed here: Fast Kicker, DR, FONT, LW, new EXT-BPM electronics + multi-OTR + tilt monitor

Propose successive realistic goals for each task

1) Start with end goals for 2009... are listed ones OK? 2) Each group asked to formulate appropriate sequence

TASK	October	November	December	End 2009
Cavity BPM				Calibration stability on day & week timescalesS-band BPMNon-mover calibrations
Strip line BPM				Offset stability & acceptable intensity dependence
BSM				• Signal evidence in 4.5 degree mode with ~ 1 μm vertical spot
C wire & β match				 Reach ~ 1 μm C wire resolution limit Waist + disp. autoscan
Traj.rec.&latt. diag.				 Sub-µm resolution in cavity BPMs Running traj.rec.& latt.diag. spy program
Dispersion				 D_y < 1 mm @ β_y waist Consistency of IP and EXT propagated results
Coupling				• $\varepsilon_y^{\text{IP}} / \varepsilon_y^{\text{EXTLINE}} < 3$
Background				First indication of "background-aperture" in Final Doublet region

[→] not listed here: Fast Kicker, DR, FONT, LW, new EXT-BPM electronics + multi-OTR + tilt monitor

External presence at KEK for ATF2 during Fall 2009

known as of 1 October 2009

	Oct 12	Oct 19	Oct 26	Nov 2	Nov 9	Nov 16	Nov 23	Nov 30	Dec 7	Dec 14
White		х	Х	31/10				Х	Х	×
Woodley			Х	Х	Х	Х		Х	Х	×
Zhou					Х	Х				
McCormick				4/11	Х	Х				
Nelson				Х	Х	Х				
Angal-Kalinin										Х
Jones					Х	Х				
Renier	Х	Х	Х	Х	X	Х	X	Х	Х	X
Rimbault										
Jeremie									Х	Х
Bolzon			Х	Х	Х	Х	Х	Х	Х	Х
Verderi				4/11	Х	Х				×
Guler				4/11	X	X			Х	X
Bai		Х	Х	Х	Х	Х	Х	Х	Х	Х
Marin-Lacoma						19/11	×	Х	Х	Х
Okamoto	Х	х	Х	Х	Х	х	×	Х	Х	Х
Faus-Golfe						X				X
Alabau (J.)	Х		Х	Х	Х	Х				Х
FON1-team										
LW & cav-BPM										

+ permanently @ KEK : Aryshev, Bambade, Kubo, Kuroda, Naito, Okugi, Oroku, Tauchi, Terunuma, Yamanaka,...

Tentative overall beam time scheduling during Fall 2009

		•								
		سہ								
topics / weeks	Oct 12	Oct 19	Oct 26	Nov 2	Nov 9	Nov 16	Nov 23	Nov 30	Dec /	Dec 14
Start-up & injection tuning										
DR low emittance tuning										
Other non-ATF2 activities										
Fast kicker										
Cavity BPM calibration stabil. Study										
S-band cavity BPMs → establish										
Strip-line BPM calibration & tests										
Test new strip-line BPM readout										
Multi-OTR preparation										
Establish post-IP C wire										
I est of new tilt cavity monitor										
BBA → EXT & FFS										
Lattice diag. + rec. / cor. Trajectory										
Dispersion EXT										
Coupling EXT										
Emittance & Twiss EXT										
IP waist scan + measure β*										
IP spot min. with optics knobs										
BSM beam & setup preparation										
BSM laser wire > interference										
Background study BSM / near IP										
Laser Wire										
FONT										
Total number of shift to schedule	(8)	12	12		13	13		13	13	9

Concluding remarks → discussion

- The progress made may be slow but is solid and can be built upon:
 - very successful installation, and performing hardware
 - BSM LW mode established and has carefully evaluated and implemented many improvements for this run
 - other instrumentation is working though needs improving
 - check of large β optics basic soundness
 - first optics correction experience
 - invaluable experience for small international team learning to work together
- Clear & agreed end-of-2009 goals + group mostly same from start
- But many different ATF2 and ATF activities: richness, though a focus and scheduling of main tasks is important given commissioning interdependencies
- A few software improvements in V-system & Flight Simulator are critical to automate and speed up tuning tasks
- Weekly Friday scheduling can consider overall scheduling, goals, progress made
- Mechanism needed to prepare, discuss + communicate weekly task schedules
- Such task schedules are in the hands of each group, but should ideally be presented & reviewed each at Friday meeting, and at least posted on the ATF web at the beginning of each week (through a button directly on the main schedule)