



2009 Linear Collider Workshop of the Americas

A joint meeting of the
American Linear Collider
Physics Group and the
ILC Global Design Effort

29 September–3 October 2009
University of New Mexico
Albuquerque, New Mexico
USA

For more information contact
ILC@phys.unm.edu or visit
<http://agenda.unm.edu/LCW09>




XFEL Cavity Production Plan

Hans Weise / DESY




*The XFEL Cold Linac is
a common project of many SRF experts
sharing the responsibility for
the superconducting linac.*

XFEL Cold Linac components



- XFEL Cavities to be contributed by DESY and INFN Milano



- Assembly to be done at CE Saclay
- Components from a number of institutes




In2p3



Institute of High Energy Physics
Chinese Academy of Sciences

- Two schemes for the final surface treatment (*Final EP* and *BCP Flash*) were studied with cavities from two different vendors.
- The preparation strategy to go for a final treatment with the cavity already welded into the He-vessel was investigated.



Results are:

- yield curves for the different schemes
- yield curves for the different vendors
- a preparation strategy
- a strategy for the call for tender



preparation cycle



9-cell cavity cw tests



analysis of recent
9-cell cavity tests

Accelerators | Photon Science | Particle Physics

Deutsches Elektronen-Synchrotron
A Research Centre of the Helmholtz Association

DESY, V401, 22603 Hamburg, Germany

[Click here and type recipient's address]

Purchaser
ProjectsTel. +49 40 8998-1539
Fax +49 40 8998-4009
Email: purchasing.v401@desy.de

July 2, 2009


**CALL FOR TENDER
EUROPEAN NEGOTIATED PROCEDURE
DESY- Reference No.: EV 012-09-XFEL****Supply of 1.3 GHz Niob Resonators for XFEL**

Dear Sir or Madam,

With reference to the VOLIA (Conditions concerning Contracts for Supplies and Services, Part A), as well as the accompanying documents, we herewith request you to submit your best offer in accordance with and subject to the following requirements and guidelines:

1. PREAMBLE

In this document, the following shall apply:


DESY refers to the Deutsches Elektron-Synchrotron in the Helmholtz-Gemeinschaft, Hamburg, Germany.**INFN** refers to the Istituto Nazionale di Fisica Nucleare, headquartered in Frascati (Rome) Italy.**Orderer** refers to the institution allocating the contract (DESY), or the institutions supervising the cavity production (DESY and/or INFN).**Contractor** refers to the company (or companies) executing the cavity production. The possible Contractors must be previously qualified through the successful production and delivery of superconducting**DESY Deutsches
Elektronen-Synchrotron**
Notkestrasse 85
22607 Hamburg
Germany
Tel. +49 40 8998-0
Fax +49 40 8998-3282**Postal address**
22603 Hamburg
Germany
Locations of DESY
Hamburg
Zeuthen/Brandenburg**Directorate**
Dr. R. Brinkmann
Prof. Dr. H. Dossel
(Chairman)
Prof. Dr. J. Mnich
C. Soherf
Prof. Dr. E. Weckert
Dr. U. Gensch
(Representative of Directors
in Zeuthen)**■ Cavity Call for Tender was published on July 2nd, 2009.****■ Production and preparation in industry.****■ Contract to be allocated by DESY.****■ Supervision of cavity production by DESY and INFN.****■ Details can be published only 6 months after contracts are placed.**



- The Call for Tender invites **two companies being qualified for the XFEL cavity production**. Both have successfully built cavities fulfilling DESY's specification.
- The specifications describe the complete **production and preparation** including the **delivery to DESY** in batches of four cavities ready for vertical testing.
- A **minimum gradient** has been specified as well as the **unloaded quality factor**.
- Acceptance to be split into different levels
 - w/o He tank (a larger number of quality checks is required)
 - w/ He tank (further checks)
 - complete documentation of production and treatment/preparation
 - final RF acceptance test to be carried out at DESY
- Some **material, equipment, and accessories** are provided to the contractor.



way to go




- Prototype was successfully used for the recent cavity production.
- **Considerably shorter tuning time.**
- Automation and documentation.
- Minor changes required for industrial use.
- Two more machines under fabrication.

SRF09

- see THPPO071
- J. Iversen et al.

RF measurement




- **Two machines** for series cavity production are under commissioning at DESY.
- Development of software and electronic devices done at FNAL.
- CE certification of the entire machine according to European rules and laws.
- **Machine can be operated by Non-RF-Experts!**



- see THPP0074


- J.-H. Thie et al.

**automatic cavity
tuning machine**







- Purchase of Niobium for series production.
- Upgrade of infrastructure and production tools for series production.
- Mechanical fabrication of cavities incl. a specified number of pre-series and reference cavities.
- Set up of infrastructure for cavity treatment (e.g. clean room facilities, cleaning equipment, chemical surface treatment, 800°C furnace, 120°C baking, HPR etc.)
- Helium tanks and welding.
- Accessories.
- Cavity treatment.
- Assembly of HOM / pick-up / high Q fix antennas.
- Leak test, cavity installation into transport frame and shipment for the vertical RF test.

XFEL Cavity schedule






schedules ... schedules ...schedules

Gantt Chart	Task	Duration
33		
34	WP3/9 out PM in string and module assembly training	200 dy
35	initial training of new assembly teams	4 wk
36	1st dis- and re-assembly of prototype modu	8 wk
37	CMTB test of re-assembled prototype #1	4 wk
38	2nd dis- and re-assembly of prototype modu	8 wk
39	CMTB test of re-assembled prototype #1	4 wk
40	1st dis- and re-assembly of prototype modu	8 wk
41	CMTB test of re-asser	
42	2nd dis- and re-asser	
43	CMTB test of re-asser	
44		
45	pre-series module asse	
46	WP03 out PM in pre-series module #1	
47	WP09 out WP03 in first pre-series string ready	0 dy
48	WP03 out PM in pre-series module #2	7 wk
49	WP09 out WP03 in second pre-series string ready	0 dy
50	WP03 out PM in pre-series module #3	7 wk
51	WP09 out WP03 in third pre-series string ready	0 dy
52	start CMTB module testing	60 dy
56		




- The cavity production schedule has to match with the **one common schedule** with all necessary **links** between the individual cold linac work packages.
- The **series production** should start early summer 2011 and will last approx. two years.
- **We need to see AMTF commissioning beginning of 2011.**

Accelerator Module Test Facility (AMTF) Including Single Cavity Tests





- First cavity tests required for 1/2011
- Commissioning of module test facility 4/2011
- AMTF ready for infrastructure installation 3/2010

Accelerator Module Test Facility (AMTF)



Cavity Tests at AMTF Starting in 2011



■ Transportation frame; actual design, tests with single cavities on-going

■ 4-cavity insert for AMTF test cryostats; design ready, construction a.s.a.p.



■ Thanks to the XFEL cavity team...