



Design Considerations for the ILC

*Towards a new baseline for TDP2:
an open discussion with the Detector &
Physics Community*

Nick Walker
for the Project Management

A horizontal dotted line in a light yellow-green color runs across the bottom of the slide, below the speaker information.



Overview

- History & Rationale
- Straw-man Baseline 2009 Working Assumptions
- Primary Focus & Issues
- Upgrades & Physics Scope Impact
- Process towards a new Baseline: Next Steps



History & Rational



The R&D Plan

- Stated TDP Goals:

- Updated ILC design

- Results of critical risk-mitigating R&D

- Updated VALUE estimate and schedule

- Project Implementation Plan



ILC Research and Development Plan for the Technical Design Phase

Release 3

February 2009

ILC Global Design Effort

Director: Barry Barish


Prepared by the Technical Design Phase Project Management

Project Managers:

Marc Ross
Nick Walker
Akira Yamamoto



TDP R&D Plan





Rationale

- **Cost constraint in TDR**
 - Updated cost estimate in 2012 ≤ 6.7 BILCU
 - Need margin against possible increased component costs
- **Process forces critical review of RDR design**
 - Errors and design issues identified
 - Iteration and refinement of design
 - More critical attention on difficult issues
- **Balance for risk mitigating R&D**
 - Majority of global resources focused in R&D
 - Important to prepare / re-focus project-orientated activities for TDP-2
- **Need for design options and flexibility**
 - Unknown site location



Rationale

- Cost constraint in TDR
 - Updated cost estimate in 2012 ≤ 6.7 BILCU
 - Need margin against possible increased component costs
- Process forces critical review of RDR design
 - Errors and design issues identified
 - Iteration and refinement of design
 - More critical attention on difficult issues
- Balance for risk mitigating R&D
 - Majority of global resources focused in R&D
 - Important to prepare / re-focus project-orientated activities for TDP-2
- Need for design options and flexibility
 - Unknown site location

PM believe this will lead to a more

- Robust
- Mature
- Defendable


Design.

Basically a better design.



History (Review)

- **DESY EC 01.2008**
 - Cost reduction endorsed/encouraged as one of the themes of TDR Plan
- **Sendai 03.2008**
 - Cost reduction studies WG
- **Dubna 06.2008**
 - Review of Cost Reduction proposals (new ideas).
 - Single tunnel central theme
 - Consolidation of “Minimum Machine” elements.
- **KEK EC 08.2008**
 - EC endorses Minimum Machine elements
- **PAC Paris 10.2008**
 - MM elements reviewed.
 - Focus on ‘simplification’ not cost saving.
- **LCWS Chicago 11.2008**
 - Discussions on Minimum Machine (clarification)
- **TILC09 Tsukuba 04.2009**
 - AAP review, including ‘minimum machine’
 - Renamed as AD&I
- **DESY AD&I 05.2009**
 - Formation of AD&I group
 - PM’s proposal SB2009 Working Assumptions
 - Action items
- **ALCPG ‘09 ALBU. 09.2009**
 - See next slide





Two Important Documents

Ideas & Concepts



ILC Minimum Machine Study Proposal

January 2009

Prepared by the Technical Design Phase Project Management

Editors: Chris Adolphsen (SLAC)
Jim Clarke (STFC Daresbury Lab.)
Kiyoshi Kubo (KEK)
Vic Kuchler (FNAL)
Ewan Paterson (SLAC)
Marc Ross (FNAL)
Andrei Seryi (SLAC)
Nick Walker (DESY)
Andy Wolski (Cockcroft Inst.)
Akira Yamamoto (KEK)

Initial baseline Proposal (Working Assumptions)



Summary report of the first meeting on Accelerator Design & Integration 28-29th May, DESY

5th June, 2009

Editors: Ewan Paterson (SLAC)
Marc Ross (FNAL)
Nick Walker (DESY)
Akira Yamamoto (KEK)

ILC-EDMS ID: D*879845

Contains proposed parameter tables



Straw-man Baseline 2009 Working Assumptions (WA)



SB-2009 Proposal (PMs)

1. A Main Linac length consistent with an optimal choice of average accelerating gradient
 - RDR: 31.5 MV/m, to be re-evaluated

2. Single-tunnel solution for the Main Linacs and RTML, with two possible variants for the HLRF
 - Klystron cluster scheme
 - DRFS scheme

3. Undulator-based e^+ source located at the end of the electron Main Linac (250 GeV)
 - Capture device: Quarter-wave transformer



SB-2009 Proposal (PMs)

4. Reduced parameter set (with respect to the RDR)
 - $n_b = 1312$ (so-called “Low Power”)

5. Approx. 3.2 km circumference damping rings at 5 GeV
 - 6 mm bunch length

6. Single-stage bunch compressor
 - compression factor of 20

7. Integration of the e^+ and e^- sources into a common “central region beam tunnel”, together with the BDS.



SB2009 Parameters (WA)

		RDR	SB2009		
Beam and RF Parameters					
No. of bunches		2625	1312		
Bunch spacing	ns	370	740		
beam current	mA	9.0	4.5		
Avg. beam power (250 GeV)	MW	10.8	5.4		
Accelerating gradient	MV/m	31.5	31.5		
P_{fwd} / cavity (matched)	kW	294	147		
Q_{ext} (matched)		3×10^6	6×10^6		
t_{fill}	ms	0.62	1.13		
RF pulse length	ms	1.6	2.0		
RF to beam efficiency	%	61	44		
IP Parameters					
Norm. horizontal emittance	mm.mr	10	10		
Norm. vertical emittance	mm.mr	0.040	0.035		
bunch length	mm	0.3	0.3		
horizontal b^*	mm	20	11		
horizontal beam size	nm	640	470		
				no trav. focus	with trav. focus
vertical β^*	mm	0.40	0.48	0.2	
vertical beam size	nm	5.7	5.8	3.8	
D_y		19	25	21	
dE_{BS}/E	%	2	4	3.6	
Avg. P_{BS}	kW	260	200	194	
Luminosity	$\text{cm}^{-2}\text{s}^{-1}$	2×10^{34}	1.5×10^{34}	2×10^{34}	




Primary Focus & Issues




CFS: Primary Cost Driver

- Assumed primary advantage of SB2009 options is reduced CFS scope
 - Underground tunnel / volume
 - Reduced cooling requirements
- Focus of 2009 activities is to assess impact on CFS solutions
 - Removed, added, modified
- SB2009 reduces underground tunnel length by ~27 km


Primary Issues



Primary Issues




Primary Issues



Two luminosities quoted:
1.5 with high vertical disruption (~25)
2.0 with 'travelling focus'

Primary Issues









Accelerating Gradient


- Parameter with largest cost-leverage
 - Major focus of global R&D effort ('S0')
- On-going database effort to evaluate 'yield'
 - Cost implications
- For TDP-2 baseline, unlikely to change current Working Assumption (31.5 MV/m)
- Change of gradient at later stage only affects length of linacs
 - At 10% level easily scalable
 - No other subsystems affected
- New approach to 'yield' being evaluated, supporting larger spread in cavity performance
 - Average still (currently) 31.5 MV/m
 - Up to 20% spread is probably acceptable



One Tunnel Variants



TYPICAL MAIN LINAC SECTION
DRAFT FOR REVIEW






High-Level RF Solution

- Seen as critical component for one-tunnel solution.
- Two solutions:
 - Klystron Cluster concept
 - RDR-like 10 MW Klystrons/modulators on surface
 - Surface building & shafts every ~2 km
 - Novel high-powered RF components (needs R&D)
 - Distributed RF Source
 - Small ~700kW klystrons+modulators in tunnel
 - One klystron per four cavities
 - ~1880 klystrons per linac
 - Challenge is design for manufacture (cost reduction)




Distributed RF Source


Sketch of 3-Cryo-module unit




6.6kV In & Rectifier Transformer
Capacitor Bank, Bouncer



Cross Section




- 5 Reference slides: RF Cluster Scheme,




- Schematic layouts of conventional facilities and RF units

ILC Underground Structures Schematic Layout (ILC-CE-1.1649.0016, 05 December 2006)




8 more RF units than RDR (#5 Shaft Cryogenic Plant)

Cryogenic System Configuration (T. Peterson, 20 July 2007)





Central Region Integration



- RDR solution complex (CFS)
- Three tunnel concept
- Looked for consolidated solutions




Central Region Integration

5 GeV Boosters share tunnel with BDS

E- Gun and injector share tunnel with BDS

Undulator + Aux Injector + E+ Tgt-Capture-Accel + Booster share tunnel with BDS


No Keep Alive source and two tunnels, beam + support



- Undulator e^+ wiggler and rf e^- wiggler and rf
- E+/- Warm Accel
- E+ Tgt + Capture + Accel
- 5GeV Injector Booster




Reduced Beam Power






Reduced Beam Power





Reduced Beam Power





Upgrades & Physics Scope Impact



Upgrade Considerations: Energy

- Need to maintain RDR TeV Upgrade capability
 - i.e. build more linac
 - BDS geometry to support 500 GeV beam energy
 - Main (high-power dumps) rated for max. beam power
- Must consider impact on SB-2009 of upgrade scenarios (compared to RDR)
 - Example: positron source




Upgrade Considerations: Luminosity

- Reduced power option opens up scope for possible Luminosity Upgrade
- i.e. putting back 30-50% missing klystrons and associated infrastructure
- Potentially up to $\times 2$ increase in L
 - After initial running experience is gained
- Impacts many systems.
- Various scenarios can be considered
 - Impacts on upfront cost saving



Low-P: Upgrade Options





Damping Ring Low-P Considerations

- Reduced ($\div 2$) bunch number \rightarrow Reduction in DR circumference by same fraction
 - Current remains constant
 - Inj/ext kicker specs remain the same
 - e-cloud issues remain ~unchanged
- Can we double the number of bunches in a 3.2km ring?
 - Double current in ring
 - Kicker timing OK (needs R&D, but part of RDR spec.)
 - **e-cloud is likely major bottleneck**



Positron Source

- SB2009 has e^+ source located at exit of e-main linac
 - RDR: at 150 GeV beam energy point in e- ML
- E_{cm} running below 300 GeV will be affected
 - RDR: decelerate the beam after undulator
 - Not without its own complications
 - SB2009: re-visit solutions proposed by TESLA
 - Double pulsing
 - Bypass concepts (probably only for GigaZ)



Three Additional Important Issues

- **Availability (single tunnel)**
 - Import consideration for single-tunnel solutions
 - Task Force charged with finding HA solutions for proposed single tunnel
 - DRFS & KCS
- **Safety Issues (single tunnel)**
 - Second important issue for single-tunnel
 - Solutions being investigated
 - Likely differing solutions for each region
- **Risk Assessment (general)**
 - Important aspect of SB2009 analysis
 - Risk Register will be reviewed and updated
 - Some increase risk expected



Three Additional Important Issues

- **Availability (single tunnel)**
 - Import consideration for single-tunnel solutions
 - Task Force charged with finding HA solutions for proposed single tunnel
 - DRFS & KCS
- **Safety Issues (single tunnel)**
 - Second important issue for single-tunnel
 - Solutions being investigated
 - Likely differing solutions for each region
- **Risk Assessment (general)**
 - Important aspect of SB2009 analysis
 - Risk Register will be reviewed and updated
 - Some increase risk expected

Subjects covered in this workshop

Results to be summarised in closing PM plenary

Process towards a Formal Baseline

Next Steps



Next Steps (2009)

- GDE focus this meeting will be to consolidate SB2009 Working Assumptions
 - Review action items and outstanding issues from DESY meeting
 - Produce a first-guess estimate of cost increments
 - Begin to prepare **Proposal Document**
- AD&I meeting 2-3.12 (DESY) } Including designated representatives from Physics & Detector community
 - 1st draft of Proposal Document
 - Resolve remaining WA issues
- Proposal Document final draft made public 18.12.09
 - Formally to Director/EC
 - Forwarded to AAP for review
 - Entire community (i.e. you) for comment/feedback



Next Steps (2010)

- AAP formal review (4-6.01.10)



Review/include feedback from AAP and ILC community

- Final establishment of TDP-2 ILC baseline at LCWS (Beijing, 03.03.10)




Preparation / planning for TDP-2 activities

- Presentation of new baseline at ICHEPP (Paris, 07.10)

Formal start of TDP-2



Technical Design Phase and Beyond





RDR Guidance for Baseline Definition

Baseline: a forward looking configuration which we are reasonably confident can achieve the required performance *and* can be used to give a reasonably accurate cost estimate by mid-end 2012 (→ TDR)

Alternate: A technology or concept which may provide a significant cost reduction, increase in performance (or both), but which will not be mature enough to be considered baseline by mid-end 2012



Summary

- AD&I process will lead to a more cost-effective, defensible and complete design
- Cost reduction element is important for
 - Cost constraint (margin for cost update)
 - Defendability
- Baseline proposal document to be submitted end of this year
- Formal acceptance as new baseline at LCWS (Beijing March 2010)
- Your comments welcome!