



GDE Summary

Marc Ross

Nick Walker

Akira Yamamoto





Content

- Accelerator Design & Integration
- SCRF status
- Workshop highlights
- GDE-CERN collaboration
- Towards the ILC Technical Design Report



Content

- Accelerator Design & Integration
- SCRF status
- Workshop highlights
- GDE-CERN collaboration
- Towards the ILC Technical Design Report



AD&I Re-Baseline Rationale

- Cost constraint in TDR
 - Updated cost estimate in 2012 ≤ 6.7 BILCU
 - Need margin against possible increased component costs
- Process forces critical review of RDR design
 - Errors and design issues identified
 - Iteration and refinement of design
 - More critical attention on difficult issues
- Balance for risk mitigating R&D
 - Majority of global resources focused in R&D
 - Important to prepare / re-focus project-orientated activities for TDP-2
- Need for design options and flexibility
 - Unknown site location

PM believe this will lead to a more

- Robust
- Mature
- Defendable

Design.

Basically a better design.



Integrating the AD&I Team

SCRIF

R&D


CFS
Global

Accelerator
Systems

R&D



Integrating the AD&I Team





AD&I

The end of
TDP-1 in sight

TDP2

Technical
Design
Report
(2012)

ALCPG '09
New baseline
Proposal
discussions
(SB2009)

End 2009
Formal
Proposal
Document for
new Baseline
(AD&I team)

LCWS Beijing
Formal
acceptance of
new Baseline
for TDP-2




The Purpose of the Baseline

- A consistent and feasible design & layout that will be used as a platform for Design and Cost work in TDP-2
 - **2 stated TDR deliverables**
- Not necessarily the machine that will be finally constructed!
 - **R&D continues in parallel**
 - **Unknown time scale to approval/construction**
 - **A ‘snapshot’ of the State-of-the-Art in 2012**
- Design variants an important aspect
 - **More than one configuration will likely be supported**
 - **Specifically → proposed Main Linac (single tunnel & HLRF)**
- Finite global design resources means we must limit our (study) options




Technical Design Phase and Beyond






Single Tunnel ML: Availability



- Availability Studies

- Technical solution for single tunnel has been found
- HA requirements have been specified
- Both HLRF schemes can be made to work from an availability standpoint
 - 3-4% RF overhead required
- Achieving HA for the ILC remains a recognized challenge

RF Waveguide






Availability Task Force Co-Conspirators:

- Group 1 (Availsim)
 - Tom Himel (lead)
 - Eckhard Elsen
 - Nick Walker
 - Ewan Paterson
- Group 2 (Analysis)
 - John Carwardine (lead)
 - Marc Ross (chair of full group)
 - Ewan Paterson
- Group 3 (Spreadsheet availability calculation)
 - Tetsuo Shidara (lead)
 - Nobuhiro Terunuma
- Contributions from Chris Adolphsen, Nobu Toge, Akira Yamamoto




Single Tunnel ML: Availability





Single Tunnel ML: Safety

Tunnel section



– Different regional approaches being studied


– Importance of flexible design to understand potential impact of regional safety codes

CERN

CLIC - Typical Cross Section - Diameter 5000mm
Draft - J.Osborne / A.Kosmicki - October 14th 2006

European Design: Tunnel Compartmentalization

Safety considerations



SHAFT POINT

- Control of the pressure from both ends of a sector.
- Control of the pressure (overpressure or underpressure in each area).
- Fire detection per sector compatible to fire fighting via water mist.



Physics Scope Impact

- Lower beam power option → more demanding beam-beam parameters
 - **Increase beamstrahlung / increased vertical disruption**
 - **Full spec. L requires exotic techniques (travelling focus)**
- E+ source at 250 GeV point
 - **Impact in lower Ecm running**
 - Light Higgs scenario



Questions (Physics & Detector)

- **Ecm <300 GeV Running**
 - **What luminosity can we expect?**
 - **What is the scope for recovering $1/\gamma$ luminosity dependence?**
 - **Understanding physics scope impact?**

- **Lower Power Option**
 - **Impact of higher beamstrahlung**
 - **Pair spectrum (backgrounds)**
 - **Luminosity spectrum**



Questions (Physics & Detector)

- **Ecm <300 GeV Running**
 - **What luminosity can we expect?**
 - **What is the scope for recovering $1/\gamma$ luminosity dependence?**
 - **Understanding physics scope impact?**
- **Lower Power Option**
 - **Impact of higher beamstrahlung**
 - **Pair spectrum (backgrounds)**
 - **Luminosity spectrum**

GDE will attempt to provide input on these questions to P&D groups as soon as possible



Cost Estimates for SB2009 Studies

- SB = Strawman Baseline – For the TDR, the GDE is considering possible changes in the ILC RDR Baseline to improve performance or to reduce cost
- Such possible scenarios or proposals were outlined for further study at DESY in May 2009
- Adoption of each of these cost reduction proposals must be weighed against increasing the risk of meeting performance goals by GDE Management
- Estimates for each of these scenarios are needed in order to identify and concentrate our limited resources on those with highest cost reduction impact
- Area Systems Leaders & Conventional Facilities team performed another cost estimating pass for these possible scenarios




Cost Increments

(Rough Estimates from 10.2008)


- Main Linac (total) ~ 300 MILCU
- Low-Power option ~ 400 MILCU
- Central injector Integration ~ 100 MILCU
- Single-stage compressor ~ 100 MILCU



Cost (VALUE) Estimate



- Estimated cost (2007) ~6.7 Billion ILCU*
– 4.87 BILCU shared




- 10,000 person-years “implicit” labour

- VERY preliminary: better estimates will be made (end 2009)
 - But still based/scaled from RDR value estimate
- Elements *not* independent! Careful of potential double counting!
- **Cost vs Performance vs Risk:** important information for making informed decisions in 2010



Understanding Risk: The Big Picture

Example: low power option



- Many aspects of SB2009 reduce risk to project as a whole
 - Reduced CFS scope (27km tunnel) → reduced risk to construction schedule and cost overruns
 - Lower beam power handling
- Must be balanced against increase 'risk' to performance
 - Beam-beam parameters
 - Low energy running scenarios
 - Availability / commissioning etc.




Upgrade Considerations: Luminosity

- Reduced power option opens up scope for possible Luminosity Upgrade
- i.e. putting back 30-50% missing klystrons and associated infrastructure
- Potentially up to $\times 2$ increase in L
 - After initial running experience is gained
- Impacts many systems.
- Various scenarios can be considered
 - Impacts on upfront cost saving



Low-P: Upgrade Options





Feedback / Input on SB2009

Input and feedback required.
Process has been defined.
The Research Director is
organizing
feedback from Phys & Det.
community.

TDP2

Technical
Design
Report
(2012)

ALCPG '09
New baseline
Proposal
discussions
(SB2009)

End 2009
Formal
Proposal
Document for
new Baseline
(AD&I team)

LCWS Beijing
Formal
acceptance of
new Baseline
for TDP-2

**AD&I SB2009
focus meeting
2-3.12 DESY**



e+ Source at 250 GeV

- **cost reduction**, dogleg instead of chicane; shares emergency extraction (MPS) and emittance diagnostics with BDS, also one less (emergency) dump. **Operations impact - MPS**
- **need to decelerate beam (RDR)**. Conceptually feasible but not easy with full beam loading. Energy spread and stability of decelerated beam. Beam energy plus klystron forward power (for beam loading compensation) all dumped into RF loads in tunnel. **Wasn't studied for RDR.**
- Rdr solution requires front end of linac to run flat out at 31.5MV/m no "risk" margin for operations.
- long e+ low-e transport line not needed in ML tunnel (more power supplies and space needed in single tunnel)



Consider E+ Source Layout

Move the source system to the end of the E- linac.....>

The Target/Capture section would now be close to the MPS collimators at the beginning of the BDS.

While on access into the IR all systems operate and the main e-drive beam would go to the tune up dump, a shared dump.

We save ½ , 600m, of the positron insert! But we also shorten the low energy e+ transport by several kilometers and open up several possible scenarios for starting the machine at lower energies and simple upgrades to “full” energy.

All systems except the linac are now within +/- 2.5 km of the IR.

An Integrated Central Campus

Paterson, Dubna, 06.2008



Positron Source Lengths - RDR

TABLE 2.3-2	
Positron Source beamline lengths.	
Area Length (meters)	
Undulator chicane insert	1257
Undulator center to target	500
Undulator insert length	200
Target Hall length	150
400 MeV long transport line	5032
Total RF acceleration length	350
Damping Ring injection line	431




Content

- Accelerator Design & Integration –
– **Main Linac Single Tunnel Design**
- SCRF status
- Workshop highlights
- GDE-CERN collaboration
- Towards the ILC Technical Design Report



Central Region Integration - CFS






Asian Sample Site Design Studies

Global Design Effort - CFS

Access Points (SB2009)






Asian Sample Site Design Studies


Global Design Effort - CFS

Tunnel Cross Section in Asian Sample Site



2 HLRF Schemes: 1) Klystron Cluster Layout


Surface rf power cluster building



2 groups of ~35 10 MW klystrons & modulators clustered in a surface building


~350 MW combined into each of 2 overmoded, low-loss waveguides

Feeds ~2.5 km of linac total (up & downstream)



- Service tunnel eliminated
- Underground heat load greatly reduced

Main Waveguide ('Big Pipe')




We've placed an order for 4,
9.75 m sections
due in January 2010

aluminum,
formed & welded

one-side double grooved flanges:

vacuum seal – Viton® fluoroelastomer
O-ring

rf back-up seal – Bal Seal® canted coil
contact spring




2) Distributed RF Scheme (DRFS)

Standard Scheme: One DC PS/MA modulator drives 26 klystrons (6 cryomodules)

High availability with backup DC PS and MA modulator


Maximum efficient usage of SC cavity




Low Power Option

Low Power Option


Aiming for the easy upgradeability to standard scheme
Low cost
Partial sacrifice of DRFS operability







DRFS Full Power Layout




Components Size



Full Scheme to Half Option



Example of LowP PDS Layout






Content

- Accelerator Design & Integration
- **SCRF status**
- Workshop highlights
- GDE-CERN collaboration
- Towards the ILC Technical Design Report

Global Plan for SCRF R&D

Year	07	2008	2009	2010	2011	2012
Phase	TDP-1			TDP-2		
Cavity Gradient in v. test to reach 35 MV/m	>> Yield 50%			>> Yield 90%		
Cavity-string to reach 31.5 MV/m, with one-cryomodule		Global effort for plug-compatible string (DESY, FNAL, INFN, KEK)				
System Test with beam acceleration		FLASH (DESY)			NML (FNAL)	
					STF2 (KEK) 	
					FLASH (DESY)	
Preparation for Industrialization				Mass Production Technology R&D		



Global Gradient R&D Highlights

- Americas

- 1st US industry built 9-cell cavity **passed ILC spec** and reached **41 MV/m**.
- **ANL/FNAL joint facility** validated by EP proc. & testing of 1-cell cavity **> 40 MV/m**.
- Improved understanding of quench limit by T-mapping and inspection.

- Asia

- **MHI#9** reached **27 MV/m** during first RF test.
- Improved understanding by T-mapping and optical inspection of 9-cell cavities.
- Successful multi-wire slicing of ingot niobium.

- Europe

- Improved understanding by optical inspection and T-mapping of 9-cell cavities.
- Microscopic understanding of defect by cutting 9-cell cavities.
- XFEL cavity call for tenders.


- GDE SCRF Cavity Technical Area

- **Yield evaluation** method proposed (**1st-pass and 2nd-pass production**).
- Formed **global cavity database team** toward global gradient yield curve.





New Production Yield after 1st and 2nd Pass (RF) Test

Electropolished 9-cell cavities



Yield at 35 MV/m:
22 % at 1st pass
33 % at up to 2nd pass

Electropolished 9-cell Cavities




ILC Operation at <31.5 MV/m
Yield reaching ~ 40 %

Reported by C. Ginsburg and GDB team



Alternate Yield Definition: Study



- Allowing for gradient spread
- Additional RF power needed to compensate
- 20% spread seems reasonable



Cavity Gradient Study - Summary

- Yield at 35 MV/m (w/ established vendors: **RI, Zanon**)
 - **22 % at 1st pass (statistics 22)**
 - **33 % at 2nd pass (statistics 21, as of 2009-07)**
 - Average Gradient reaching 30 MV/m
 - DESY Prod-4 data to be added, (10 more statistics)
- New statistics coming (w/ potential vendors)
 - **AES: to be counted from #5** (to be confirmed)
 - **MHI: to be counted from #5** (to be confirmed)
- Selecting statistics needed for ‘Production Yield’
 - **to evaluate readiness of industrialization and cost**

Note: *Numbers of Cavities for ‘gradient research’: need to be separately counted.*




Progress and Prospect of Cavity Gradient Yield Statistics

	PAC-09 Last/Best 2009-05	FALC 1 st Pass 2009-07	ALCPG 2nd Pass 2009-10	To be added (2009-11)	Coming Prod. Y. (2010-06)	Research cavities
DESY	9 (AC) 16 (ZA)	8 (AC) 7 (ZA)	14 (AC/ZA)	10 (Prod- 4)	5	8 (large G.)
JLAB FNAL/A NL/Corn ell	8 (AC) 4 (AE) 1 (KE-LL5) 1 (JL-2)	7 (AC)	7 (AC)	~ 5 (AE)	12 (AC) 6 (AE)	6 (NW) (including large-G)
KEK/IH EP				5 (MH)	2 (MH)	~5 (LL) 1 (IHEP)
Sum	39	22	21	20	25	~ 20
G-Sum				41	66	

Statistics for Production Yield in Progress to reach > 60, within TDP-1.
We may need to have separate statistics for 'production' and for 'research'

AES8 First RF Test Following First Light EP





S1 Goal: Reached at DESY with PXFEL1 reported by H. Weise, at SRF-09



Around the World

Cryomodule surpasses ILC gradient test


European-XFEL cryomodule using SCRF technology sets new record



The cryomodule that set the world gradient record in the testbench at DESY

A cryomodule prototype for the European XFEL has set the world gradient record for cryomodules built with superconducting radiofrequency technology, reaching an average accelerating gradient of more than 32 megavolts per metre (MV/m) in recent

PXFEL 1



First XFEL prototype module **exceeds 31.5 MV/m average**
Module will see beam in FLASH accelerator in 2010
(average of 30MV/m)


Note: DESY prepared cavities and assembled with the cryomodule cold mass contributed by IHEP - Beijing for XFEL prototype



S1-Global in Progress

INFN/ZANON completing Cryomodule

- Global effort for cryomodule test for ILC operational goal
 - **INFN: Cryomodule**
 - **DESY: 2 cavities**
 - **FNAL/JLab: 2 cavities**
 - **KEK: 2 cavities, Cryomodule**



INFN/KEK Crew visit Z for diagnostics installation in July 2009



S1 Global at this Meeting

1. 5 of 8 cavities identified (2/2 DESY, 3/4 KEK, 0/2 FNAL)...remainder in process
2. 99% Deliverable Parts Agreed Upon
3. Delivery Dates of Parts Mapped Out / Confirmed
4. Test Plans Presented
5. Instrumentation Plans in Progress
6. Review of RF Systems at KEK for S1G
7. Discussions on:
 1. Tooling requirements and review of potential pieces available worldwide
 2. Coordinating use of FNAL shipping frames for all DESY/FNAL cavities
 3. Assembly procedures
 4. Further meetings for further information transfer in next months
 5. Proposals for participation by laboratories presented




S2: 9mA Experiment - DESY



History of bunch charge and number of bunches during Week #2

Charge (nC)



Number of bunches

One week Operation 14-22.09.2009




S2: 9mA Experiment

- **26 KW beam operation** at FLASH (6.7 MW equivalent at 250 GeV) for short periods



Last shift... almost 2400 bunches



ILC – 3.2 nC,
2625 bunches

Number of
bunches

One shift Operation 2100:0600 20-21.09.2009



XFEL Project Governance:

- Full speed ahead for the European XFEL GmbH!



- It is “an important step for basic research,” as Prof. Frieder Meyer-Krahmer, State Secretary at the German Federal Ministry of Education and Research (BMBF), put it: the international state convention on the construction and operation of the European XFEL was initialled on 23 September 2009 in Berlin. *“Nothing could stop the foundation of our research institution any more now,” rejoices Prof. Massimo Altarelli*, designated chairperson of the management board of the European XFEL GmbH.



XFEL Project Linac Update

- XFEL Linac ~835 cavity contract call for tender has been distributed
- Expect contracts to be negotiated and signed by early 2010 – delivery starting ~one year later
- XFEL production ‘stream’ contract will include ~ 30 ‘high gradient’ cavities funded through EC
 - **These will be processed and subjected to tests beyond nominal production process**
- Costs and production strategy to be discussed between project teams





Content

- Accelerator Design & Integration
- SCRF status
- **Workshop highlights – R & D**
- GDE-CERN collaboration
- Towards the ILC Technical Design Report



Gun Development at Jlab

- Inverted Gun installed at CEBAF →
- Development of single crystal Nb electrodes (suppression) of field emission
- Work on HV design to reach 200 kV (and beyond) →







Positron target

- Baseline target eddy current experiment data analysis has started
- Results agree best with simple model which doesn't include spokes – puzzling but good news as lowest torques (lowest energy dumped in target)!

10/Mar/2009 11:47:59





KEK Beam Tests

- Hybrid target (300 Hz source)
 - Installed on KEKB linac
 - Pilot run OK, full expt Jan – Mar 2010
- Liquid lead target (300 Hz source)
 - On ATF Linac – parameters not testing enough but good experience will be gained
 - Install Dec/Jan, expt schedule not set yet
- BN Window test (for liquid lead target)
 - On KEKB ring beam dump
 - Will use BN-solid Pb-BN sandwich
 - First tests Oct 09
 - Beam parameters well matched




E cloud Mitigation Studies

- Comparisons of EC mitigations:
 - Environments: Drift, Dipole, Wiggler
 - Chamber Surfaces: Al, Cu, TiN coating, amorphous carbon coating, grooves, electrodes

KEK

Groove and Clearing electrode


- Compared to the case of TiN-coated flat surface
 - Clearing electrode (> +300 V): 1/100~1/500
 - ~1/50 of groove structure




October 3, 2009

Measurements at CsrTA

1x45 e+, 14ns, 5GeV, Normalized



Cu and TiN-coated Wiggler Chamber Comparisons





LCWA09

54





Wiggler: ECLoud RFA Model



From Joe Calvey

Coherent tune shift vs. bunch number





Working Group Charges



- To **evaluate electron cloud mitigation techniques**, simulations and code benchmarking for the Damping Ring. In particular, evaluate the differences between mitigations as grooves clearing electrodes, coating (TiN, TiZrV NEG and amorphous Carbon) regarding their feasibility, effectiveness, impact on the vacuum system, on the beam impedance and on costs, for different regions of the DR as drifts, arc magnets and wigglers.
- To **recommend a baseline solution** for the electron cloud mitigations in the 6.4km (RDR) and 3.2km (SB2009) DR.
- **Evaluate the 'upgrade' potential** from the SB2009 proposed 1312 bunches back to the current RDR nominal value of 2623 (doubling the current) immediately identified bottlenecks.
- **Evaluate the current limits** due to e-cloud for the 3.2 km DR.



Content

- Accelerator Design & Integration
- SCRF status
- Workshop highlights
- **GDE-CERN collaboration**
- Towards the ILC Technical Design Report



CERN-GDE Collaboration

- Beyond CLIC-ILC synergy →
 - **Have prepared a request to CERN for collaborative activity on:**
 - **Cryomodule mass-production**
 - **Cryogenics**
 - **Tunnel Safety (partly included in CLIC Collaboration CFS working group)**
-
- A horizontal dotted line in a light green color is located at the bottom of the slide, mirroring the one at the top.



Content

- Accelerator Design & Integration
- SCRF status
- Workshop highlights
- GDE-CERN collaboration
- **Towards the ILC Technical Design Report**



Planning for TDP-2

- Must now begin
- AD&I effort will focus on
 - **Consolidating new accepted baseline**
 - **Further detailed design work**
 - **Cost estimation (update)**
 - **Construction schedule**
 - **Documentation (ILC-EDMS)**
- Project Implementation Plan
 - **SRF mass-production and in-kind models**
 - Industrialisation
 - **Governance etc.**
- Risk Mitigating R&D
 - **Continues**
- Major update to R&D Plan expected in mid-2010
 - **Reflect detail plans for the above**