

KEK Cavity Preparation for S1-G

Eiji Kako

(KEK, Japan)



Outline

- 1. Cavities and Surface Preparation
- 2. Status of Vertical Tests
- 3. Outlook for S1-Global
- 4. Summary



Five Cavities for S-1 Global

STF-BL #5 Cavity (MHI-05) STF-BL #6 Cavity (MHI-06) STF-BL #7 Cavity (MHI-07) STF-BL #8 Cavity (MHI-08) STF-BL #9 Cavity (MHI-09)





Delivery in 2008' March

Delivery in 2009' March

Surface Preparation for S1-G Cavities

No Barrel Polishing, EP + HPR + Assembly @ STF preEP(5μm) + First EP (20+100μm) + HT at 750°C for 3 h --- Surface Inspection in each step ---

```
MHI-05; I. EP(50)+H_2O_2 II. EP(50)+H_2O_2 III. EP(20)+C_2H_5OH
```

MHI-06; I.
$$EP(50)+H_2O_2$$
 II. $EP(50)+H_2O_2$ III. $EP(20)+C_2H_5OH$

IV.
$$EP(20)+C_2H_5OH$$

MHI-07; I.
$$EP(20)+C_2H_5OH$$


MHI-08; I.
$$EP(20)+C_2H_5OH$$

MHI-09; I.
$$EP(20)+C_2H_5OH$$

Comparison of Rinsing Effect by H₂O₂, C₂H₅OH, Degrease



MHI-05, MHI-06 Cavity, 1st VT



E. KAKO (KEK) 2009' Sept. 30


S1-G @ Albuquerque Global Design Effort



Vertical Test Results of MHI-05, MHI-06

MHI-05 Cavity


MHI-06 Cavity



MHI-05 and MHI-06 cavities are candidates for S1-G.




Eacc, max (cell) by Passbands modes Meas.






MHI-07, MHI-08 Cavity, 1st VT






MHI-09 Cavity, 1st VT





Summary of VT at STF (MHI-05 ~ 09)




Sept, 2009

Best 4 cavities for S1-G cryomodule will be selected till the end of Nov.



Schedule of V.T for S-1 Global





SUMMARY

- Infrastructure for the vertical test at STF was completed in July 2008, and have been operated routinely.
- Vertical tests of 5 cavities for S1-G cryomodule have been continuing to achieve Eacc,max > 30 MV/m, till the end of November.
- Average max. gradient of 4 cavities for S1-G will be expected to be nearly 30 MV/m.