

# ILC Cavity Gradient Strategy, A Proposal

**Akira Yamamoto**

**ILC-GDE Project Manager / KEK**

**To be presented at ILC-10, Beijing, March 28, 2010**



# TDP Goals of ILC-SCRF R&D

as of March 2010, in TPD-1

- **Cavity Field Gradient (S0)**
  - 35 MV/m in vertical test
- **Cavity-string Assembly in Cryomodule (S1)**
  - <31.5 MV/m> in cavity string test in cryomodule
    - To be re-evaluated in preparation for SB-2009 proposal.
  - Efficient R&D with “Plug-compatibility” for
    - improvement and ‘creative work’ in R&D (TDP) phase
- **Accelerator System with SCRF (S2)**
  - Beam Acceleration with SCRF Accelerator Unit
    - Need to discuss an reliable, operational field gradient including adequate HLRF/LLRF control margin for stable operation
- **Industrial Production R&D**
  - Preparing for production, quality control, cost saving
    - “Plug compatibility” for global sharing in production phase



# Global Plan for SCRF R&D

Year	07	2008	2009	2010	2011	2012
Phase	TDP-1			TDP-2		
Cavity Gradient in v. test to reach 35 MV/m	→ Yield 50%			→ Yield 90%		
Cavity-string to reach 31.5 MV/m, with one-cryomodule		Global effort for string assembly and test (DESY, FNAL, INFN, KEK)				
System Test with beam acceleration			FLASH (DESY) , NML (FNAL) STF2 (KEK, extend beyond 2012)			
Preparation for Industrialization				Production Technology R&D		



# What we need to Discuss?

- **Fundamental Research** to improve 'Gradient'
  - R&D status and understanding of limit
  - **Strategy** for improvement
- **Preparation** for 'Industrialization'
  - **Cost effective production and quality control**
    - 90 % (9-cell cavity) corresponding to ~ 99 % (1-cell cavity)
  - **Balance** between R&D and ILC operation parameters with beam,
- **System Design and Engineering**
  - Integration (compatibility, alignment, accuracy)
  - **Optimization** with other components,
    - CFS, HLRF/LLRF, Beam handling, and others,
    - Best Operation Gradient to be determined



# ILC Gradient Goals

## 500 GeV: Gradient and Q


Based on BCD cavity shape (TESLA cavity)

- BCD: Linac operating performance  
E<sub>acc</sub> = **31,5** MV/m; Q = **1x10<sup>10</sup>**
- BCD: Installed performance  
E<sub>acc</sub> ≥ **35** MV/m; Q ≥ **0.8x10<sup>10</sup>**
- Required R&D
  - Reduction of field emission and multipacting
  - Reduction of scatter of cavity performance


H. Edwards, D. Proch, K. Saito,  
ILC snowmass 05, Wg5

Parameter	Value
Type of accelerating structure	Standing Wave
Accelerating Mode	TM <sub>010</sub> , π mode
Fundamental Frequency	1.300 GHz
Average installed gradient	31.5 MV/m
Qualification gradient	35.0 MV/m
Installed quality factor	≥1×10 <sup>10</sup>
Quality factor during qualification	≥0.8×10 <sup>10</sup>
Active length	1.038 m
Number of cells	9
Cell to cell coupling	1.87%
Iris diameter	70 mm
R/Q	1036 Ω
Geometry factor	270 Ω
E <sub>peak</sub> /E <sub>acc</sub>	2.0
B <sub>peak</sub> /E <sub>acc</sub>	4.26 mT MV <sup>-1</sup> m <sup>-1</sup>
Tuning range	±300 kHz
Δf/ΔL	315 kHz/mm
Number of HOM couplers	2

2005 Snowmass BCD proposal



2007 RDR



SB2009

### 4.1.2 Issues of Main Linac System Design

In conjunction with the (GDE and AAP) review process in 2010, based on the current R&D results we propose to keep the cavity gradient goals at 35MV/m in vertical test,S0, and 31.5MV/m in operation in an installed cryomodule, S1. We note that as the R&D progresses, including horizontal testing of



# Standard Process Selected in Cavity Production and the Yield

	Standard Cavity Recipe
Fabrication	Nb-sheet ( <b>Fine Grain</b> )
	Component preparation
	Cavity assembly w/ EBW ( <b>w/ experienced vendors</b> )
Process	<b>1st Electro-polishing</b> (~150um)
	Ultrasonic degreasing with detergent, or ethanol rinse
	High-pressure pure-water rinsing
	Hydrogen degassing at > 600 C
	Field flatness tuning
	<b>2nd Electro-polishing</b> (~20um)
	Ultrasonic degreasing or ethanol
	High-pressure pure-water rinsing
	Antenna Assembly
	Baking at 120 C
Cold Test (vert. test)	Performance Test with temperature and mode measurement ( <b>1<sup>st</sup> / 2<sup>nd</sup> successful RF Test</b> )






# Historical Progression of Up-to-second-pass yield w/ qualified vendors

GDE: 1.Oct.2009

AAP: 6-7Jan.2010

ILC-10: 28 March, 2010



Camille Ginsburg & DB Team:

Yield and statistical uncertainties:

Reported, March 27, 2010:

	>25 MV/m		>35 MV/m	
	1st pass	2nd pass	1st pass	2nd pass
ALCPG-Albuquerque 1.Oct.2009	63+-10	67+-10	23+-9	33+-10
AAP-Oxford 6.Jan.2010	63+-9	64+-10	27+-8	44+-10
ILC-10-Beijing 28.Mar.2010	66+-8	70+-9	28+-8	48+-10



# Alternative Yield Plot Analysis



originated by N. Walker and updated by J. Kerby

Dec 2009 Data:

1st +2nd Pass, 1st pass cut 35MV/m,  
vendors w/ 1 cavity > 35MV/m

Electropolished 9-cell cavities

JLab/DESY (combined) up-to-second successful test of cavities from qualified vendors - ACCEL.



- Yield: estimated assuming a specific lower cut-off in cavity performance, below which cavities are assumed 'rejected'.
- Error bar: +/- one RMS value (standard deviation of the population) of the remaining (accepted) cavities (gradient above cut-off).
- Additional bars (min, max) indicated the minimum and maximum gradients in the remaining cavities.






# To Establish ILC Operational Gradient

- The **RDR** has a gradient goal of **35MV/m** such that a machine performance based on **31.5MV/m (-10%)** may be achieved, and S1 and S2 goals have been set at 31.5MV/m
- This **10%** reduction was assumed (in Snowmass, 2005)
  - to include limitations due to both **‘final assembly problems’** and required **‘machine operational overhead associated with HLRF/LLRF and beam-loading’**
- Further efforts on cavity performance, TDP-2 gives several opportunities to further investigate and quantify the actual required value, and thus the machine design
  - **FLASH at DESY**
  - **NML at FNAL**
  - **STF2 at KEK**

# FLASH layout (now)

## New layout







From Nick's talk at FLASH workshop at DESY, on Feb. 22:

# Cavity tilts with long bunch trains and heavy beam loading (3mA and 7.5mA, long bunch trains)

ACC6 gradients (3mA, 800 us)




ACC6 gradients (7.5mA, 550 us)




Gradient tilts are a consequence of using a single RF source to power cavities running at different gradients

At 7.5mA, ACC6 cavities #1 and #2 approached their quench limits at the end of the pulse

ACC6 Fwd Power (3mA, 800 us)



ACC6 Fwd Power (7.5mA, 550 us)



The RF power during flat-top is higher than the fill power for the 7.5mA case


## Around the World

### Cryomodule surpasses ILC gradient test

European-XFEL cryomodule using SCRF technology sets new record



The cryomodule that set the world gradient record in the testbench at DESY




First XFEL prototype module exceeds 31.5 MV/m average

- Module will see beam in FLASH in 2010 (av. of 30MV/m)
- Cryostat (cryomodule cold-mass) contributed by IHEP, in cooperation with INFN




# FLASH

## Cryomodule Layout and Field Gradient



Max. operation (Now)



Nominal foreseen for 1.3 GeV beam energy



# What we need to study in TDP-2

- Balance between R&D target values and Operational parameters  
Will be reviewed after S1 experience
- System design should require reasonable margin for the individual component and the system operation

## S1 (~ Component performance) > ILC-Acc. Operational Gradient

	RDR/SB2009	Re-optimization required with cautious, systematic design	
R&D goal: S0	35 (> 90%)	35 MV/m (> 90 %) <i>Keep it, and forward looking</i>	
S1 (w/o beam)	31.5 in av.	<i>need:</i> > 31.5 in av., to be further optimized	31.5 in av.
S2 (w/ beam acc.)	31.5 in av.	> 31.5 in av.	31.5 in av.
ILC: operational gradient	31.5 in av.	31.5 in av. (+/- 10 ~ 20 %)	<i>or:</i> < 31.5 in av., to be further optimized



# A Proposal for Cavity Gradient

- Appropriate balance should be re-considered b/w
  - R&D stage and Project stage
  - Components and Accelerator System Operation
- A new guideline toward TDP-2 and TDR
  - R&D Goal for Cavity Gradient (unchanged) : 35 MV/m (@ 90 % yield)
  - Guideline for System Engineering to be updated:

$$\begin{aligned} & - G_{\text{Cavity}} > G_{\text{Cryomodule}} > G_{\text{ILC-operation}} \\ & - \langle 35 \text{ MV/m} \rangle : \langle 33 \text{ MV/m} \rangle : \langle 31.5 \text{ MV/m} \rangle \end{aligned}$$

- Our homework
  - How much gradient spread to be allowed?
    - To be optimized within 10 – 20 % in balance of RF distribution efficiency
  - Can we justify the above operational margins?
    - ~ 5 % in Cavity (itself) operational margin in cryomodule operation
      - To prevent excessive field/field-emission/cryogenics-load and quench
    - ~ 5 % in LLRF/HLRF and beam tune-ability and operational margin or overhead
      - We shall learn FLASH/NML/STF progress in TDP-2

- In SB2009, ILC operational field gradient left unchanged
  - CF&S study enables to stay at 31 km in ML tunnel length
- R&D Goal for SCRF cavity gradient
  - **Keep: 35 MV/m** (at  $Q_0 = 8E9$ ) with the production yield of 90 %,
  - **Allow: Spread** of cavity gradient effective to be taken into account
    - to seek for the best cost effective cavity production and use,
- System Design to establish ILC operational gradient
  - Necessary adequate balance/redundancy between the ‘R&D gradient-milestone’ and the ‘ILC operational gradient’
    - $G_{\text{Cavity}} > G_{\text{Cryomodule}} > G_{\text{ILC-operation}}$
    - $\langle 35 \text{ MV/m} \rangle : \langle 33 \text{ MV/m} \rangle : \langle 31.5 \text{ MV/m} \rangle$
- Industrialization to be prepared
  - Lab’s collaboration and effort with regional varieties/features,
  - Industrialization model to be discussed and studied
    - [A satellite meeting for the ‘ILC cavity Industrialization at IPAC, May 23, 2010.](#)