
## Goals at this meeting

1. Review commissioning status - BPMs, Carbon WS, BSM etc. and software - High Beta Optics beam tuning 2. Plan the strategy and milestones - in details for the 1st and 2nd goals up to 2010 and 2012, respectively, , identifying key issues 3. Future plan after TDP2, i.e. 2013 - SC Q proposal Update

T. Tauchi, A.Seryi, P.Bambade, 9th ATF2 Project Meeting, 14-17 December 2009

#### ATF2 beam line and planned/proposed R&Ds 2008 - 2010 - 2012 - 2014 -




2009年 12月 15日 火曜日

## Parameters at ATF2

#### to be updates

IP Parameter	nominal	May 2009	Dec. 2009				
Beam energy	1.3GeV	1.3GeV	1.3GeV				
Emittance in x	2 nm	1.7nm	1.7nm				
Emittance in y	12 pm	11pm	<10pm				
Beta function in x	4 mm	8cm	8cm				
Beta function in y	0.1mm	lcm	lcm				
beam size in x	2.8 µm	~10 µm	~10 µm				
beam size in y	35 nm	not yet	1.5 µm				



Vertical Emittance

#### Horizontal beam size by the LW mode of the IPBSM





Figure 5: Convoluted horizontal size measured by BSM in laser wire mode in March 2009.

2009年 12月 15日 火曜日



Hardware, recently commissioned 1. Carbon wire scanner with  $5\mu$ m at the post IP note : 45 degree scanner with  $10 \mu$ m tungsten wires have been fully commissioned - vertical scanner with three  $5\mu$ m carbon wires one horizontal and two +/- 1.3 degree wires 2. OTR at the beginning of extraction line 3. Stripline BPMs with short and large aperture note : long and small aperture ones have been well calibrated. 4. S-band BPMs

- some issue (software?) remains


#### 5. Shintake monitor

note : laser wire mode has been fully commissioned

- Interference mode, 2°, 8°, 30° and 174°
- IPBPM will be installed in next year


#### "ATF2" site works in this summer done 1. Monalisa - Vibration measurement at IP 2. Straightness monitor done - installation 3. Laserwire (LW) done - installation/commissioning the laser system 4. Shintake monitor done - new screen, wire scanner and new laser - RHUL/Oxford-LW laser transport line not yet 5. Alignment at ATF2 beam line done 6. HLS system done - a collaborator from SLAC

## ATF beam operation schedule



13th Nov. First signals from the interference


All the BPMs are calibrated.



ATF2 beam tuning

50% for ATF2 as a general rule

#### Beam Extraction succeeded from DR to ATF2 by using Fast Kicker



One of the significant technology to realize the International Linear Collider is the fast kicker of the damping ring(DR), which injects/extracts the long bunch train to the DR/ from the DR. The left side picture shows the proto-type of the fast kicker installed in the DR of ATF-KEK. The beam is extracted by using the fast kicker, the right picture shows the beam profile at the end of the ATF2 beam line.


## First Multi-bunch Extraction Oct.28

Bunch interval
 5.6ns

ilr

ΪĹ


- Kicker excitation interval 308ns
- Upper line:
  bunch charge
  measured in the
  extraction line
- Hor: 400ns/div
- Ver: 0.2nC/div



PAC Review, Nov.2.2009

K.Yokoya

### First Interference result by IPBSM



# **Online Model Check**

QM13FF measure — — — QM13FF mode — — — QM13FF mode 15	IV IIIIII	ed with th Glen, 11th D	
10 5		Ā	A
0-		 ≠ ¥ ↓	Ţ₽Ź Ţ
-5			
-15 XIBW XIBW	Mafex Mafex Mafex Marex Marex Marex Marex Marex Marex		Marstr Marstr Madzer Madzer Madzer Master Master Master

_ ATF2 internal _		2009				2010													
milestones, Dec.08		jan	feb	mar	apr	may		oct	vou	dec	jan	feb	mar	apr	may		oct	vou	dec
BSM Laser Wire mode commissioned						ach	niev	ed											
First test of fast kicker																			
Observe several micron beam size					_														
BSM 8° (0.25-1.5um) commissioned																			
Observe sub micron beam size																			
BSM 2° mode (1-6um) commissioned																			
Achieve <sup>E</sup> y=24pm beam in DR																			
BSM 30° (70-400nm) commissioned																			
Extract and preserve of <sup>E</sup> y=24pm									1		~	٥,							
First observation of ILC-scaled <sup>o</sup> y=75nm									C										
Achievement of $^{\mathcal{E}}$ y < 12pm in DR										C	0								
Repeat observation of 75nm beam												1		7	シ				
Extract & preserve <sup>&amp;</sup> y=12pm beam												1	0,	$\mathbf{v}$	1	12			
BSM 174° (20-100nm) commissioned													4	6	×				
First observation of design 37nm beam															0				
Fast kicker system fully commissioned																9			
Monalisa installed on beamline																			
Reliable observation of 37nm beam																			
Achieve 2nm resolution of IP BPM																			
Evaluate IR position stability to nm level																			
Commissioning of Monalisa																			
Commissioning of FONT feedback																			
Observe of nm stability of IP position																			
Initial tests of squeezed -function																			

## Session Organization

	14th Dec. Monday	15th Dec. Tuesday	16th Dec. Wednesday	17th Dec. Thursday
9:00		Milestones in 2009 - 2010	Future Plan 2013 - SC-Q	Re-examination of strategy for next years followed up the TB discussion
	Introduction -start at 14:00 Comm. status	Milestones in 2011 - 2012	TB/SGC R&D Status Proposal update of SC-Q closed session Conclusion	Updates of commissioning status Joint w. ILC-BDS

16:30, ATF Daily operation meeting

18:00- YearEnd Party

#### Message on the SC-Q to ATF/ATF2 Members;

Thus, I would like to propose the following -

1. The importance, the validity, the technical contents of the project, and conformity with the ATF2 schedule are the subject of discussion for the coming TB meeting in December, 2009;

2. However, the go or no-go decision for the SC quad project is to be deferred until the ATF TB meeting next year (May, 2010 or later);. We hope you understand our situation.

Kaoru Yokoya, Head of KEK LC Office

9th December, 2009

## Goals at this meeting 1. Update of "monthly" milestones by 2010

- with experiences so far and the goal of 37nm by end of 2010 **2. Detailed plan for sub-systems**
- Beam tuning procedure automatically as much as possible
- OTR system as a complementary to the wire scanners
- Stripline BPMs, S-band BPMs : monitoring the stability
- IPBPM, tilt monitor, Monalisa, straightness monitor, LW and FONT etc.
- 3. Update of the SC-Q as future plan
- Essential program for the ILC and CLIC
- Worldwide collaboration
  - SLAC, BNL, KEK, LAL, LAPP, CERN, Oxford univ. and more

"We have to have a well-structured, realistic, feasible and reasonable plan for this, not just a long to-do list."