

# High Gradient Cavities: Cost and Operational Considerations

TDR: is it a Technical Design Report or a

TDR Time Domain Reflectometry

TDR Transfer Of Development Rights

TDR Time Domain Reflectometer

TDR Tokyo Disney Resort

TDR Transferable Development Rights

TDR The Death Race

TDR Tricom, S A

TDR Time Depth Recorder

TDR Transportation Discrepancy Report

TDR The Demonic Radicals

TDR Training Device Requirement

TDR The Dark Riders

TDR Test Discrepancy Report

TDR The Dirty Rag

TDR Contents of Arvid tape

TDR Transaction Data Repository

TDR Total Death Race

TDR Total Debt Restructuring

TDR Tasks, Duties, and Responsibilities

TDR Task Description Report

TDR Timmy Don't Read

TDR Technical Design Review

TDR Tom De Ridder

TDR Time Domain Reflectometry

TDR Technical Documentation Report

# Cryomodule and Cryoplant Costs



Pulse Length:  $T_{fac} = (T_b + T_{fo} * g / g_o) / (T_b + T_{fo})$

Coupler Cryo Load:  $P_{fac} = (g / g_o) * (T_b + 2 * T_{fo} * g / g_o) / (T_b + 2 * T_{fo})$

Cavity Cryo Load:  $G_{fac} = (g^2 / g_o^2) * Q_{fac} * (T_b + 1.1 * T_{fo} * g / g_o) / (T_b + 1.1 * T_{fo})$

Cryomodule Cost =  $(C_{module} + C_{inst} + C_{vac}) * (g_o / g)$

Cryoplant Cost =  $(C_{plant} + C_{dist}) * [(0.52 + 0.10 * P_{fac} + 0.38 * G_{fac}) * (g_o / g)]^{0.6}$




# RF System Cost

Pulse Length:  $T_{fac} = (T_b + T_{fo} * g / g_o) / (T_b + T_{fo})$

Number of klystrons and modulators independent of gradient – number of cavities fed per klystron scale as  $g_o / g$ .

RF System Cost =  $C_{mod} * (0.45 + 0.55 * T_{fac}) + C_{kly} * (0.74 + 0.26 * T_{fac}) + (C_{dist} + C_{llrf} + C_{global}) * (g_o / g) + C_{inst} * (0.3 + 0.7 * (g_o / g))$




# Civil Cost


Pulse Length:  $T_{fac} = (T_b + T_{fo} * g / g_o) / (T_b + T_{fo})$ ;

Assume electrical and cooling cost scale as load, number of shafts, and surface buildings constant



$$\text{Civil Cost} = C_{\text{shaft}} + C_{\text{tunnel}} * (g_o / g) + C_{\text{elect}} * T_{fac} \\ + C_{\text{cooling}} * (0.22 + 0.78 * T_{fac})$$



# Americas ILC Linac Cost Versus Cavity Gradient and Qo



# More Optimal 30 mm LL Cavity Design



	$an$	$bn$	$Es/Ea$	$Hs/Ea$	$Bs/Ea$ (mT/(MV/m))	$Ea$ ((MV/m)/180mT)
TTF cell ( $a=35mm$ )	12.00	19.00	1.984	0.00332	4.168	43.19
Original LL ( $a=30mm$ )	7.60	10.00	2.303	0.00287	3.608	49.88
opt-3 ( $a=30mm$ ) 0mm slope	10.50	17.10	1.984	0.00295	3.712	48.49
$a=30mm$ 0mm slope	11.80	20.80	1.894	0.00300	3.770	47.75

5%  $Es$  reduction  
10%  $Hs$  reduction

Reduces cryoload by 10%, rf pulse length by 6%, and site power by ~ 4%, but short-range transverse wakes ~ 85% larger

# High Gradient Operational Challenges

- Stronger Lorentz Force Detuning (LFD) to Cavity Bandwidth (BW) Ratio: For TESLA cavities:

Gradient (MV/m)	Current (mA)	Qext (10 <sup>6</sup> )	BW (Hz)	LFD (Hz)	LFD/BW
31.5	9.0	3.5	370	990	2.7
31.5	4.5	7.0	185	990	5.4
40	4.5	8.9	146	1600	11
50	4.5	11.1	117	2500	21

- BW > 1e7 required for CW ERLs and proton linacs, but LFD is constant after slow ramp-up
- Could stiffen cavity but constrained by thermal runaway if make the walls thicker


# High Gradient Operational Challenges (cont)

- For same field emitters, much higher dark currents
  - Limited to 50 nA per cavity to keep loading  $< 0.1$  W/m
  - However, reducing field emitters seems necessary to achieve high gradient, so this may not be a separate problem
- For same current, input power increases as gradient
  - At 9 mA and 31.5 MV/m, approaching power limits of couplers
  - However at 4.5 mA, the input power at 63 MV/m would be the same





# Higher Frequency Cavities


For same cavity wall thickness, gradient becomes limited by thermal run-away due to higher surface resistance,  $R_s$ , which scales as frequency<sup>2</sup>



Cavity Wall




# Thermal Breakdown Data and Simulation for the FNAL 3.9 GHz 'Linearizer' Cavities Built for FLASH




Comparison of measured data for cavity #5 (dashed) with model for the three thermal cases. Case 1 - RED, Case 2 - BLUE, Case 3 - BLACK. Solid lines are for the constant surface magnetic field model, dotted for real fields calculated by HFSS.


$h_k = 0.3 \text{ W/cm}^2\text{K at } 1.8\text{K.}$




Measured thermal conductivity and values used in models (pink)



Measured values of Kapitza conductance and values used in model (solid lines)



# 3.9 GHz Vertical Test Results: Qo vs Gradient



**Bottom Line:** Cavity and cryomodule costs likely lower at 2.6 GHz and 3.9 GHz, but need to optimize cavity wall thickness for thermal limit and LFD, and evaluate energy where increased wakes from the smaller aperture could be tolerated.

From 10/2007

# Sergei Nagaitsev: What we will NOT learn from the ILC SRF Facilities by 2011

- It is likely that by end of 2010 neither facility [NML or STF] will have an rf unit with Type 4 CM's
- NML will not operate at 5 Hz rep rate.
- We (NML or STF) may have at least one CM operating at 31.5 MV/m
  - Need to verify gradient with beam – proof of ILC CM existence!
- Neither lab will have a separate CM test stand
  - Thus no rapid CM tests with pulsed rf power
- NML and STF will not validate system optimization for the best “value engineering”, such as
  - Beam dynamics and quadrupoles system design
  - Cryomodule design with cryogenics system design

# What we will NOT learn ... (continued)

- Will not validate some interface parameters:
  - Plug compatibility
- We will have difficulties with:
  - Long-term reliability tests of CM components, such as tuners, piezos, couplers
  - Evaluating HOM absorption and propagation
    - Need to do it with an ILC CM's
  - Static and dynamic heat loads
    - NML temporary cryo system is not properly instrumented; wrong temperatures

# H. Weise: XFEL Components

- XFEL needs
    - 808 cavities for
    - 101 accelerator modules, i.e.
    - 808 frequency tuners,
    - 808 RF main input couplers,
    - 1616 HOM pick-ups,
    - 101 HOM absorbers
    - etc.
  - Overall rate: 1 module per week for 2 years
  - Orders will be placed not later than 2009, so the prices are known on the basis of 5% ILC
  - Component tests start in Q3/2010
- End of 2010 approx. 5 modules, 40+40 cavities, coupler, ...
- Mid of 2011 approx. 30 modules, 300 cavities, coupler ...

**First 5-10% of  
modules in 2010,  
majority in 2011 /  
2012**

**Tunnel installation  
finished spring 2013**