Experimental Hall in Mountain Regions

Y.Sugimoto 2010/8/2 ILC CFS Workshop @SLAC


Study of CF in mountain regions

- Design study of conventional facilities (CF) in mountain regions is actively being done by KEK CFS group and AAA (Advanced Accelerator Associates Promoting Science and Technology) in Japan
- There was an International review on the Asian single tunnel design and the CF study in mountain regions (June 1-2)

http://ilcagenda.linearcollider.org/conferenceDisplay.py? confld=4613

- Review chair: Victor Kuchler (FNAL)
- Positive review report
- Since CF design needs detector hall design, we are now involved in this activity (since Apr.2010)

An example of Asian mountain site



Exp-hall in mountain regions


- For CMS-style assembly using big vertical shafts, depth of IP should be d≤100m
- This requirement restricts the location of IP in mountain regions
- By removing the constraint of d≤100m, more flexible choice of IP location and accelerator layout can be made
 - Selecting the location of the cavern with better geology would reduce the cost and the construction period
 - Exp-hall without vertical shafts may be more suitable for some candidate sites in mountain region



• In that case, access tunnels are used to carry detector and accelerator components into detector cavern or accelerator tunnel


• We have just started to study on the exp-hall design and detector assembly method without vertical shafts as an option

(n.b. It does not mean that the CMS-style assembly using vertical shafts is excluded for all candidate sites in mountain regions)




A-A'

B-B'










D-D'

E-E'









Huge caverns in Japan

- More than 20 huge caverns with access tunnels have been constructed in Japan for hydroelectric power plants
- A 25m(W)x47m(H)x130m(L) (94,000m³) cavern can be excavated only in 14 months, and a 34mx54mx210m (250,000m³) was excavated in 21 months



Example of a cavern

- Underground hydroelectric power plant in Japan (Kannagawa power plant)
- Cavern size: 33m(W)x51.4m(H)x215.9m(L) in hard sedimentary rocks
- Construction (excavation) period: ~1y for arch, ~1y for bench
- Depth: d~600m → Heavy components of generators were carried into the cavern through access tunnels




Detector assembly


- Assembly hall locates at the entrance of access tunnel where wide flat surface and wide roads exist
- Detector would be assembled to relatively small pieces (<100~200 ton) at the assembly hall, carried to the cavern through the access tunnel, and integrated to the large detector inside the cavern (Similar to "modified CMS style assembly" which was proposed by GLD group in 2006)
- Barrel iron structure would be divided in φ (and R) direction, rather than Z direction
- Solenoid coil would be wound on surface for 5 modules, and these modules are connected into one solenoid in the cavern
- Detailed study on the assembly method is necessary

Construction period

- Construction period is one of the most controversial issues for the shaft-less exp-hall
- Construction period of an access tunnel (L~1km) would be similar to that of a vertical shaft (φ=18m, d~100m)
- Assembly of the iron yoke structure and the solenoid in the cavern would take ~1y, but it does not mean that non-CMS style assembly (new modified CMS-style assembly) takes 1y more than CMS style assembly

CMS Style





Modified CMS style

		1																				
ID	0	Name	Duration		2015		2016		2017		2018			ио d col c	2 01	2020		2021		2022		2023
1		Project approval	Od		• <u>101/</u>	<u>നിന്</u> പും 101		<u>x 1 (13 (1</u> 4	1 (1) (1	× (13 (14	1631 163	<u>∖ (13 (</u> 3	4 (3,	<u>1 (</u> 1) (<u>13 ('h</u>	101	(<u>17 ⊢(13 ⊢(</u> 14		(1/1)	<u>ki (31 (</u>	r× - (13 - (3d	-(ŋ (1 ⁄
2		Beam lines construction	1955d]	•																-	
3		Cavern/Tunnel	260w													L.						
4		Beamline harware install	105w													Ľ.						
5		Start of beam commissioning	Od																	. €_ 12/2	29	
6		BDS pre-commissioning	26w																			
7		BDS ready for detectors	Od																		🔶 06/29	
8		Detector construction	1955d																			
9		Surface assembly hall	120w				1															
10		Detectorassembly	245w										-					-		Ъ,		
11		Detector surface commissioning	26w																	Ľ		
12		Detector ready for BDS	Od																		Ě 06/29	1
13		Final assembly & commissioning	130d											-						L		•
14		Detector underground assembly	13w								styl.											
15		Final beam commissioning	13w							MS s	styn	5										h l
16		Ready for physics run	Od																			• 12/28

ID	_	Name	Duration		2015	2016		2017		2018		2019		2020		202	1	2022		2023
	0			04									CR C4						ന്നിന	
1	11	Project approval	Od		• <u>101/0</u>															
2		Beam lines construction	1955d																	
3		Cavem/Tunnel	260w					-		1				h.						
4		Beantine harware install	105w																	
5		Start of beam commissioning	0d															. € _12/	/29	
6		BDS pre-commissioning	26w																	
7		BDS ready for detectors	Od																🔶 🆸 🔶 🌒	
8		Detector construction	1690d																	
9		Surface assembly hall	120w			1														
10		Detector assembly on surface	218w											1		1				
11		Final assembly & commissioning	785d										,							
12		Detector underground assembly	105w																	
13		Detector pre-commissioning	26w										4.	¢	Value					
14		Detectorroll-in	4w										1y	TOP	токе а	ISSE	embly +	-	ų.	
15		Support tube, beam pipe, VTX install	5w										1y	for	Sub-de	eteo	embly + ctor ins	tall	<u>É</u>	
16		Detector check-out	4w				Mo	difi	ed C	MS st	tvle		,						ų.	
17		Final beam commissioning	13w				1110				. y i								Ľ.	ե
18		Ready for physics run	Od																	• 12/28


http://www-project.slac.stanford.edu/ilc/acceldev/beamdelivery/rdr/docs/CCR surface/BDS schedule.pdf

New modified CMS style

				_									
ID	0	Name	Duration			2016	2017	2018	2010		2021		
1		Project approval	Od		•	· · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · · · · · · ·	1.1.1.1.22 1.33 1.22	1.21 1.22 1.23 1.24	<u> </u>		1.01 . (35 . 1	<u>134 - 194 - 191 -</u>
2		Beam lines construction	1955d	_ ·	₩.							Ý	
3		Cavem/Tunnel	260w	1						h.			
4		Beamine harware install	105w	1								h,	
5		Start of beam commissioning	Od	1							-	∳ 1,12/29 -	
6		BDS pre-commissioning	26w	1									
7		BDS ready for detectors	Od	1								•	06/29
8		Detector construction on surface	1850d		•								
9		Surface assembly hall	120w	1									
10		Detector assembly on surface	250w	1			Ĺ				-	<u> </u>	
11		Detector assembly in cavem	550d						Į.	1			
12		Yoke assembly	53w	;						L			
13		Solenoid assembly/install/test	66w	1						*			
14		Field mapping	4w	v							L L		
15		HCAL install/cabling/test	12w	1									
16		ECAL install/cabling/test	12w	1									
17		TPC install/cabling/test	8w	v									
18		SIT/FTD/VTX install/cabling/test	8w	v									
19		Commissioning	235d										•
20		Detector pre-commissioning	26w	;								Ľ	
21		Detector roll-in	4w	v									
22		Detector check-out	4w	v									Ц.
23		Final beam commissioning	13w	1									Ľ.
24		Ready for physics run	Od	1									🔶 🕴 12

Space for assembly

- We need enough space to assemble the iron yoke and the solenoid in parallel
- Solenoid assembly procedure and installation method have to be studied
- Exp-hall should be equipped with two 200-ton cranes: usually one for each detector, and occasionally two cranes are used together to carry heavy (>200 ton) components



Summary

- Collaborating with KEK CFS group, we have just started design study of experimental hall and assembly method of ILD assuming a cavern without vertical shaft for mountain region sites
- In this scheme (exp-hall without vertical shaft), CMS style assembly cannot be adopted, and new detector assembly procedure has to be studied
- In addition, there are many issues to be studied for the optimization of the exp-hall design; some of them are common to the CMS style assembly:
 - Drainage of ground water (Cavern floor is lower than the proposed subtunnel)
 - Ventilation
 - Human safety
 - Cooling (Power consumption of the detector)
 - Cryogenic system (He compressor ~1km away from the solenoid?)
 - Vehicle for heavy (100~200 ton) components through the access tunnel

—