AHCAL Electronics.

integration status and open issues

Mathias Reinecke

CALICE main meeting Univ. HASSAN II, Casablanca, Morocco Sept. 23rd, 2010









Outline

- Status Electronics / Hamburg Activities
 - Testbeam Setup (HBU_II)
 - Laboratory Setup (HBU_I)
- Next Generation (Full Layer EUDET Module)
 - Status Redesigns Boards (DESY)
 - Tiles
 - LED Systems for Calibration
- Status DAQ / Discussion about CALICE DAQ
- Conclusion



DESY Testbeam Setup – HBU_II



- DESY 6GeV electron Testbeam operation: Setup optimization, Channel-wise calibration with MIPs: Mark Terwort
- Integrated LED System, uniformity studies / optimiz.: U. Wuppertal



DESY Testbeam - Autotrigger



Jeremy Rouene

Mathias Reinecke | CALICE meeting Casablanca | Sept. 23rd, 2010 | Page 4

Testbeam – multi-channel studies



A MIP efficiency of ~95% can be achieved for a thresholdpedestal cut at 10⁽⁻⁴⁾ for most channels (autotrigger mode).

Preliminary tests show a lightlyield of ~8.5pixels / MIP



Summary SPIROC2 and HBU measurements

- > Autotrigger Mode of SPIROC2 under test (channelwise)
- Threshold is adjusted to optimize MIP efficiency
- Multi-channel analysis in testbeam
 - has to incorporate tile and SiPM variations
- Multi-channel Autotrigger and Timing (TDC) studies to be done



Charge Injection Setup – HBU_I in laboratory



Advantage of charge injection: Amount of charge well defined.



Autotrigger Threshold Adjustment



More results on SPIROC2 tests in "electronics/DAQ" session.

Results by Jeremy Rouene



New generation's modules



AHCAL Layer – Cross Section (Height Limitations)



Compliant with Steel and Tungsten options.



Status Redesigns





done



in preparation



not started yet

- Most critical part: HBU2 (depends still on results from ASIC tests, tile size definition).
 HBU2 can carry SPIROC2, 2a or 2b.
- SIB is not needed for layer module => delayed.
- all modules needed for EUDET layer-module.
- > DIF design taken over by NIU thank you!!

DESY Redesigns: M. Zeribi, H. Wentzlaff, M. Reinecke



Mathias Reinecke | CALICE meeting Casablanca | Sept. 23rd, 2010 | Page 11

CALIB2 module (realized)



-JTAG- and testconnectors

ARM7 µController

Connector to CIB

Board survived smoke test, µController is running with old code already.



CALIB2 module (left) vs CALIB1 module (right)



(height, x,y-dimensions)



POWER2 Module (in production)





CIB Module (in production)





EUDET Tiles

The first 50 have arrived from ITEP in Hamburg – Thank You!!!







Mathias Reinecke | CALICE meeting Casablanca | Sept. 23rd, 2010 | Page 16

EUDET Tiles - Dimensions



- Tile Dimensions still under discussion => HBU2 design delayed!
- > Tile alignment testboard in design-phase (ITEP-DESY coordination)



Integration of ASCR Prague LED system into DESY setup



See talk from our Prague colleagues!



Mathias Reinecke | CALICE meeting Casablanca | Sept. 23rd, 2010 | Page 18

LED Calibration Systems II – DESY + Uni Wuppertal



- LED uniformity under investigation
- Wuppertal recommended new LED driving circuit and new LED type with lower spread in output.
- HBU2 will contain solder parameter field in order to adjust LED power per channel.
- to be optimized: LED light output spread, dynamic range (saturation)



LED Calibration System – Current Activities



Results by Julian Sauer



AHCAL DAQ – currently still Labview and USB

CALICE DAQ integration still not scheduled

- hardware missing (e.g C&C to LDA, not all LDA outputs work)
- DAQ operation/firmware: LLR did great progress, but parallel development
 @DESY does not make sense.
- > DIF firmware structure/block definition within DIF task force
 - first step for CALICE DAQ integration
 - AHCAL DAQ runs with specified command set.
- AHCAL layer module cannot really run with USB DAQ data taking will be very slow (~1Hz).



Conclusions and Outlook

- > 2 prototype setups running in parallel in Hamburg:
 - testbeam: channel-wise calibration with MIPs
 - lab-setup: SPIROC2 tests
- redesigns are ongoing, but are delayed by ongoing system tests and optimization of tile tolerances.
- CALICE DAQ integration strongly delayed due to situation in UK.
- LED calibration system development ongoing with 2 options.
- Eagerly awaiting SPIROC 2a/2b.

