

# News and preparation of the Semi-Digital Hadronic CALorimeter prototype

Imad Laktineh

CIEMAT, Gent, IPNL, LAL, LAPP, LLN, LLR, LPC, Protvino, Tsinghua, Tunis



# Outline

- Preparation for the prototype construction

# The Technological prototype

We intend to validate the **SDHCAL concept** by building a prototype which is as close as possible to the proposed SDHCAL for ILD


- Self-supporting mechanics
- Minimized dead zone
- Minimized thickness
- One-side services
- Power pulsed electronics

The prototype will be made of 40 units. Each unit is made of :

**2 cm absorber**  
**+ 0.6 cm sensitive medium**

1 cm<sup>2</sup> transversal granularity

This is about **5  $\lambda_I$**   
and **368640** channels





*The modular structure we propose makes it possible to increase the number of units up to 48*

# Mechanical structure : Self-supporting

The structure is built using the absorbers. Each of them is 1.5cm thick and with lateral dimensions of 101.1 x 105.4 cm<sup>2</sup>

Spacer thickness:  
13 mm






## Mechanical structure

**The material type** : stainless steel **304L** ( measured permeability had a maximum value of **1.5** → This allows to use the SDHCAL prototype in 4-Tesla magnet


**Tolerance** : **± 50 μm** on the thickness and **250μm** maximum on the planarity of the surface.

Quality control during the mass production of the plates will include verification by the company, both of the thickness and the planarity, and then a crosscheck will be performed at CIEMAT by using a laser interferometer system ((Precision of the system about the 30-40 μm for the planarity measurement).



## Mechanical structure



A first assembly test has been performed at CIEMAT using bare and specific tools for the handling of the plates. Some prototypes have been already built and others are under the final design.





## Mechanical structure

The 1m<sup>3</sup> prototype is a heavy structure (~8500 Kg) that we need to move and eventually rotate (for cosmic tests at the lab for example). The design of the needed tooling is being finalized and will be built at CIEMAT in the next months.






## Mechanical structure

We expect the mechanical structure to be ready by  
March 2010

# Cross-section of GRPCs




Total thickness including embedded electronics: **5.925mm**

We want to put this in a robust cassette whose walls are part of the absorber


# Cassette structure

Cassette forms the elementary unit. It includes the GRPC detector and associated electronics. It allows to fix the electronics on one plate (cover) and the detector on the other plate. The two plates ( $2+3 = 5$  mm) are a part of the absorber

The total thickness of a cassette is  $5$  mm +  $6$  mm (sensitive medium)




# Cassette structure




Cassette frame made of  
6X5 mm<sup>2</sup> section Steel bar

BONNEVAUX Alain I.P.N.Lyon 09-2010




Services outlets are  
now finalized

BONNEVAUX Alain I.P.N.Lyon 09-2010




Distance from detector to edge = 2 mm

# Assembling procedure




Clearance : 2 mm in Z  
4 mm in X





Full cassette was  
successfully tested  
at T9-PS  
May 17- 29







## Cassette structure


We expect full production of all components of the cassettes before the end of November 2010

# Electronics


- 1- ASIC : Produced and being tested and calibrated (9000 ASICs)
- 2- DIF : Produced and tested 165 available
- 3- ASU : Being finalized. 300 to be produced and cabled by end of November

## Many evolutions.....


Connector board to DIF:  
Kapton flex



Connector board to board:  
Kapton flex



144 ASICs= 9216 channels/1m<sup>2</sup>




1 pad= 1cm<sup>2</sup>, interpad distance = .5 mm


## Electronics

A big effort is made on the connectors

- 1- More robust
- 2- Easily plugged



ASU-ASU connector  
seems ok.





We will slightly modify  
the ASU-DIF connector  
Rigid-Flex to Rigid-Flex-Rigid

# Electronics

A robot is being used to test the ASICs

Max test time : 10 minutes/ASIC using Labview-based application





## Electronics

Electronics assembling will start as soon as the ASUs are cabled. First 1m<sup>2</sup> will be completed starting from December 2010

# Detectors


Components to build 60 chambers are at hand  
Painting of 16 plates with semi-automatic silk screen print machine was performed.

- 1- Painting area : 2-3 mm far from the edge was respected  
important to limit sparks with the  
cassette edges
- 2- Painting homogeneity : very good

1	0,53	2,6	0,18	0,29	0,17	0,25	0,16	0,32	0,16	0,36	0,18	0,33	0,18	0,42	0,25	0,22
2	0,7	2,3	0,22	0,33	0,21	0,32	0,16	0,34	0,18	0,47	0,24	0,4	0,23	0,52	0,23	0,27
3	0,7	2,5	0,15	4,7	0,18	0,23	0,15	0,37	0,19	0,33	0,17	0,36	0,18	0,37	0,18	0,23
4	0,82	3,5	0,27	0,38	0,22	0,37	0,2	0,45	0,29	0,46	0,24	0,47	0,26	0,52	0,34	0,35
5	0,97	3,8	0,23	0,45	0,19	0,37	0,25	0,45	0,23	0,42	0,23	0,47	0,26	0,46	0,29	0,33
6	0,67	3,5	0,29	0,31	0,18	0,25	0,19	0,36	0,21	0,36	0,2	0,4	0,21	0,53	0,24	0,25
7	0,97	3,2	0,26	0,42	0,22	0,37	0,22	0,41	0,25	0,44	0,23	0,46	0,26	0,62	0,28	0,31
8	0,77	52	0,21	0,3	0,18	0,29	0,22	0,34	0,27	0,36	0,17	0,4	0,18	0,5	0,19	0,28
9	0,97	∞	0,31	0,47	0,24	0,35	0,25	0,4	0,27	0,49	0,25	0,47	0,27	0,59	0,27	0,34
10	0,97	3,4	0,22	0,44	0,2	0,38	0,25	0,45	0,25	0,46	0,25	0,5	0,32	0,51	0,3	0,35
11	0,85	4	0,28	0,4	0,26	0,25	0,18	0,45	0,17	0,41	0,21	0,43	0,19	0,43	0,23	0,35
12	0,97	5,4	0,19	0,43	0,23	0,4	0,16	0,45	0,22	0,59	0,26	0,54	0,23	0,62	0,23	0,59
13	0,9	3,2	0,14	0,26	0,16	0,3	0,2	0,34	0,48	0,42	0,26	0,43	0,28	0,61	0,23	0,73
Valeur Min	0,53	2,3	0,14	0,26	0,16	0,23	0,15	0,32	0,16	0,33	0,17	0,33	0,18	0,37	0,18	0,22
Valeur Max	0,97	52	0,31	4,7	0,26	0,4	0,25	0,45	0,48	0,59	0,26	0,54	0,32	0,62	0,34	0,73
Valeur Moy	0,83	#####	0,23	0,71	0,20	0,32	0,20	0,33	0,24	0,43	0,22	0,44	0,23	0,52	0,25	0,35
Rapport Max/Min	1,83	22,61	2,21	18,08	1,63	1,74	1,67	1,41	3,00	1,79	1,53	1,64	1,78	1,68	1,89	3,32
Epaisseur Verre	1,1	1,1	0,7	1,1	0,7	1,1	0,7	1,1	0,7	1,1	0,7	1,1	0,7	1,1	0,7	0,7

Verre N°2 et N°4 => Manque de Peinture

Not enough painting



POINTS DE CONTROLE RESISTIVITES





# Detectors



Painting of additional 100 plates will take place next month. It takes 2 days.

Construction of detectors has already started  
We expect to build 2 chambers/week

# Validation test

We intend to test our chambers and validate them using a cosmic ray stand developed by the group of Louvain.

The stand is made of 4 planes of scintillators 160X160 cm<sup>2</sup> each two X-Y doublets



# Validation tests

The two doublets will be separated  
By .9 m.  
Up to 3 GRPC can be tested at the  
same time.  
4 hours are enough to study the  
Efficiency of each pad of the GRPC  
chamber.

Gas system is already installed  
and fully functional.

GRPCs will be transported from  
Lyon to Louvain by a group of 6



# Services: High Voltage

Cockcroft-Walton system is selected as the baseline for the technological prototype. It satisfies safety requirement and ILD volume limitation.



A module was developed in collaboration with ISEG

Characteristics:

- $0-5\text{ V} \rightarrow 0-10\text{ kV}$
- $I < 10\mu\text{A}$
- I,V monitoring
- Residual noise 50 mV

**Still we are working to  
To reduce its thickness to 21mm**


A card to control/monitor the voltage/current of the 40 modules independently was conceived and being produced




CAN Transceiver

ADC

DAC



# Services: Gas distribution system




To feed 40 GRPCs without  
contamination risks  
Dynamic precision < 2%

To be delivered soon

# Acquisition system and Software

Situation is much happier now than 3 months ago  
See talks of Vincent and Laurent



We think we will have the system ready by February 2011

# The prototype construction schedule

- **ASICs** are produced and packed **LAL**
- and then **tested** using the CMS adapted Robot **IPNL**
- **DIFs** are produced and tested **LAPP**
- **DCC, LDA** and other DAQ related boards are produced and being tested by **LLR**
- **PCBs** are being finalized and production is expected soon **IPNL**
- **Cabling** will start after (**IPNL**)
- **RPCs** production will start soon (2/week) (**IPNL+Gent+LPC**)
- **Cassettes** designed and should be built by a private company and PNL,LLR..
- **Assembling** units (detector+cassette+electronics) will take place starting from November (**IPNL**)
- **Testing** units : **Louvain-La-Neuve**
- **Mechanical structure** will be ready by the February 2010: **CIEMAT**

# Conclusion

- Many components are ready
- Tests are still ongoing
- Mass production has already started
- DAQ HW and SW are in advanced phase
- Realistic simulation is ongoing

We hope to be ready before March 2011



# Simulation and performance study

Simulation should be as realistic as possible :



- 1- Including dead zones and edge effects
- 2- Obtaining the same efficiency and multiplicity as for data  
see R.Han talk

Performance study

- 3- Developing new algorithms to improve on energy resolution and PFA: Neural Network, Hough Transform, Minimum Spanning Tree.....


# Energy resolution

To determine the energy a **Neural Network** can be very helpful




**INPUTS** : Number of pads with 1st, 2d and 3d threshold ( $N_1, N_2, N_3$ )

Additional inputs taking into account the shower **shape** and its extension as well as shower **density** distribution are being studied



# Tracking, clustering algorithms

**Hough Transform** : find MIP inside the hadronic shower and use them to **calibrate/control** the detector



Ongoing study

**Minimum Spanning Tree** :

- Powerful tool to connect **clusters** into appropriate branches.
- Useful to separate **electromagnetic** from **hadronic** contribution

