

Construction of the DHCAL Prototype



José Repond
Argonne National Laboratory

CALICE Collaboration Meeting
University Hassan II
Casablanca, Morocco
September 22 – 24, 2010

DHCAL Collaboration


Boston University (Data Collector)

John Butler (Professor)
Eric Hazen (Electronics Engineer)
Shouxiang Wu (Electronics Engineer)



Fermilab (Front-end chip, Trigger and Timing Module, Event Display)

Alan Baumbaugh (Electronics Engineer)
Louis Dal Monte (Electronics Engineer)
Jim Hoff (Electronics Engineer)
Scott Holm (Electronics Engineer)
George Mavromanolakis (Postdoc)
Ray Yarema (Electronics Engineer)



University of Iowa (High Voltage and gas systems)


Burak Bilki (Graduate Student)
Edwin Norbeck (Professor Emeritus)
David Northacker (Mechanical Engineer)
Yasar Onel (Professor)



McGill University




François Corriveau (Professor)
Daniel Trojand (Graduate Student)*



Northwestern University



Nicholas Mucia (Graduate Student)
Brian Pollack (Graduate Student)
Mayda Velasco (Professor)



University of Texas at Arlington



Jacob Smith (Graduate Student)*
Jaehoon Yu (Professor)



IHEP (Beijing)



Qingmin Zhang (Postdoc)*



*Supported (in part) by Argonne



Argonne Electronics Group

Carol Adams (Electronics Technician)
Mike Anthony (Engineering Assistant)
Eddie Davies (Draftsman)
Patrick De Lurgio (Electronics Engineer)
Gary Drake (Electronics Engineer)
Bill Haberichter (Engineering Assistant)
Andrew Kreps (Electronics Engineer)
James Schlereth (Computer Scientist)
John Walendziak (Electronics Technician)



Argonne Mechanical Group

Robert Furst (Technician)
Victor Guarino (Engineer)
Zeljko Matijas (Technician)
Frank Skrzecz (Engineering Assistant)
Ken Wood (Engineering Assistant)
Allen Zhao (Engineer)

Argonne Physicists

Kurt Francis (Postdoc)
José Repond (Physicist)
David Underwood (Physicist)
Lei Xia (Physicist)

| DHCAL Collaboration | Heads |
|-----------------------|-----------|
| Engineers/Technicians | 22 |
| Students/Postdocs | 8 |
| Physicists | 9 |
| Total | 39 |

Overview

Chamber construction

- Spraying of glass → Measurement of R_{\square}
- Assembly of RPCs → Thickness measurement, leak test
- Attaching of HV connectors → HV tests

Electronics

- Front-end board fabrication and assembly → Tests
- Pad- and Front-end board gluing → Tests
- Data collectors
- Timing and trigger modules
- Cables

Cassettes

- Assembly
- Transportation to FNAL

Peripherals

- Low voltage system
- High voltage system
- Gas system






Glass Spraying

Need to coat anode glass with resistive paint with $R_{\square} = 1 - 5 \text{ M}\Omega$
 R_{\square} of cathode glass not as important

Built automatic spraying booth

- 1 button operation
- fumes (non toxic) vented outside of building
- 1 glass/2 minutes, but long set-up times
- Standard operation: 8 glass/day
- Total production needed ~250 pieces




Production completed
Never gained complete control over R_{\square}
RMS actually rather good

RPC Assembly




Each chamber 32 x 96 cm²
Important to maintain gas gap size constant
Need 114 chambers to equip cubic meter

Built precision fixtures for assembly

- 1 frame cutting fixture
- 3 RPC assembly fixtures
- Assembly of 1 RPC/technician/day
- Produced a total of 149 chambers



RPC 001



Production completed with 149/114 chambers
Thickness variation on rim acceptable
(not all chambers measured)
All chambers passed leak test at 0.3" of H₂O



HV Connection

- 3 steps: 1) attach connector
2) cover chamber in Mylar sheets
3) protect connector with RTV

Nominal voltage 6.3 kV

Built test stand

- 6 chambers tested simultaneously
- Tests performed at 7.0 kV
- Monitoring of (dark) currents






**~127/114 chamber successfully tested at 7.0 kV
Currents ~ 0.25 μ A/chamber**

Front-end Boards

Each board contains 1536 channels and 24 ASICs
The data concentrator is implemented into the same board
2 boards are needed per RPC

Built 3 computer controlled test stations

- Extensive tests (S-curves, noise rates...)
- 3 – 6 hours/board
- Demanded less than 4/1536 dead channels





Testing complete
254/228 boards tested successfully

Pad- and FE-board Gluing

Each board contains 1536 channels which need to be connected with conductive glue
The glue dries in 3 hours

Built a gluing fixture

- Dispenses glue on gluing dots
- Takes only 25 minutes/board
- Glued 10 boards/day
- Glue is cured in oven at 70 C⁰



**Gluing complete
254/228 glued boards in hand**


Data Collector Modules

1 Data Collector Module per 12 front-end boards
Need 19 for cubic meter

Built test station at Boston



Production complete
30/20 boards delivered to Argonne




Timing and Triggering Module

Provide control to up to 24 Data Collectors
Need 1 Master and 2 Slaves for cubic meter





Designed and debugged at FNAL

12 boards produced
6/3 assembled so far



Cables

Proposed layout in beam area



| Cable | Amount needed | Measured length [feet] | Length to be cut [feet] |
|---------------------|---------------|------------------------|-------------------------|
| Signal | 228 | R/L = 19/22 | 28 |
| Low Voltage 110 V | 6 | 20 | 20 |
| Low Voltage 5 V | 76 | 24 | 30 |
| High Voltage 110 V | 3 | 25 | 25 |
| High Voltage 6.5 kV | 38 | 21 | 25 |

All cables + spares in hand

Cassette Assembly

3 RPCs assembled into a cassette


Front-plate is copper (for cooling of ASICs) and back plane is steel

Cassette is compressed horizontally with a set of 4 (Badminton) strings

Strings are tensioned to ~ 20 lbs


Assembly

- Not very difficult
- Best timing so far:
45 minutes/cassette



15/38 cassettes assembled
Possible to assemble at least 5 cassettes/day

Cassette Transportation



Need to transport cassettes to FNAL
(glass breaks!)

Built transport fixture

Able to transport 8 cassettes at a time
Frame mounted on dampers to absorb shocks

Tested successfully with 1 cassette

- Loading on truck at ANL
- Transportation to FNAL
- Unloading from truck at Mtest
- Insertion into the CALICE stack
- Extraction from CALICE stack
- Loading onto truck at Mtest
- Transportation back to ANL
- Unloading at ANL

Peripherals

Low Voltage Power Supply

Need power to 228 front-end boards (+5V)
Acquired 7 Wiener power supplies
Built 7 power distribution boxes
All fully operational

High Voltage Power supply

Need 6.3 kV to 38 layers (3 RPCs powered by 1 line)
Borrowed 3 LeCroy 4032 power supplies
Borrowed 2 sets of controllers
Developed computer control program
All fully tested

Gas Supply

Need 19 lines (2 layers or 6 RPCs per line)
Built mixing rack for 3 gases
Built distribution rack
All fully operational

All (virtually) complete



Commissioning/move/data taking

- 1) All layers will be powered up and tested at Argonne
- 2) Starting September 27th layers and crates will be transported to FNAL
- 3) Starting October 4th layers will be powered up and commissioned at FNAL
- 4) Starting October 9th we will accept beam
- 5) Test beam ends November 2nd

Test Beam Plans

Broadband muons for calibration

Calorimeter not rotated

Move calorimeter around to expose entire volume (4 x 4 positions)

Most likely for one week, depending on statistics and width of beam

(rough calculation: $(100/\text{pad}) \times (9216 \text{ pads}) / (350 \text{ muons/spill}) = 2,600 \text{ spills} = 44 \text{ hours}$)

Energy scans (separation of positrons and pions offline using Cerenkov)

Calorimeter not rotated

Into center of calorimeter

1,2,4,8,12,16,20,24,32,40,48,60 GeV

(rough calculation: $100,000 \text{ events/E} / (300 \text{ particles/spill}) \times (12 \text{ E}) = 4,000 \text{ spills} = 67 \text{ hours}$)

Broadband muons at 20°

Only into center of calorimeter

Energy scans at 20°

Into center of calorimeter

Some energy points

Conclusions

We have been busy since the last meeting in Texas

Construction is almost complete

Cassette assembly is not expected to take more than a few days

Commissioning is ongoing

We will have 38 layers in the test beam on October 9th

We will take data with the stack over the following 4 weeks

We will build more layers to equip the tail catcher



The second test period (including the ECAL) will be in January/February 2011



Backup Slides



Efficiency across the spacer



ZOOM(55.-110.) of Hit Position ((hits w/ tdc only))/((all hits))


Half width about 1.8 mm

$$\epsilon \sim 15\% \times 3 \text{ mm} = 45\% \text{ mm} = 100\% \times 0.45 \text{ mm}$$


Spacer \varnothing is 0.64 mm



Slide from October 2003



Select vertical tracks only



ZOOM(50.-110.) of Hit Position ((hits w/ tdc only))/((all hits))

Half width is about 1.1 mm

Efficiency loss due to fishing lines

Assuming inefficiency given by diameter of fishing line (it's better than that)


$$\text{Inefficient area} = I = N \times L \times D = 4 \times 32.0 \text{ cm} \times 0.115 \text{ cm} = 14.7 \text{ cm}^2$$

$$\text{Total area} = A = L \times W = 96.0 \text{ cm} \times 32.0 \text{ cm} = 3072 \text{ cm}^2$$

$$\text{Inefficiency} = I/A = 0.47 \%$$

Assuming inefficiency given by $D^2/3$

$$\text{Inefficiency} = 0.31 \%$$



Inefficiency due to fishing lines 0.3 - 0.4%

Neutral particles

250 GeV jets

Assuming 25% of these jets with $E_{\text{particle}}^0 > 80 \text{ GeV}$

Fraction = $80\text{GeV}/250\text{GeV} \times 0.25 = 8\%$

Overall neutral hadron energy $\sim 10\%$ of E_{jet}

Segmented calorimeter

Offers possibility of software compensation

Needs to be applied to the DHCAL

Nevertheless

Would be good to have better response at high energy

→ Finer granularity: $1 \rightarrow 0.25 \text{ cm}^2$ (works in Monte Carlo)

→ Better single pad resolution (digital \rightarrow semi-digital) ???

