

# Goals at this meeting

1. Commissioning status - critical review
  - BPMs, IPBSM, Multi-OTR, IPBPMs and LW
  - Continuous Run with the nominal optics
2. Plan the strategy and milestones
  - in details for the 1st and 2nd goals

by end of JFY2010 and 2012, respectively,  
discussing key issues

T. Tauchi, A.Seryi, G.White and P.Bambade,  
11th ATF2 Project Meeting, SLAC, 1/13-14, 2011



# Parameters at ATF2

IP Parameter	nominal		April 2010	May 2010	Dec 2010
Beam energy	1.3GeV		1.3GeV	1.3GeV	1.3GeV
Emittance in x	2 nm		1.7nm	1.7nm	1.8-2.7nm
Emittance in y	12 pm		<10pm	<10pm	28-64pm
Beta function in x	4 mm		4cm	4cm	10mm
Beta function in y	0.1mm		1mm	1mm	0.1mm
beam size in x	2.8 $\mu\text{m}$		$\sim 10 \mu\text{m}$	$\sim 10 \mu\text{m}$	7.5 $\mu\text{m}$
beam size in y	35 nm		900 nm	300 nm	439(247) nm



# “ATF2” works in this summer, 2010

1. New Modulators (#0,#8) at LINAC **done**
2. Alignment **done**
  - DR, QD0 and QF1
3. Laserwire (LW) **done**
  - commissioning the laser system
4. Shintake monitor **done except for phase monitor/feedback**
  - addition of carbon wires, 2nd fringe pattern and phase feedback
5. New targets of multi-OTRs **done**
6. Smoothing timing of fast kicker for the multi-bunch **tested**
7. Software development **continued**
8. Multipole components of QEA magnets **studied**



# Results of Re-alignment of QD0FF and QF1FF presented by R. Sugahara, 14th September 2010

## Summary of Analysis

QF1 rotations are -6.25mrad at E-end (upstream) and -4.09mrad at W-end.  
Average is -5.17mrad.

QD0 rotations are +2.69mrad at E-end (upstream) and +2.79mrad at W-end.  
Average is +2.74mrad.

After all, we have decided to rotate

**QD0 by -2.5mrad and**

**QF1 by +4.5mrad**

**in re-alignment, so that the fine correction can be done with movers at the time of beam tuning**

# Measurement comparison between IHEP and KEK for sextupole skew component: good agreement






Fig. 9. Sextupole component vs magnet number.  
presented at the APAC 2007, M. Masuzawa

Phase information needed for calculating the skew component.  
Sextupole phase with respect to the quadrupole phase was used.





A Skew Sextupole  
magnet was installed  
at upstream of QF5B  
in January, 2011.  
power supply :  $\pm 20\text{A}$   
cooling ?





# Achievements in this continuous run, Dec.2010

## Beam sizes :

12./15 ~10:00 min.  $\sigma^*_x = 7.53\mu\text{m}$  at 130.048A by QD0FF scan by IP carbon wire

12/16 15:00 The minimum  $\sigma^*_y$  was ~400nm, one fluctuated to 247nm (M=0.95).

note: during the scans (12/16 12:30 -15:30), the modulation (M) frequently exceeded 1 for M became negative at the minimum due to statistical fluctuation.

Then, 6 to 30 degree made , skipping 8 deg. ?

## Emittances :

DR :  $\varepsilon_y = 14.1 \pm 0.7\text{pm}$ ,

EXT:

Large emittance growth in ATF2 ?

12/13  $\varepsilon_y = 33.9 \pm 0.7\text{pm}$  (  $\varepsilon_x = 2.74 \pm 0.04\text{nm}$ ) by OTR,

12/14 6:49 - 8:35  $\varepsilon_y = 41.33 \pm 0.26\text{pm}$  (  $\varepsilon_x = 2.699 \pm 0.004\text{nm}$ ) by OTR

12:00 - 14:00  $\varepsilon_y = 27.6 \pm 1.8\text{pm}$  (  $\varepsilon_x = 1.78 \pm 0.13\text{nm}$ ) at MW1X by wire scanners

20:00 optimize fit parameters in OTR code to get consistent emittance results

12/15 21:35  $\varepsilon_y(\text{proj}) = 54\text{pm}$ ,  $\varepsilon_y(\text{intr}) = 45\text{pm}$  by OTR

12/17 5:30  $\varepsilon_y(\text{proj}) = 63.6\text{pm}$

Difference between OTRs and MW ?

## Dispersions :

12/14 18:05-  $\eta_x = 0.56 \pm 0.05\text{mm}$ ,  $\eta_y = -0.27 \pm 0.03\text{mm}$

12/15 ~3:00  $\eta_x = 2\text{mm}$ ,  $\eta_y = 2\text{mm}$  by IP wires,  $\Delta f = \pm 3\text{KHz}$

$\eta_y$  is small enough ?



# Session Organization

	13th January Thursday	14th January Friday
9:00	<p><b>(Introduction)</b></p> <p><b>Instrumentation</b></p> <p>FONT5, QBPMs, IPBSM (Shintake monitor), IPBPM, LW, Multi-OTR,</p>	<p><b>Towards the 1st goal</b></p> <p>Effect of multipoles in ATF2 magnets, QEA field measurements, IPBSM operation and strategy</p> <p><b>Towards the 2nd goal</b></p> <p>IPBPM, FONT for IP feedback and milestones for 2011 to 2012</p>
12:40		
14:00	<p><b>Beam Tuning</b></p> <p>DR, EXT, FFS, IPBSM, simulation, EXT/FFS matching &amp; BBA, steering and dispersion (SVD), beam jitter at EXT/FFS</p>	<p><b>11th TB/SGC Meeting</b></p> <p>Summary of the ATF2 project meeting, proposals, future plan etc.</p>
18:30		

19:30- Banquet



# Goals at this meeting

- 1. Detailed plan / strategy for the goal 1  
by end of 31 March, 2011**
2. Milestones of the second goal in 2011 -2012
3. Discussion of future prospect