

Interconnection of ASUs


SiW ECAL LLR 08/02/2011
P Cornebise CNRS LAL




Contents

- 1 Introduction
- 2 Current method of interconnection
- 3 PCB FEV interconnection with ACF 3M
 - 3.1 Test results from 3M Beauchamps (95)
 - 3.2 Next tests with the current thermode
 - 3.3 Next steps with our thermode if we buy it
- 4 Eudet LAL assembling hall


1 Introduction



With:
7 ASUs+1DIFF




**My presentation focuses on the
ASUs interconnections study**




1111µm

2


Current method of interconnection




Kapton comb 1 connector



Solder bench



Silk screen for
Manual solder paste laying
(very delicate operation)



Halogen lamp for the solder
200°C for 2.30 minutes



We developed this method with the Cambridge University
and used for interconnect 8 FEV temp




3 PCB FEV interconnection with ACF 3M

3.1 Test results from 3M Beauchamps (95)

Components

1 FEV7 CIP



1 Kapton comb
1 connector



ACF 3M 7303 film
width=5mm length= 25meters





Miyachi thermode test bench



3.1

3M Anisotropic Conductive Film Adhesives ACF 7303 use characteristics


Meet specification for the ACF employment



The ACF technology is used to:
-Flat screen
-Laptop
-Smartphone...

Minimum Pad Overlap = 0.75mm² (3M)

FEV
2.5mm²




General Properties of ACF 7303

Adhesive Type: Epoxy/Acrylate Blend
Particle Type : Silver-coated glass
Particle Size : 43 µm
Liner Type: Polyester-coated Kraft with Silicone Release
Adhesive Thickness: 74 µm
Liner Thickness: 100 µm



3.1 Process

The ACF 3M looks like double-sided tape

Put the ACF on FEV
Remove the protect film (brown)



Positioning of the comb
(It's possible to repeat the positioning)




Using
Myachi
Thermode





Temperature 150°C
Time 25 seconds
Pressure 18 Bar

3.1 Results



Kapton comb pictures with binocular



Results of electrical test made with a precision multimeter Keithley
Resistance between wires in PCB = 0.2 ohms
Isolation between wires in PCB = ∞

Advantage of the ACF is:

- Ease to use, low stress for PCBs
- **Industrialization of process is very easy**

R&D issues:

- Currently limited information on the lifetime,
Requires further electrical and aging tests

3.2





Next tests with the current thermode

- Interconnect 3 FEVs with a thermode available to us for free at 3M company or Miyachi company
- Electrical tests in 3 FEVs, resistors, current, high voltage...
- Check the limits of ACF 3M with the use of an oven
 - Required to manufacture a mechanical support for 3 FEVs (part1)
 - Required to produce simple PCBs without chips (part2)
 - Required to produce Kapton combs with 4 connectors (part3)

Note:

3M Adhesive has a lifetime of 30 days at room temperature if stored in a freezer

3.2 (1) Mechanical support for 3FEVs by Julien Bonis



3.2



(2) PCB FEV8 3C CAO LAL

by Dominique Cuisy and Pascal Rusquart

4 connectors

Wire by wire

4 connectors




3.2

(3) Kapton combs CAO LAL

by Dominique Cuisy and JC Hernandez

Kapton combs FEV8



4 connectors with 36 copper pads length=14mm width=0.5mm thickness 35 μ m

Thickness of kapton = 50 μ m


Total thickness = 85 μ m

-Completed 06/01/2011


3.2

Preparation of test bench for testing


Positioning FEV8 3C
to mechanical support




Positioning kapton combs
on ACF 3M



The test bench is now ready
to start interconnection process



**The test is scheduled for March 9
and we'll go together me and Rémi Cornat**



3.3

Next steps with our thermode if we buy it


- The price of thermode is estimated at 10 000 euros (ANR)
- The new machine has a nozzle adapted to interconnect 4 or 2 half connectors simultaneously
- We need a new mechanical support for 7 FEV8 and if possible automated

4

Eudet LAL assembling hall

- Status
 - Demounting crane n°1 completed
 - Computer and phone network completed
 - Water heating system completed
 - Electrical installation current
 - Control crane n°2 to be done
 - Replacement front door to be done
 - Painting to be done
 - Work completed planned middle of March

Inauguration planned for March 14 2011



Thank's for your attention

