



ECAL Technological prototype for test beam



CALICE Collaboration Meeting @ Cambridge / September 17th-19th, 2012 ANR-2010-BLANC-0429-01







ECAL Technological prototype for test beam

- 1 ECAL Si/W "conservative design"
- 2 ECAL Si/W "test beam"
- 3 ECAL Si/W "BGA design""
- 4 ECAL design





⇒ The goal:

1 – Build an operational SLAB for alveolar structure of 7.3 mm thick and 180 mm wide





⇒ Current design: 2 SI detection layer per Slab

Chips and bonded wires inside the PCB



⇒ Gaps (slab integration) : 500 µm
⇒ Heat shield : 500 µm
⇒ PCB : 1200 µm ? (flatness problems)
⇒ Thickness of glue : 100 µm (gluing by LPNHE)
⇒ Thickness of wafer : 325 µm
⇒ Kapton[®] film HV : 100 µm
⇒ Thickness of W : 2100/4200 µm (± 80 µm)

⇒ Conservative design: Short U Slab CIP, 1 SI detection layer per Slab





Assembling process at LAL

1 ASU/adapt mounting station



3 Slab part Assembling



2 Interconnection ASU/Adapt



4 ASU/Adapt Assembling in U Slab





Assembling process at LAL

5 Heating glue station



7 Slab closing



6 Wafer leakage current test



8 Finished slab





⇒ Conservative design: Long U Slab CIP

Next step : Design and production of the support structure of the slab and the mould of the long slab

U shape according to the different solutions : ECAL Si/W "conservative design" & ECAL Scint/W : U-Shaped structure (same !) Do we need this long U slab?

If yes...We need

- ⇒ Long Slab support design : 1 or 2 k€
- ⇒ New long Slab mould design : 3 or 4k€
- ⇒ Term: 2 months



ECAL Si/W "test beam"



⇒ The goal:

1 – Realize a mechanical system to secure the Slab in position :

- 10 Short U SLAB CIP (conservative design)
- 10 W plates of 2,1mm thickness



ECAL Si/W "BGA design"



 \Rightarrow The goal: Build a slab with chip CIP as thin as possible and already tested

1 – Study a short U Slab with 16 chips CIP BGA for read 4 wafers (1 layer)





Kapton: 100 µm

2 – Study a short H Slab with 32 chips CIP BGA for read 8 wafers (2 layers)



ECAL design



⇒ Beam structure:

This Beam structure is necessary to rotate the ECAL structure and protect it during the manipulation operations

1 – Scew the Beam structure on the mould plate



4 – And screw the *false rails* on the Ecal



2 – Turn the Ecal structure module with the beam



3 – Unscrew the mould plate



ECAL design



⇒ Safety structure:

1 – This system can be completely removed for beams tests and simulates a space of 30mm between the ECAL and another detector.

2– This system can be used for test-beam combined

- Global length: 1491 mm vs 1491.15 mm +/- 0.15

- Global width: 552.3 mm vs 552.65 mm +/- 0.05

- Global tickness: 205.3 mm vs 205 mm 0/+5.28 !!! Expected (structure dim.) vs Measured



ECAL design



⇒ Transport carriage:

This carriage is necessary for protect the ECAL against mechanical stress during all transport

1 – This transport carriage is provided with a shock absorber in case of too severe transport conditions

2– All the windows can be closed by a plate 3 mm aluminum thick.





ECAL design

⇒ Clamping Slab:

The clamping system is used to lock all the short Slab inside the alveolar structure during the test beam.

1 – This system allows to lock the slabs at 45 ° or 90 ° in the ECAL structure



10 slabs at 45 • inside the ECAL structure

10 slabs at 90 • inside the ECAL structure





 \Rightarrow Clamping Slab: The clamping system is used to lock all the short Slab inside the alveolar structure during the test beam.

1 – If the modification of the angle is necessary...

it would be better to choose the beam angle before the tests because the slab displacement will take several hours (disassembly of cables, supports)







⇒ Preparation of mechanical test:

1 – Determine the maximum allowable stress in the alveolar wall in a case of loading at 0°, 45°,90°

2 – Find a subcontractor to constrain our demonstrator while recording measurements of fiber Bragg Grating molded into it (like the schema 2 and 3)

3 –Improve the simulation about the global mechanical behavior





- **Today, 6 short Slab U are operational**
- We plan to study more molds and parts for Slabs development short U/H and long U/H
- We prepare our demonstrator for destructive test
- We prepare some tools to integrate the Slabs and ECAL structure for next test beam .

The conclusion



Thank you for your attention







ECAL Endcap

structure and cooling studies

18.09.2012 Denis Grondin, Julien Giraud, Johann Menu, Guilhem Frèche CALICE Collaboration Meeting @ Cambridge / September 17th-19th, 2012

Current structure of End-Caps





Frotin CALICE Meeting @ Cambridge / 17-19 September 2012

ECAL End-Cap & cooling studies

End Cap : evolution of skin thickness



Problem of bending stress of alveoli skins



Long alveoli moulding & fastening



2.5 m alveoli molding

- <u>The end-cap layer test consisted of</u>
- 3 long alveoli (representative of end-cap module longest layers)
- Width of cell: 182,3 mm like barrel's one (for electronic uniformity) besign don't fit LOI parameters (R~2062 / 2090 of LOI)
- •Thickness of cells : 7.3 mm wall: 0.5 mm
- Length : 2.490 m



>Next test: Long End-Cap alveolar layer (September 2012)

3D design of different fastening system \Rightarrow Thickness 30 mm & double row sized







Vertical

2 Double

8

Finite element calculation to determine the stiffness of the rails



Critères de TSAI Hill Version 1 (7621)9.90E-03Déplacement (mm)0.16Opening in rails for cooling and

Première contrainte principale (11411) (MPa)

Type d'accrochage (vertical, horizontal)

Type de rail (simple, bouble)

services on each column (EUDET)

Finite element End Cap simulation : MODULE N°1

2.5 m long / 3 columns / position 0° and 90° / M = 2550 Kg

- ⇒ Goal of simulations: Influence of **position / nbr** of fastening systems on the mechanical behaviour (displacement / stress) ...
- \Rightarrow Even if module is fastened with <u>2 double rails</u> instead of 3 simple rails, deflections are less important.

Nombre de rails

Cooling/ heat exchanger link





Cooling/ true scale leakless loop



LPSC cooling test area and cooling station

Fall 2012 : design of cooling station : tank, pipes, wiring Spring 2013 : cooling station assembly, leak less tests (<1atm)



LPSC cooling test area with a drop of 13 m



Work on real scale leak less loop including real module altitude / electronic / sensors

- Three lines will be conducted: height mini, medium and maximum

- Work on reliable connection between the cooling system and the water heat exchanger
- First Design: hydraulic safety, hardened components, cooling supervision...
- Global cooling / Pipe integration