

# ATF2 Status

T. Tauchi

ILC PAC, KEK, 13 -14 December 2012

# Content

## 1. Introduction

ATF2 purposes, characteristics and layout

## 2. Major issues featured at ATF2 ( not ILC )

- multipole components of quadrupole magnets at the final focus system
- IP beam size monitor, so-called Shintake monitor

## 3. Schedule and brief history in October through December, 2012

## 4. Technical failures and recoveries

- power supply of 6.6kV
- RF no.2 ( modulator)
- air conditioning system in DR
- realignment of DR for the earthquake M7.3, 12/4 2012

## 5. Beam tuning status

- Comparison of TWISS parameters beteen upstream and downstream
- IPBSM 30 degree performance
- wakefield
- emittance growth at EXT, i.e. large vertical emittance

## 6. Summary

# ATF2 : Goal - I (- 2012)

## A. Achievement of 37nm beam size

A1) Demonstration of a new compact final focus system;  
proposed by P.Raimondi and A.Seryi in 2000,

A2) Maintenance of the small beam size  
(several hours at the FFTB/SLAC)

## Goal - II (2013 - )


## B. Control of the beam position

B1) Demonstration of beam orbit stabilization with  
nano-meter precision at IP.

(The beam jitter at FFTB/SLAC was about 40nm.)

B2) Establishment of beam jitter controlling technique  
at nano-meter level with ILC-like beam


Parameters	unit	ATF2	ILC	CLIC	S-KEKB (LER/HER)
Beam Energy	GeV	1.3	250	1500	4/7
$L^*$	m	1	3.5-4.5	3.5	0.47/1.3
$\gamma \epsilon_x$	m-rad	$5 \times 10^{-6}$	$1 \times 10^{-5}$	$6.6 \times 10^{-7}$	$2.5/3.3 \times 10^{-5}$
$\epsilon_x$	nm	2	1.0 (DR)	0.1 (DR)	3.2/2.4
$\gamma \epsilon_y$	m-rad	$3 \times 10^{-8}$	$4 \times 10^{-8}$	$2 \times 10^{-8}$	$1.0/1.2 \times 10^{-7}$
$\epsilon_y$	pm	12	2(DR)	1(DR)	13/8.4
$\beta_x^*$	mm	4	21	6.9	32/25
$\beta_y^*$	mm	0.1	0.4	0.07	0.27/0.41
$\eta'$	rad	0.14	0.0094	0.00144	
$\sigma_E$	%	~0.1	~0.1	~0.3	0.08/0.06
Chromaticity	$L^*/\beta_y^*$	~ $10^4$	~ $10^4$	~ $5 \times 10^4$	$1.7/3.2 \times 10^3$
$\sigma_x^*$	$\mu\text{m}$	2.8	0.655	0.039	10.2/7.8
$\sigma_y^*$	nm	37	5.7	0.7	59/59




# ATF2 Features

- The same number of magnets as the ILC-FF.
- The tuning knob, methods are the same, too.
- Beam instrumentation has been developed with the ILC specifications; BPMs, BSMs, movers, magnet support, laserwires, HA power supplies, FONT-feedback system etc. .
- International participation in the commissioning and operation


Field strength error giving 2% effect on beam size




Jitter position error giving 2% effect on beam size



Magnet tilt error giving 2% effect on beam size



Static position error giving 2% effect on beam size




# Parameters at ATF2

3.11 Earthquake




IP Parameter	nominal	May 2010	Feb 2011	Dec 2011	Feb 2012
Beam energy	1.3GeV	1.3GeV	1.3GeV	1.3GeV	1.3GeV
Emittance in x	2 nm	1.7nm	1.8-1.7nm	2nm	1.8nm
Emittance in y	12 pm	<10pm	27-28pm	~50 pm wakefield@mOTR	15.6 pm
Beta function in x	4 mm	4cm	10mm	1cm	4cm
Beta function in y	0.1mm	1mm	0.1mm	0.5mm	0.3mm
beam size in x	2.8 $\mu\text{m}$	~10 $\mu\text{m}$	-	9.2 $\mu\text{m}/2$	11.2 $\mu\text{m}$
beam size in y	35 nm	300 nm 8deg.mode	1.8um@PIP C-wire	850nm 5deg.mode	165nm 30deg.mode





# Effect of Magnet Swap on Tracked Beam size for optimized lattice (v4.5 BX2.5BY1 lattice, emit\_x=2nm)




- Very little effect for this configuration.
- Need to check for larger emit\_x (3-4nm)



G.White, ATF2 meeting July 6

# S-band BPM feed-through

- feed-through of Cavity BPM has Kovar, i.e. magnetic, at Final doublet; the s-band BPMs have been removed.





Feed through of S-band BPM(Kovar)



Skew multipole components measured with kovar feedthrough in position A at varying distances from magnet coil face.

# Addition of Skew 6 magnets

From 1 to 4 magnets to correct skew sextupole components at quadrupole magnets



**Red ; No correction**

**Yellow ; with SK1FF correction**


**Blue; with 4 SKs correction  
( 10A maximum)**

*By using 4 SKs correction, tolerances for QF9BFF, QF9AFF, QD4BFF, QD4AFF, QF1FF, QD0FF increase.*

T.Okugi、ATF2 meeting July 13

# New IP-BSM System from 2012 Autumn Operation

by N.Terunuma



*All optical component should be aligned with respect to the reference line of base plate (old system don't have the reference line for the optical component).*

*Laser collision angle will be controlled by linear stage ( old system used the rotator).*

*- The laser paths for lower angle mode can be kept in higher angle mode measurement.*




*Path length for upper path and lower path are designed to the same length*

*All focal lenses will be on the linear stage. (old system was used the reducer to change the focal length )*

*-The focal points for upper path and lower path can be set to same .position.*


*Dove prism for 30degree mode will be removed.*

# IPBSM : Beam size measurement as a function of crossing angle



	174°	30°	8°	2°
Fringe pitch	266 nm	1.03 μm	3.81 μm	15.2 μm
Minimum	25 nm	100 nm	360 nm	-
Maximum	100 nm	360 nm	-	6 μm

# Degradation of Modulation



$N_0$  = average energy in the interference region

$N_1$  = energy in non-overlapping region

$$N_\gamma(\phi_L) = N_0(1 + \tilde{M} \cos(\phi_L - \phi_0)) + N_1 = (N_0 + N_1)\left(1 + \frac{N_0}{N_0 + N_1} \tilde{M} \cos(\phi_L - \phi_0)\right)$$

Therefore, modulation is just degraded by  $\frac{N_0}{N_0 + N_1}$

# Repetition rate 1.5 Hz → 3 Hz

- Speedup the beam tuning
- Adaptation of monitor systems, e.g. BPMs in the DR




Air-conditioning in the DR does not work since the beginning in October, which causes variation of the DR circumference; e.g. a few kHz/day

BPMs@DR at 3Hz  
FONT (IP-feedback)  
Cavity Compton  
IPBSM

RF(modulator)-2 failed 11/9  
IPBSM 30deg.  
new QF1FF  
ref. cavities removed

6.6kV power system failed 10x1 Optics



■ ... Beam

earthquake M7.3 12/7  
realignment in the DR  
wakefield studies  
large vertical emittance



# ATF2 beam tuning shift plan in last 2 weeks, 2012

	1:00 – 9:00	9:00 – 17:00	17:00 – 25:00
12/10 Mo	---	---	<i>Kubo</i>
12/11 Tu	Kuroda + A	White + B	<i>Okugi</i> + C
12/12 Wd	Woodley + D	<i>Tauchi</i> + E	Kuroda + A
12/13 Th	Kubo + B	<i>Okugi</i> + C	Tauchi + D
12/14 Fr	White + E	Terunuma + A	Woodley + B
12/15 Sa	Kuroda + C	Terunuma + D	White + E
12/16 Su	Kubo + A	Tauchi + B	Woodley + C
12/17 Mo	Okugi + D	White + E	<i>Terunuma</i> + A
12/18 Tu	<i>Kuroda</i> + B	Tauchi + C	Okugi + D
12/19 Wd	Woodley + E	<i>Kubo</i> + A	White + B
12/20 Th	<i>Okugi</i> + C	Kuroda + D	Kubo + E
12/21 Fr	White + A	<i>Tauchi</i> + B	

Name: Study/Tuning leader (*Italic: shift leader (for safety)*)

A-D: Study/Tuning sub-leaders

The assignments are not strict and you may move and/or join flexibly to any shifts.

A: J. Nelson, E. Marin, L. Corner

B: Y. Renier, H. Garcia Morales

C: S. Boogerd, J. Snuverink, m

D: Y-I Kim, N. Blaskovic, Davis

E: J. Pfingstner, Akagi, Tanaka


5 operation teams by  
young/senior researchers

## Failure of LINAC RF#2

- The LINAC RF#2 had a serious trouble in evening of last Friday, 11/9 2012.
- Survey had been done from Nov. 12<sup>th</sup> to 15<sup>th</sup>. We had to de-assemble the Klystron section to check the inside of the HV tank.
- It was found the HV pulse transformer, DC-HV cables and sockets, Thyatron trigger box and Grid resistor were damaged.
- The trouble seems to be started by the unexpected shots of the Thyatron with much higher repetition but without the trigger.

# Devices for Recovery

HV pulse transformer is swapped by that for SLAC 5045 klystron




Spare klystrons, Toshiba 3712, 80 MW.  
Use brand new klystron. We have more but repaired and low powered.




# New QF1FF was installed

2012 11/19-22



- New magnet was put on the mover.
- Mover keeps its middle position more than a day.
- Cabling was almost done.
- Fine alignment is in progress.
- Vacuum chambers will be connected today.



# Reference Cavities

2012 11/19-22

- Three C-band reference cavities (not used at present) were **removed** from the beamline.
- That for S-band was also **relocated** 3 meter upstream. We need relocate the pickup cable.

# 4 OTR measurements and reconstruction of IP parameters

2012.12.11 20:10

Horizontal projected emittance parameters at first OTR

```

energy = 1.2690 GeV
emit = 1.6021 +- 0.0787 nm
emitn = 3978.5209 +- 195.4115 nm
emit*bmag = 1.9924 +- 0.0339 nm
bmag = 1.2437 +- 0.0412 ( 1.0000)
bmag_cos = 0.1695 +- 0.0000 ( 0.0000)
bmag_sin = -0.5698 +- 0.0000 ( 0.0000)
beta = 9.1707 +- 0.3830 m ( 6.3052)
alpha = -7.2455 +- 0.3377 (-4.4943)
chisq/N = 3.2873
    
```

Horizontal projected emittance parameters at IP

```

sig = 40.3802 +- 0.2032 um ( 7.9947)
sigp = 293.8991 +- 1.4073 ur (200.4496)
beta = 1017.7782 +- 56.7444 mm ( 39.6952)
alpha = -7.3399 +- 0.4081 (-0.0238)
    
```

Horizontal projected emittance parameters at waist

```

L = -0.1361 +- 0.0004 m
beta = 18.5476 +- 0.9924 mm
sig = 5.4511 +- 0.2787 um
    
```

$\beta^*_x = 18.5 \pm 1.0 \text{ mm}$

Vertical projected emittance parameters at first OTR

```

energy = 1.2690 GeV
emit = 40.6210 +- 0.5315 pm
emitn = 100.8760 +- 1.3200 nm
emit*bmag = 42.5895 +- 0.5652 pm
bmag = 1.0485 +- 0.0045 ( 1.0000)
bmag_cos = 0.2594 +- 0.0000 ( 0.0000)
bmag_sin = 0.1517 +- 0.0000 ( 0.0000)
beta = 8.1739 +- 0.1095 m ( 6.1903)
alpha = 3.5609 +- 0.0511 ( 2.5763)
chisq/N = 87.1894
    
```

Vertical projected emittance parameters at IP

```





sig = 1.1553 +- 0.0162 um ( 0.0639)
sigp = 630.5855 +- 0.3151 ur (635.3753)
beta = 32.8570 +- 0.5697 mm ( 0.1006)
alpha = 17.9063 +- 0.3092 ( 0.0019)
    
```

Vertical projected emittance parameters at waist

```

L = 0.0018 +- 0.0000 m
beta = 0.1022 +- 0.0017 mm
sig = 0.0644 +- 0.0004 um
    
```

$\beta^*_y = 0.10 \pm 0.002 \text{ mm}$



456)

# 4 OTR measurements and reconstruction of IP parameters

2012.12.12 6:41

**Status / Calculation Data**

beta = 801.9018 +- 7.5797 mm ( 39.8952)  
alpha = -5.2411 +- 0.0456 ( -0.0238)

**Horizontal ellipse emittance parameters at waist**

L = -0.1476 +- 0.0002 m  
beta = 28.1673 +- 0.2083 mm  
sig = 6.5339 +- 0.0444 um

**Vertical ellipse emittance parameters at first OTR**

energy = 1.2690 GeV  
emit = 69.6697 +- 0.3907 pm  
emitn = 173.0140 +- 0.9703 nm  
emit\*bmag = 76.4471 +- 0.3577 pm  
bmag = 1.0973 +- 0.0011 ( 1.0000)  
bmag\_cos = 0.3721 +- 0.0000 ( 0.0000)  
bmag\_sin = 0.1760 +- 0.0000 ( 0.0000)  
beta = 9.3201 +- 0.0363 m ( 6.1903)  
alpha = 4.0720 +- 0.0111 ( 2.5763)  
chisq/N = 181.7248

**Vertical ellipse emittance parameters at IP**

sig = 5.8757 +- 0.0330 um ( 0.0837)  
sigg = 824.5793 +- 0.1866 ur ( 832.1029)  
beta = 495.5371 +- 2.7864 mm ( 0.1006)  
alpha = -69.5350 +- 0.3882 ( 0.0019)

**Vertical ellipse emittance parameters at waist**

L = -0.0071 +- 0.0000 m  
beta = 0.1025 +- 0.0006 mm  
sig = 0.0845 +- 0.0000 um

**Figure 1**

Normalized Horizontal Phase Space at OTR0X (projected data)

**Horizontal projected emittance parameters at first OTR**

energy = 1.2690 GeV  
emit = 1.8988 +- 0.0203 nm  
emitn = 4715.2666 +- 50.4662 nm  
emit\*bmag = 1.9145 +- 0.0194 nm  
bmag = 1.0083 +- 0.0011 ( 1.0000)  
bmag\_cos = -0.1179 +- 0.0000 ( 0.0000)  
bmag\_sin = -0.0494 +- 0.0000 ( 0.0000)  
beta = 5.6076 +- 0.0429 m ( 6.3052)  
alpha = -4.0469 +- 0.0424 ( -4.4943)  
chisq/N = 3.2557

**Horizontal projected emittance parameters at IP**

sig = 37.1298 +- 0.2187 um ( 8.7035)  
sigg = 250.1400 +- 1.2299 ur ( 218.2215)  
beta = 726.0676 +- 14.0007 mm ( 39.8952)  
alpha = -4.7681 +- 0.0899 ( -0.0238)

**Horizontal projected emittance parameters at waist**

L = -0.1453 +- 0.0004 m  
beta = 30.3461 +- 0.5100 mm  
sig = 7.5908 +- 0.1002 um

**Figure 2**

Normalized Vertical Phase Space at OTR0X (projected data)

**Vertical projected emittance parameters at first OTR**

energy = 1.2690 GeV  
emit = 63.2885 +- 1.4919 pm  
emitn = 157.1671 +- 3.7049 nm  
emit\*bmag = 68.8126 +- 1.6750 pm  
bmag = 1.0873 +- 0.0042 ( 1.0000)  
bmag\_cos = 0.2342 +- 0.0000 ( 0.0000)  
bmag\_sin = 0.3151 +- 0.0000 ( 0.0000)  
beta = 8.3070 +- 0.1619 m ( 6.1903)  
alpha = 3.7998 +- 0.0562 ( 2.5763)  
chisq/N = 1.8084

**Vertical projected emittance parameters at IP**

sig = 6.1735 +- 0.1537 um ( 0.0798)  
sigg = 865.3559 +- 0.8901 ur ( 793.0605)  
beta = 602.2053 +- 16.0766 mm ( 0.1006)  
alpha = -84.4062 +- 2.2399 ( 0.0019)

**Vertical projected emittance parameters at waist**

L = -0.0071 +- 0.0000 m  
beta = 0.0845 +- 0.0022 mm  
sig = 0.0731 +- 0.0003 um

**mOTR\_start**

ICT1X (units = # electrons / 1e10)  
 Apply Cut? 0.2 **0.41** 1.2

Emittance: OTR0, OTR1, OTR2, OTR3

Target: OUT, NonOTR

Mode: NonOTR

Limits: IN, OUT

Measurement Mode: IN, OUT

Messages: Get CCD Background

Flight Simulator Command: **Running**

CCD Camera Power Reset In

Restart mOTR EPICS IOC

$\beta^*_x = 30.3 \pm 0.5 \text{ mm}$

$\beta^*_y = 0.085 \pm 0.002 \text{ mm}$

(Unsubject))  
Error while evaluating uicontrol Callback

2012年 12月 14日 金曜日

# Estimation of IP Beta function by 5umΦ IP carbon wire scans

**20:45 correct horizontal dispersion at final focus by scanning QF1FF strength and damping ring frequency (+- 2kHz)**

new magnet setting 122.674 A (min. beam size)

- $\eta_x = 5.38$  mm
- 5 micron contribution to beam size


horizontal beam size: 13.575 um

estimated  $\beta^*_x$  0.057 m



estimated hor. emittance 4 nm

**2012 12/21 21:52 move to vertical knob scans, QD0FF scan**

- change to 129.225A
- beam size 3.8 um
- If we assumed to emit<sub>y</sub>=40pm (OTR measurement),  $\beta_{y^*}=0.093$ mm.
- QD0FF\_carbon\_121211\_221347.png:



$\chi^2 / \text{ndf}$	150896624.00000 / 6
Constant	72.97757 ± 0.00063
X-min	129.22487 ± 0.00000
Y-min	3.62891 ± 0.00007






# 2012 12.13 Day shift

## QF1FF current scan

red cross; measurement

green line; fit to the measured data

blue line; SAD model (emittx=2nm)




## QD0FF current scan

red cross; measurement

green line; fit to the measured data

blue line; SAD model (emitty=40pm)



# IP vertical beam size measurement by IPBSM 2012 12.5 14:22


NotUse | TimingScan | LW28 | LW30 | LW174 | Fringe28 | Fringe30 | Fringe174 | Zscan28 | Zscan30 | Zscan174 | TimingScan28 | TimingScan

## Fringe Scan 2-8 degrees

Ready to scan

### 7.3 Degree

**Graph**



$\chi^2 / \text{ndf}$	383.74585 / 207
Average	1969.33765 ± 60.28453
Modulation	0.93658 ± 0.02674
Phase	0.86580 ± 0.03748

**Phase Scan Range**

Min	Max	Step	Nread
10.00	30.00	1.00	10

Origin Phase Position: 3.48533  
Current Phase Position: 3.50912  
Intensity Cut [e9]: 3.000 < I < 20.000  
Fit Mode: layer 1-4 4.980

Start Stop


Collision Angle: 7.32387  
Filename: /atf/data/ipbsm/interfere/meas121205\_141800

FileSelect Recalculation


Modulation	0.937	+/-	0.027
Beam Size	224.5	+/-	52.8 nm
Average	1969.338	+/-	60.285
Phase	0.866	+/-	0.037

Print window

**Energy deposit**



**ICT**



# IP vertical beam size measurement by IPBSM 2012 12.5 15:00

5 continuous measurements M30LY: 11.719 2012/12/5 30 deg 10x1 beta

data	M	M_error	beamsize	beamsize_err	avg	avg_err	phase	phase_err	Nav	Noflines	1/err^2M	1/err^2size	size/err^2M	size/err^2size
145649	0.208	0.053	276	6	2178	85	2.964	0.268	3	80	355.998576	0.0277777778	74.04770381	7.666666667
145810	0.342	0.032	223.1	4.5	1946	43	1.508	0.089	10	220	976.5625	0.049382716	333.984375	11.01728395
150556	0.248	0.033	258.6	3.9	2322	53	1.2	0.13	10	220	918.2736455	0.06574622	227.7318641	17.00197239
150749	0.251	0.033	257.6	3.9	2242	52	0.651	0.129	10	220	918.2736455	0.06574622	230.486685	16.93622617
150942	0.184	0.025	288	2.6	2073	37	-1.764	0.134	10	220	1600	0.147928994	294.4	42.6035503

5 measurements

## Fringe Scan 30 degrees

Ready to scan

Phase Scan Range

Min	Max	Step	Nread
10.00	30.00	1.00	10

Origin Phase Position: 3.48533  
Current Phase Position: 3.48533  
Intensity Cut [e9]: 3.000 < I < 20.000  
Fit Mode: layer 1-4 6.085

Collision Angle: 7.32387  
Filename: /atf/data/ipbsm/interfere/meas121205\_1458

Modulation	0.342	+/-	0.032
Beam Size	223.1	+/-	4.5 nm
Average	1945.642	+/-	43.307
Phase	1.508	+/-	0.089


Energy deposit

ICT

30 Degree

Very consistent with one at 7.3 degrees

# Installation of a c-band reference cavity (MREF3FF) for wakefield study at large Beta(y), 12/5 Owl shift



# Earthquake in Japan

JMA (Japan Meteorological Agency)			<a href="http://www.jma.go.jp/jma/kishou/known/shindo/explane.html">http://www.jma.go.jp/jma/kishou/known/shindo/explane.html</a>		
Scale(m)	gal JMA lower end	Acc(cm/s <sup>2</sup> ) 0.45x10 <sup>m/2</sup>	People	Indoor Situations	Outdoor Situations
0			Imperceptible to people.		
1	0.8	1.4	Felt by only some people in the building.		
2	2.5	4.5	Felt by most people in the building. Some people awake.	Hanging objects such as lamps swing slightly.	
3	8	14	Felt by most people in the building. Some people are frightened.	Dishes in a cupboard rattle occasionally.	Electric wires swing slightly.
2012.12.7 (M7.3)@Tsukuba 4	25	45	Many people are frightened. Some people try to escape from danger. Most sleeping people awake.	Hanging objects swing considerably and dishes in a cupboard rattle. Unstable ornaments fall occasionally.	Electric wires swing considerably. People walking on a street and some people driving automobiles notice the tremor.
5-Lower	80	142	Most people try to escape from a danger. Some people find it difficult to move.	Hanging objects swing violently. Most Unstable ornaments fall. Occasionally, dishes in a cupboard and books on a bookshelf fall and furniture moves.	People notice electric-light poles swing. occasionally, windowpanes are broken and fall, un-reinforced concrete-block walls collapse, and roads suffer damage.
5-Upper		253	Many people are considerably frightened and find it difficult to move.	Most dishes in a cupboard and most books on a bookshelf fall. Occasionally, a TV set on a rack falls, heavy furniture such as a chest of drawers falls, sliding doors slip out of their groove and the deformation of a door frame makes it impossible to open the door.	In many cases , un-reinforced concrete-block walls collapse and tombstones overturn. Many automobiles stop because it becomes difficult to drive. Occasionally, poorly-installed vending machines fall.
2011.3.11 (M9.0)@Tsukuba 6-Lower	250	450	Difficult to keep standing.	A lot of heavy and unfixed furniture moves and falls. It is impossible to open the door in many cases.	In some buildings, wall tiles and windowpanes are damaged and fall.
6-Upper		800	Impossible to keep standing and to move without crawling.	Most heavy and unfixed furniture moves and falls. Occasionally, sliding doors are thrown from their groove.	In many buildings, wall tiles and windowpanes are damaged and fall. Most un-reinforced concrete-block walls collapse.
7	400	1423	Thrown by the shaking and impossible to move at will.	Most furniture moves to a large extent and some jumps up.	In most buildings, wall tiles and windowpanes are damaged and fall. In some cases, reinforced concrete-block walls collapse.

## Work for wakefield sources, 2012 12.12 20:00 - 12.13 3:00

The work had been started at 20:00 and whole ATF2 beamline was opened. The evacuation was started at 1:30AM and leakage check was done at 3:00AM. After that, it took 5 hours to reach the vacuum pressure for beam operation


- (1) T-tube for pumping port was **exchanged** Cross-tube to have a vertical symmetry.
- (2) MS1X screen monitor was **removed**.
- (3) MFB1FF, stripline BPM for slow feedback was **removed**.
- (4) A gate valve was **relocated** to the low betay position.
- (5) Test Cavity BPM for CLIC (near LW) was **removed**.
- (6) Parallel chamber system for IP-BPM test stand was **removed**.
- (7) MW0X and MW4X, wire scanners, were **removed** because we could not move to the beam-stay-clear position.
- (8) MW2X and MW3X were checked and put their wire holder into beam-stay-clear (twice wider aperture) position.
- (9) A few bellows (wider diameter) were **replaced** to the standard one which has similar aperture of the neighbor chambers.

In addition above, we looked inside of the beamline.

- (1) The mOTR had no interfere objects. It keeps the aperture of bellows mounted on both side of the OTR. Bellows is bigger than the standard beam pipe (diameter 24mm).
- (2) No structure such as bent electrode or fallen electrode was found. I just saw the circular straight aperture.

## 2012 12.13 16:10 MREF3FF scan

- no clear dependence after -1mm, 0mm, 1mm (all modulation close to 0.9)
- FF magnet power tripped, beam off
- modulation seems a bit reduced afterwards (only those points taken into account)
- set to 0.0 mm (low background: ~1500), very high background at negative values
- MREF3FF\_fringe\_121213\_164816.png:



# Multi-knobs by (skew) sextupoles

## Linear Knobs

Ax, Ex, Ay, Ey, C2

	Ax			Ex			Ay		
	x	y	tilt	x	y	tilt	x	y	tilt
SF6FF	142.0	0.0	0.0	250.0	0.0	0.0	348.0	0.0	0.0
SF5FF	-127.0	0.0	0.0	-301.0	0.0	0.0	300.0	0.0	0.0
SD4FF	9.0	0.0	-1.0	-298.0	0.0	0.0	-679.0	0.0	0.0
SF1FF	-65.0	0.0	0.0	714.0	0.0	0.0	-334.0	0.0	0.0
SD0FF	-94.0	0.0	0.0	890.0	0.0	0.0	-808.0	0.0	0.0

	Ey			<del>Coup1</del>			Coup2		
	x	y	tilt	x	y	tilt	x	y	tilt
SF6FF	0.0	-51.0	0.0	0.0	0.0	0.0	0.0	24.0	0.0
SF5FF	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SD4FF	0.0	-290.0	0.0	0.0	0.0	0.0	0.0	124.0	0.0
SF1FF	0.0	-96.0	0.0	0.0	100.0	0.0	0.0	-1.0	0.0
SD0FF	0.0	350.0	0.0	0.0	-100.0	0.0	0.0	99.0	0.0

## Non-linear knobs


Y26, Y22

	Y24	Y46	Y22	Y26
SF6FF	0.002	0.008	0.000	0.000
SF5FF	-0.008	-0.032	0.000	0.000
SD4FF	-0.097	-0.390	0.000	0.000
SF1FF	0.004	-0.022	0.000	0.000
SD0FF	0.016	-0.103	0.000	0.000
SK1FF	0.000	0.000	-0.002	-0.352
SK2FF	0.000	0.000	0.068	0.083
SK3FF	0.000	0.000	0.000	0.000
SK4FF	0.000	0.000	0.716	1.420




# Response of beam parameters at IP to each knob (1)


## Ay scan







## Ey scan




## Coup2 scan




# 6.87 degree mode, 2012 12.13




# Issue of large vertical emittance at EXT



# large vertical emittance due to BS3X skew Q?



Horizontal orbit position at BS3X center estimated by back-propagation from EXT BPM measurements (QF1X-QF4X) ... courtesy of Yves Renier



$$\Delta x = R_{12} \Delta \theta, \Delta \theta = c \Delta V, c = \frac{1}{R_{12}} \left( \frac{\Delta x}{\Delta V} \right)$$

$R_{12} = 4.7329 \mu\text{m}/\mu\text{rad}$   
 $dX/dV = -0.5085 \mu\text{m}/\text{V}$   
 $d\theta/dV = -0.1074 \mu\text{rad}/\text{V}$   
 $\theta_0 = -5 \text{ mrad} \Rightarrow V_0 = 46.5 \text{ kV}$   
 (SLAC NDR KEX:  $0.1158 \mu\text{rad}/\text{V}$ )

measurement: 2012/12/07 Owl Shift  
 BS3X Skew Quadrupole Field Dependence  
 on EXT Kicker Strength by Mark Woodley

# Summary

1. IPBSM upgrade was done and commissioned at <30 degree mode.
2. ATF was quickly recovered troubles and earthquake.
3. New QF1FF was installed.
4. Candidate sources of wakefield were removed as much as possible.
5. Measured optics is well consistent with the model (design).
6. R&Ds are progressing towards the goal 2.
7. Present IP beam has  $M=0.34$  at 30 degree mode of IPBSM.
8. Issue to be solved is the large vertical emittance at EXT.
9. We are eager to achieve the beam size of less than 70nm in this run, i.e. by end of 2012.