

# Status of ASTA, CM-2 at Fermilab

Elvin Harms

International Workshop on Future Linear Colliders/SCRF Technologies


13/14 November 2013

# Talking Points

- Introduction to ASTA – an AARD User Facility  
(Advanced Superconducting Test Accelerator)
- Major Subsystems
  - Laser
  - Photoinjector Gun
  - Capture Cavities
  - Cryomodules
  - Electron Production
- Future plans
- Summary


*the contents of this presentation reflects the work of many dedicated, highly motivated people at Fermilab and partner organizations*

## Intensity Frontier of Particle Physics




- Nonlinear, integrable optics
- Space-charge compensation

## Energy Frontier of Particle Physics




- Optical Stochastic Cooling
- Advanced phase-space manipulation
- Flat beam-driven DWFA in slabs

## Superconducting Accelerators for Science




- Beam-based system tests with high-gradient cryomodules
- Long-range wakes
- Ultra-stable operation of SCLs

## Novel Radiation Sources




- High-brightness x-ray channeling
- Inverse Compton Gamma Ray source and applications

## Stewardship and Applications





- Generation and Manipulation Ultra-Low Emittance Beams for Future Hard X-ray FELs
- Beam Dechirper for FELs

# Overview of ASTA Facility






# Overview of ASTA Facility




Proposal recently updated: [asta.fnal.gov](http://asta.fnal.gov)

# Full ASTA Layout



# ASTA Buildout and Operation Occurs in Stages: Stage I

## Stage I






# 50 MeV Injector + 1 Cryomodule

- Goal: Installation complete and beam commissioning started in 2014
  - RF gun + RF system and photocathode laser system
  - 2 SRF booster cavities (CC1 and CC2) + RF systems
  - 50 MeV Injector beam line elements and instrumentation to the low energy dump
  - Low energy beam dump
  - SRF cryomodule (CM2)
  - High energy beam line to dump
- Installation of 1st AARD experiment (high brightness X-ray channeling source)




# Stage I.0: Expected Configuration in 2014 (Completed 50 MeV Beamline)





# Photoinjector Laser

- Commercial 1054 nm Yb-fiber seed laser operating at 1.3 GHz; followed by 1 multipass, 3 single pass, and commercial amplifier, pulse-picked to 3 MHz, and frequency quadrupled to 263 nm UV
- Can now deliver 25  $\mu$ J, 300  $\mu$ sec pulse train (UV): delivered charge - **37.5 nC**



Main laser table

### NML Gun Laser Room

<b>General</b> Room Temp: 69.4°F 20.8°C Humidity: 30.8 % Dew Point: 2.6°F -16.3°C Xport Alignment Laser: <span style="color: red;">■</span> Agilent 6104A Front Panel <span style="color: yellow;">■</span> Digitized Signals <span style="color: blue;">■</span>	<b>Seed Laser</b> Voltage: 1.036 V Phase: 17.2 ps PD Gain: 1.43 dB	<b>Amplifiers</b> <table style="width: 100%; text-align: center;"> <tr> <td></td> <td>MPA</td> <td>SPA #1</td> <td></td> <td></td> <td></td> </tr> <tr> <td>Diode Current:</td> <td>0.0 A</td> <td>0.0 A</td> <td>0.0 A</td> <td>0.0 A</td> <td>0 A</td> </tr> <tr> <td>Trigger Delay:</td> <td>1.510 mS</td> <td>1.600 mS</td> <td>1.800 mS</td> <td>1.990 mS</td> <td>2.000 mS</td> </tr> <tr> <td>Pulse Width:</td> <td>0.900 mS</td> <td>1.000 mS</td> <td>0.800 mS</td> <td>0.800 mS</td> <td>2000 us</td> </tr> </table> <div style="text-align: center; background-color: red; color: white; padding: 2px; width: fit-content; margin: 0 auto;">OFF</div>		MPA	SPA #1				Diode Current:	0.0 A	0.0 A	0.0 A	0.0 A	0 A	Trigger Delay:	1.510 mS	1.600 mS	1.800 mS	1.990 mS	2.000 mS	Pulse Width:	0.900 mS	1.000 mS	0.800 mS	0.800 mS	2000 us	<b>Green Crystal:</b> 0 <b>UV Crystal:</b> 0 <b>WavePlate:</b> 0.0% <b>E-Meter:</b> 0.0E0 J/p <b>9-Way:</b> 0.0E0 J/p <b>Xport Eff:</b> 0.0%
	MPA	SPA #1																									
Diode Current:	0.0 A	0.0 A	0.0 A	0.0 A	0 A																						
Trigger Delay:	1.510 mS	1.600 mS	1.800 mS	1.990 mS	2.000 mS																						
Pulse Width:	0.900 mS	1.000 mS	0.800 mS	0.800 mS	2000 us																						



Area: 192" x 47"

<b>Timing</b> Pulse Number: 5.0 Timing Diagram <span style="color: blue;">■</span>	<b>Shutters</b> <span style="color: red;">●</span> Seed <span style="color: red;">●</span> MPA <span style="color: red;">●</span> NGA <span style="color: red;">●</span> GR <span style="color: red;">●</span> UV <span style="color: red;">●</span> Xport <span style="color: red;">■</span>	<b>Flippers</b> Streak Flipper: Out Xport Simulation: Out	<b>Chillers</b> Termotec: <span style="color: green;">●</span> PolyScience: <span style="color: green;">●</span>
--	--	---	--

Laser synoptic display

# Photoinjector Gun

- 1.5 cell copper L-band (1.3 GHz) photocathode gun (identical to FLASH design)
- Focusing Solenoids
- Water cooled
- Installation of cathode system, gun, and coupler was completed in Nov. 2012
- Conditioning started on Dec. 27, 2012.




# Photoinjector Gun

- Five RF Windows high power tested (conditioned ) to 3.8 MW, 1 millisecond pulse width in 2011
- First stage Coupler/Gun Conditioning completed to 1.2 MW, 1 ms pulse width, 5 Hz repetition rate
- Second stage of conditioning in progress
  - Up to 2.55+ MW, 1 ms, 5 Hz
  - **2.68 MW, 1 ms, 1 Hz continuous for 4 hours achieved**
- Typically running at ~1.8 MW now
- Klystron will be upgraded to a 5 MW model
  - Gun-cavity will be conditioned up to ~ 4 MW / 1ms / 5Hz.




# Photoinjector Cathodes

- Currently operating with an uncoated Molybdenum plug
- 3 Cs<sub>2</sub>Te 'coated' cathodes in hand
- Preparing to install
- Coating/Preparation done at Fermilab




Cs<sub>2</sub>TE Coated Cathode



Coating and Transport Chamber

# Capture Cavities

- Two 'Booster' 1.3 GHz cavities – single cavities each in their own cryomodule
  - Each cavity is powered by its own 300 KW RF system.





# Capture Cavities

- Capture Cavity 1 was previously the A0 Photoinjector workhorse
  - (Significant) Upgrade in progress including new cavity
  - Dressed Cavity achieved  $\sim 29$  MV/ m in January 2013 test at Fermilab's Horizontal Test Stand
  - 'Modern' cryomodule
  - Installation expected in December


# Capture Cavities

- Capture Cavity 2 - first SRF device delivered and operational at NML
  - 22 MV/m, 1 ms pulse, 5 Hz
  - LLRF & LFDC operational
  - Recommissioning in progress
    - Warm Coupler Conditioning completed
    - Cooled to 2K this week and tuned to resonance (1300 MHz)
    - Begin cold powering today

# Cryomodules – CM1

- Installed, cooled to 2 Kelvin, commissioned and operated from October 2009 – April 2012
- Peak gradients from 20 – 28 MV/m
- Detailed LLRF & LFDC studies
- Valuable experience on many aspects of SRF operation

Comparison of CM-1 Cavity Gradients




CM1 installed at ASTA


# Cryomodules – CM2

- CM2 Commissioning in progress
  - Cryomodule installed in April 2013
  - Welding and cryo circuits leak checking and pressure testing complete
  - **Warm Coupler conditioning complete** (9 May – 18 June)
    - Each cavity powered to up to  $\sim 1$  MW with short pulse (tens of  $\mu$ s)
    - 500 kW long pulse (up to 1 ms)
    - 5 Hz operation
  - **Cooldown to 2 K completed this past Monday**
  - First powering earlier today, begin on-resonance conditioning of Cavity #1 tomorrow
  - Test plan includes individual cavity characterization followed by full module powering

# Cryomodules – CM2




Cool down to 4 Kelvin



3 kW on CM-2 Cavity #1






# Cryomodules – CM2



# Electrons

- Photoelectrons first produced at ASTA on 20 June 2013
  - Molybdenum (uncoated) cathode
  - Visible on Loss Monitor, Faraday cup, and Wall Current Monitor
- Electron operation since
  - 80  $\mu$ s pulse, 1.8 MW peak power typical
  - Calibrate FC, WCM, look for BPM signals
  - RF Phase scans to optimize electron output
  - Low Level RF operated in closed loop
  - Extend pulse length/laser for more bunches
  - Exercising trim dipoles – verify beam movement, perform energy measurements

# First Electrons



## Electronic Logbook entry from first electron production:


5280, Mike Church (church), Thu, 06/20/2013 17:53:24

Gun/Commissioning

Summary of this afternoon's activities: We successfully produced our 1st photoelectron beam from the gun into a Faraday cup. 8-15 pulses at 1 Hz rep rate. Conditions were approximately as listed in entry [Entry #5273](#). Signal was observed on the resistive wall monitor, loss monitor, and YAG screen as shown in the last 3 entries. Hooray!


# Electrons – 9-way Cross

- Instrumentation platform directly downstream of the gun containing
  - Laser optics
  - Laser Injection Mirror
  - YAG profile monitor
  - Cathode viewing mirror
  - Dark current collimator
  - Faraday cup
  - Wall Current monitor
  - 2 BPM's
  - 2 Corrector magnets
  - Vacuum pumping



# Electrons – Energy Measurement



- Estimating Electron Kinetic energy by means of dipole scans
- Next step to scan solenoids






# Instrumentation

- Faraday Cup measures total current on each pulse
  - Nominal Bunch Charge measured to be **0.5 pCoulomb**
- Wall Current Monitor is a complementary, non-invasive monitor
  - Verified charge produced with Faraday Cup



# Instrumentation (2)



## 9-way Cross YAG Screen – 5 Bunches

# Accomplishments in 2013


- Laser installed & Commissioned - UV to ASTA cave
- CM2 Installed and ready for cooldown
- CM2 Warm Coupler Conditioning completed
- Gun installed and first phase of conditioning complete
  - 2<sup>nd</sup> stage in progress
- 9-way diagnostic cross installed and operational
- Electrons
  - Beam sensed on Faraday cup, Loss Monitor, Wall Current Monitor, and BPM
  - Instrumentation commissioning & calibration
- Gun energy measurements

# Planned Activities in FY14

- Complete RF Gun conditioning – 45 MV/m
- Install ‘coated’ cathode – generate a real beam
- Bring CM2 into operation
- Complete upgrade and install CC1
- Re-commission CC2
- Complete installation & begin commissioning 50 MeV Injector to low energy dump (Stage I.0)
- Begin installation of high energy beam line to dump (Stage I.2)



# ASTA Buildout and Operation Occurs in Stages: Stages II, III, IV



# Summary

- Major components of ASTA Stage I.0 are nearly in place
- Commissioning is in progress
- Collaborations and interactions with young scientists and other have already begun – other guests welcome!
- Look forward to first 50 MeV beam in early 2014

Thank you for your attention  
Questions?



# Ancillary Systems

- Gun, CC2, Cryomodule RF systems in place and operational
  - some upgrades, improvements planned including Gun Klystron replaced with 5 MW model (in hand), 10 MW multi-beam klystron for CM's (installation beginning)
- CC1 RF installation in progress
- Protection systems, Vacuum, water, Controls verified functional in early stages
- Some life testing carried out as part of commissioning systems



# Timeline

## Timeline for ASTA at Fermilab

