

Conceptual plan of ILD solenoid magnet on-site manufacture

Yasuhiro Makida, Takahiro Okamura, Toshiaki Tauchi,
Yasuhiro Sugimoto, Tomoyuki Sanuki

Final assembly of the ILD solenoid should be carried out at an assembly hall which is ground floor of the experimental cavern, because the completed ILD solenoid is too huge to be delivered from the factories.

One third block of coil winding module made in a factory is transported to the assembly hall, then the composed coil is installed into a cryostat.

We have investigate a possible transportation method. That require huge number of preparations must be done before the transportation. **Removal signals, fences and traffic signs. Reinforcement of bridges.**


So, we are now discussing an alternative plan to reduce a transportation weight of the coil parts by on-site winding.

Status of research about on-site winding will be presented.

Contents


1. **Manufacture & Transportation Plan presented in LCWS2021.**
2. New Proposal with on-site winding process.
3. Conclusion.

Outline of ILD Coil manufacturing process presented in LCWA 2021



Module Transportation presented in LCWA 2021

- Transportation of CMS coil modules ($7.4 \times 7.4 \times 3.0 \text{ m}^3$) was a hard task (at the limit of what can be transported on the road).
- ILD module has larger dimensions ($8.0 \times 8.0 \times 2.5 \text{ m}^3$)
- Possible route and cost for transportation have been investigated by **Hitachi Transport System** (<https://www.hitachi-transportssystem.com/en/>).



Land Transportation of Solenoid Coil Module


presented in LCWA 2021

Solenoid Coil Module Package


Dimension	8500 × 8500 × 3608 mm ³
Weight	90.0 ton (module 57 ton)
Package No.	3

寸法 (L) 8500 × (W) 7936 × (H) 3606mm


Carrying condition		Per axle 8 wheels	Total 64 wheels
Axle load w/o goods		12,15 kg	97.200 kg
Goods weight		11.25 kg	90,000 kg
With goods	Axle load	23,400 kg	187,200 kg
	Wheel load	2,925 kg	
Ground Pressure	Pressurized area	1.60m × 7 × 4.86m = 54.43 m ²	
	Pressure	3.4 ton /m ²	



8500



8500



Many Obstacles presented in LCWA 2021


- There are many traffic signs, signals, poles, lights and fences to be temporally removed.
 - 154 points (upper obstacle 60 points)
 - Trees are not counted.
 - Preparation and recovery cost may be comparable with transportation fee.
- Some bridges must be reinforced.
 - Reinforcement cost may be huge.
- Permissions and public approvals are necessary to occupy the road and removing road instruments.




Contents

1. Manufacture & Transportation Plan presented in LCWS2021.
2. **New Proposal with on-site winding process.**
3. Conclusion.



Outline of ILD Coil manufacturing process Onsite winding option




From P. Fabricatore, I
EEE Trans. Appl. Super., Vol. 12, p.358




**In Assembly Hall
T.Sh. setting onto C.Mass and I.V.V.**



**In Assembly Hall
V.Cylinder Welding**




Onsite manufacture of cold mass (solenoid coil and Anti-DID)



Direct inner winding line(1)

“IEEE TRANSACTIONS ON APPLIED SUPERCONDUCTIVITY, VOL. 12, NO. 1, MARCH 2002
The Winding Line for the CMS Reinforced Conductor” by Fabricatoreより



De-spooling and Straightening



De-spooling the conductor and making it as straight as possible.

Cleaning unit
Solvent bath coupled with ultrasonic device.
To prepare conductor surface for adhesion through epoxy resin.

Bending unit : two-steps 3 points bending

Sand- Blasting unit : the conductor surface is sandblasted to maximize the adhesion surface.

Winding table :
A fixed table supports a rotating table.
Both tables can move in vertical position
(through the large rods attached to the central structure),



Insulation tape wrapping unit : Wrapping two insulation tapes



Taping unit



Sand – Blasting Unit

Milling machine, placed aside the cleaning unit : Removing Al-alloy to prepare electric joint at the beginning and at the end






ANSALDO SUPERCONDUTTORI

Direct inner winding line(2)

“IEEE TRANSACTIONS ON APPLIED SUPERCONDUCTIVITY, VOL. 12, NO. 1, MARCH 2002
The Winding Line for the CMS Reinforced Conductor” by Fabricatoreより

Bending Unit

Working principle of the two-step bending unit. Rollers A, A' drive the conductor. Rollers B, C' and D bend the conductor at a radius R_1 (Roller B' and C are not active). Rollers E, F and G bend the conductor at the final radius $R_2 < R_1$.



Conductor Driven Unit :

This unit is a structure made of rods and motorized rollers, driving the insulated turn, from the top of the mandrel to the turn location inside the winding.

Direct inner winding line(3)


Final positioning

“Coil Winding Issues” by Fabbricatoreより


Once each turn is led to approach the winding (internally against the mandrel or existing layer), it is necessary to push it longitudinally and radially. This is done by a special unit, working as three hands, which clamp the conductor and push it. The system is always kept (by a hydraulic circuit) in operation, so to avoid releases of turns.




Arrow 1




Arrow 2



Arrow 3




Final Positioning




Process of cold mass manufacture (1)

Solenoid Coil Winding Process at the Assembly Hall




Process of cold mass manufacture (2)

Anti-DID Coil Winding Process





Cryostat Assembly (Learning by CMS experience)



These photos are copied from CMS web sites.

Workplace in AH for SC Magnet






Land Transportation of Support Cylinder


Lighter and Smaller

Solenoid Coil Package -> Support Cylinder Package


Dimension	8.5 × 8.5 × 3.6 m ³	8.5 × 8.5 × 2.8 m³
Weight	90.0 (module 57) ton	12? (module 6.5) ton
Package No.	3	4



8.5 × 8.5 × 2.8 m³
12? (6.5) ton



Signals, traffic signs and lights are placed to **5 m** in height.



Contents

1. Manufacture & Transportation Plan presented in LCWS2021.
2. New Proposal with on-site winding process.
3. **Conclusion.**

Conclusion

- On-site winding process has been considered to reduce risks at the module transportation from the factory to the assembly hall.
- That can reduce the weight and height of transported module from 57 ton to 6.5 ton and from 5.2 m to 4.0 m. That can reduce number of temporal removal of road instruments and bridge reinforcements.
- Max 90×40 m² space for magnet manufacture, including the main assembling area, is required from 3rd to 8th year (6 years).
- Hopefully, it may be possible to arrange the space.

3. サイトインフラ

○巻線環境の温度管理

- ex1 ITER製造 $20^{\circ}\text{C} \pm 5^{\circ}\text{C}$ ($15^{\circ}\text{C} \sim 25^{\circ}\text{C}$)
- ex2 巻線室 $24^{\circ}\text{C} \pm 3^{\circ}\text{C}$ ($21^{\circ}\text{C} \sim 27^{\circ}\text{C}$)
- ex3 湿度の制限:なし

→ILC 温度制限: $21^{\circ}\text{C} \pm 6^{\circ}\text{C}$ ($15^{\circ}\text{C} \sim 27^{\circ}\text{C}$)
湿度制限: 無し

○乾燥炉

- ex1熱風循環型乾燥炉 最大 210°C 2.3m×3m×3.5m (24.2m³)
25kW×6系統=150kW
- ex2熱風循環型乾燥炉 最大 180°C 3.9m×3.9m×3.5m(53.2m³)
40kW×6系統=240kW

3. サイトインフラ

○巻線後樹脂熱硬化用乾燥炉

仕様

雰囲気: 大気

形式 : 熱風循環型乾燥炉

最大温度: 180°C

サイズ: 10m × 10m × 10m (1000m³)

コイル重量 最大200ton

アルミ熱容量 905 J/kg・K

ΔT 160K

として24Hrで温度上昇するためには、放熱を無視して

$$905\text{J/kg}\cdot\text{K}\cdot 2\text{E}5\text{kg}\cdot 160\text{deg}/(24\text{Hr}\cdot 3600\text{sec})=335\text{kW}$$

放熱係数 1W/m²とすると

乾燥炉表面積 600m²

最大温度差 200K

として 最大放熱ロス

$$600\cdot 200=120,000=120\text{kW}$$

結果 (335kW+120kW) * 1.2安全率 =550 kW

* それらしい値だが確証が無いので、炉メーカーに問合せ中

4. スペース

○メモ


- ・ケーブル仮巻きは行わず、巻線機上でプリベンドを行う
- ・スウィベリングシステムは中央寄りに設置
ヨーク下半作成後、真空容器を置き、その後マグネットを挿入して行く。
- ・熱処理炉は建屋端としない
クレーンが寄り付かないため
- ・多目的 溶接、発塵エリアを設ける
端面機械加工が必要な場合は同エリアを使用

○その他



- ・クレーン
ヨーク用 250ton
コイル用 80ton
- ・電力
建設中 2MW(仮) * 上がっても良い

4. スペース

○高さ方向



5. クライオスタット組立(2)



回転片持ち梁が必要(ソレノイドで整備)



(別案) 中央の梁で挿入