### Beam tests of the new scintillator HCAL modules at DESY

- > results from DESY e<sup>+</sup> testbeam
  - MIP calibration
  - time measurement
- > plans for CERN  $\pi$  testbeam

Katja Krüger (DESY)

LCWS2012 International Workshop on Future Linear Colliders Arlington, Texas, 22-26 October 2012









### **Scintillator HCAL**






### **HCAL Base Units (HBUs)**

- > 144 scintillator tiles
- 4 chips reading out 36 channels each
- > two trigger modes:
  - external trigger
  - autotrigger: OR of 36 channels above threshold, possibility of trigger validation
- measurement of size (ADC) and time (TDC) of a signal
- > 4 new HBUs: equipped with tiles, electronics for all channels adjusted in lab




### **DESY testbeam**



- > positron beam of 1-6 GeV, a few kHz rate at 2-3 GeV, nearly continuous
- > goals
  - cross check gain equalization: positrons (or electrons) at these energies passing through a tile deposit nearly exactly the same energy as a Minimum lonizing Particle (MIP)
  - test trigger verification
  - test external time reference



### Calibration in DESY testbeam



- verify channel gain equalization at an energy scale relevant for physics by measuring a MIP signal in all tiles
- setting trigger threshold for MIP measurement is a compromise between noise rate and minimizing influence on MIP signal






# **DESY Testbeam: Trigger Validation**


- chips have buffer depth of 16 events
  - sufficient for ILC operation
  - limiting for testbeam operation
- trigger modes of Spiroc2b chip:
  - external trigger
  - autotrigger: OR of 36 channels
- trigger validation for autotrigger:
  - if no external reference signal is given (within a certain time window), the current buffer will be overwritten by the next event
  - use signal from trigger scintillator as external reference signal
  - large suppression of non-beam related background, essential for testbeam operation

# without validation ADC Fintries 15984 Mean 479 RMS 122.1 Integral 1.475e+04 200 400 600 800 1000 ADC






# Distribution of MIP most probable values



- > all MIP spectra are fitted with Landau ⊗ Gauss
- most probable value (before pedestal subtraction) consistent between channels

# **Efficiency**


- determine trigger efficiency for a MIP as function of threshold from shape of MIP signals
- → for thresholds below 0.5 MIP efficiencies of ~95% or better are reached
- aim to run with threshold below 0.5 MIP





# **Threshold setting**

- > 1 global trigger threshold per chip, necessary conditions:
  - uniform gain (gain equalization with single pixel spectra and preamplifier capacitances → talk by O. Hartbrich)
  - uniform light yield (adjusted SiPM voltages)
- verify that position of 0.5 MIP is similar for all channels





fulfilled for all four HBUs



### **Time measurement**

- measure time in auto-trigger mode relative to bunch clock
- time measurement is implemented with TDC ramps (low power consumption)
- dual TDC ramp in switched by a multiplexer to reduce dead time due to ramp reset








### **External time reference**


- > for testbeam running, the internal clock is not correlated to the beam
- > no direct input of external time reference foreseen in electronics
- no information about absolute time of a hit
- use capability of time measurement of the channels, replace 1 tile signal by signal of trigger scintillator
- time difference between channel with MIP signal and channel with reference T0 shows sharp peak:
  - width ~10 ticks, 1 tick ~ 1.5 ns (no corrections applied)
  - offset due to electronics






# **Electromagnetic shower**

> tested operation with signals in all 4 chips with electromagnetic shower






# **Preparation for CERN testbeam**




- will operate 1 layer with 4 HBUs in 50-180 GeV π beam
- assembly done at DESY
- first operation tests successful








# **Goals for Testbeam at CERN**

- System test of prototype with 4 HBUs
- Study time structure of hadron showers
  - differences in the time development of showers between tGeant4 physics lists
  - HP contains better modeling of low energy neutrons
  - differences especially in the shower tail










# **Summary & Outlook**

- tests & calibrations of single HBUs done in DESY positron beam:
  - MIP measurements
  - time reference
  - electromagnetic shower
- first tests with 4 HBUs
- plans for CERN hadron beam:
  - demonstrate operation of engineering prototype layer
  - measure time structure of hadron showers
  - simulation studies started
- next steps
  - slab with 6 HBUs
  - small elm. stack
  - large 1m³ prototype






# Backup



# **Noise Rate**

- determine noise rate with threshold at 0.5 MIP:
  - dependence of rate on trigger threshold (in DAC) already measured in Lab



need MIP measurements to determine threshold we will use

