







Joint Session of the LCWS: MDI and ILC: BDS Workgroups held at DESY on 1 June 2007.

"IR Systems Integration Issues Relevant to Push-Pull," IR Magnet Point of View.

In this talk we will view the IR systems integration issues from the perspective of how our design decisions influence the IR magnet requirements.

Personal Goal: In the discussion time after this talk I hope we can come up with a tentative list of contact people from the accelerator and technical groups as well as all four detector collaborations along with a list of homework assignments that can be completed in time for review at the September IR workshop at SLAC. – B. Parker

Workshop on ILC Interaction Region Engineering Design SLAC, September 17-21, 2007

Machine

MOOD

Detector

IR Magnets

Homework Item #1: Implications of BROOKHAVEN Desired Changeover Time Scale.

Assertions - Superconducting magnet (detector & final focus) warm-up/cool-down time scales are long enough that these magnets have to be moved while cold? But they may be de-energized?

If true, this drives a need for long "umbilical" connections to each of the experiments that are able to accommodate ≈20 m motion while cold.

Cryogenic requirements? Safety Codes? Previous experience?

Interface requirements? What about R&D and testing?



Heat Load and Power Requirements.



At this point in time the service cryostat that is being designed for the QDO engineering prototype (see above information) is being used as a place holder for the cryogenic interface definition. Note the diameter of the cryogenic connection to the QDO cryostat <u>depends critically on assumptions of static and dynamic heat</u> load as well as the distance to the service cryostat.

What are reasonable static (warm-cold & supports) heat loads (4.5K & 1.9K) and how much should we budget for the dynamic (normal running & upset conditions) heat load?

Homework Item #3: Path & Length Between QD0 and Service Cryostat.

Interface Box



Experiment B

Service Cryostat

Experiment A

Warm bus, vacuum and helium supply/return lines?

Plan View

Interface Box QD0 Cryostat |

If/how each experiment opens up while at beam position?

Separate the recooler and current lead functionality?

Where is the interface box and connection to umbilical?

What about the pacman?



while keeping heat exchanger's elevation close to that of QD0.

Homework Item #3': Path & Length BrookHaven Between QD0 and Service Cryostat.



Support heat exchanger and cryo lines from top?

Elevation View

Beam View



Information Gained Via QD0 Cryostat BROOKHAVEN Engineering Prototype Systems Test.

BDS R&D plan stresses the importance of integrated systems testing of an engineering prototype (QDO with connection to service cryostat) to among other things establish the degree of coupling of external vibration sources to the QDO cold mass. For a 100 nm goal will standard practice be good enough or will we need to develop mitigation schemes? Is "100 nm" a reasonable goal?



Homework Item #5: All Detector Concepts! BROOKHAVEN We Need QD0 Support / Access Scenarios. Magnet Division



Homework Item #6: Space and Position of BROOKHAVEN QD0 Cryostat for Each Detector Concept. Magnet Division



Homework Item #7: All Detector Concepts! BROOKHAVEN Backgrounds & Magnet Energy Deposition. Magnet Division

Experiments are especially concerned with computing (minimizing) detector backgrounds. For the magnet system we need to understand the expected level of energy deposition in magnets.

Optimized (anti)-DID field profile?

Optimized anti-solenoid field profile?

Get ED results from tracking?

What about beam tuning or abnormal operating conditions? What are "safe" (but not too conservative) ED budgets? (see Homework Item #2) Pairs and Radiative Bhabhas in 14 mrad Crossing Geometry (interaction turned off).



"Detector Background Update for L*=3.51 m, L*(ext)=5.5m," Takashi Maruyama, BDS Weekly Meeting at SLAC.

Right now I (BP) can generate sample field profiles for the DID and antisolenoid but to go further we need agreed upon requirements for each detector concept. Maintaining multiple L*s and layouts does increase the work to be done.

Homework Item #8: Responsibility BROOK for Pulling the Information Together. Superconducting Magnet Division Can we identify <u>here</u> folks who will be responsible to do the homework outlined in time for next meeting? Machine How should we balance conflicting requirements? Schedule of interim discussions before September? What resources do we have to draw upon? Almost all of these issues have TR been discussed in many different Detector venues by a variety of people. Up Magnets until now there has been intense time pressure to complete the BCD, RDR, reduce costs etc. but it seems to me that now that we are starting the Thank you for your attention. - B. Parker EDR, it is time to really flesh out IR systems integration issues in detail.