


SRF Technology : status and plan



H. Hayano (KEK)

SC RF activities Highlights

from TTC at DESY (Jan. '08) and recent new results

Asia;

KEK STF 0.5; TESLA-type cavity cooled down,

LL cavity is under cool-down experiment.

STF EP is under commissioning.

Kyoto camera provides more data of 3 DESY cavities.

EU;

XFEL is in detailed planning, under industrialization, call for tender process.

cavity package & module 3* is under pressure test. (later by Lutz)

INFN & DESY: blade tuner test results. (later by Lutz)

Saclay: Ar baking on Ichiro single cell results.

XFEL: horizontal MBK was delivered and tested.

NA;

CM 1 (module 9) is ready to test.

Ichiro#5 is under test in Jlab.

24 cavities will be delivered in 2008.

Re-plan of cryomodule development.

Status of Asia

STF development plan update

Phase 1 (2005 -2007),

for quick startup of ILC SCRF, **infra-structure** development subdivided to

Phase 0.5 TESLA-shape: 1 cavity in short cryostat
(cool-down was in Oct-Nov. 2007)

Phase 0.5 LL-shape: 1 cavity in short cryostat
(cool-down will be in Feb-Mar. 2008)

Phase 1.0 : 4 cavities in each short cryostat
(cool-down schedule is under discussion)

Phase 2 (2008 - 2010),

develop **ILC Main Linac RF unit**
start design Apr. 2008; fabrication in 2009 and 2010
completion end of 2010 (cool-down 2011)


New plan of “S1 global”
is under discussion



GDE S0 task (2006 - 2009)

develop **ILC performance cavity (>35MV/m at vertical test)**

Phase 3 plan
will be requested



TESLA-shape cavity cool-down test






Program:

Oct. 03-12: cool down test,
suspended by SRF workshop
Oct. 22 -26: re-cool down
Oct.29 - Nov. 02 : 4K Test (1 week)
Nov.05 - Nov. 09 : 2K Test(1 week)
Nov.12 - Nov 22 : 2K with HLRF on
(2 weeks)

Study Item:

Cool down control
Heat load measurements
Cavity fundamentals($Q, E_{acc}, f_0..$)
Lorentz detuning
Piezo compensation
Mechanical vibration
GRP distortion by WPM
etc.


Cryomodule Thermal Performance




Steady state Heat Load to 2K system: 5.6W

Achieved Eacc,max

Cavity Tests




Compensation by Piezo (1) ; higher Tension




$K = -0.5 \text{ Hz}/(\text{MV}/\text{m})^2$
Flat-top Lorentz detuning

Eacc = 18. MV/m
Piezo / OFF





Eacc = 18. MV/m
Piezo / ON
300 Hz, 500 V, - 700 μsec



4 TESLA cavities are ready for STF 1 experiment




TESLA-style cavities were assembled in clean room, hung on the cold mass, and inserted into the vessel, on Feb. 29, 2008.



LL ICHIRO cavity in STF0.5 experiment

**Ichiro #1 cool down
test in cryomodule:
Feb. 13 to Mar. 28,
2008**


Now under test!



**Heat load measurement,
Ball-screw tuner test,
coupler performance test,
cavity performance test (19.5MV/m in VT),
etc.**

STF Cavity Surface Process Facility

Under commissioning



STF – EP system commissioning using old MHI cavity
 Picture shows acid draining by holding cavity up.
 3 times EP cycle (40+60+60 μ m removal) were done.



Cavity on the turntable,
 moveable into rinse position.

STF Vertical Stand

Under final Installation, almost ready to commission



Meas. room

space for pre-tuning machine




Four cavity stands



Two Pits, so far only one cryostat installed.

Kyoto/KEK High Resolution Camera


For visual inspection of cavity inner surface.



Camera system ($7\mu\text{m}/\text{pix}$)
in 50mm diameter pipe.

sliding mechanism of camera

perpendicular illumination
by LED & half mirror





tilted sheet illumination
by Electro-Luminescence

results of Z84 (DESY)

**Z84: 27 – 22 MV/m, Q-disease,
530 μ m total removal at the last test.**


→ many tiny spots found in equator




- 28 spots like cat's-eye were found at the equators of the cells. (only the spots with diameters larger than 100 μ m are counted.)**

Results of AES01 (FNAL)



3rd Test Results





84 μ m height
60 μ m height



~21mm



AES01 has hard quench at 15MV/m, its location was identified by Cernox at FNAL.



Kyoto-camera found 3 spots in their exact location

Results of AC71,AC74,AC80(DES Y)

Summary of Vertical Test

cavity	# of meas.	# of T-map data	Exp # with T-map
AC71	17	0	
AC74	8	2	#2 & #3
AC80	6	1	#4

Summary of T-map


cavity	Exp. #	date	# of data	comment	results
AC74	2	2002/02/15	6	T-map at 18.0MV/m	Hot spot at #2cell 35°
AC74	3	2002/02/22	4	T-map at 17.6MV/m	Hot spot at #2cell 60°
AC80	4	2004/09/03	3	T-map at 27.7MV/m self-pulsing	Hot spot at #5cell 90°

AC74

Field Emission, and Break Down


T-map indicate; hot spot at cell#4 near Iris, **→ Found small balls**
 at cell #2 between Iris & Equator **→ Nothing Found**

Found many small pits on many Iris




● Max Eacc [MV/m]


● removed materials [µm]





AC74 Test #2 ①



AC74 Test #3 ①





AC74: hot spot1 95°



Cell #4

1mm


AC74: hot spot2 141°





Cell #4

1mm




AC74: iris between cell#1 and #2



$\theta=296^\circ$



$\theta=298^\circ$



$\theta=302^\circ$



1mm

A white scale bar indicating 1mm.


AC80

Quench at cell #5, cell #1 or 9

T-map indicate;
hot spot at cell#5 equator

Found small pits, however angle is not match to T-map
Need check again.


Vertical Test Results



● Max Eacc [MV/m]

● - remove

AC80




Max Eacc [MV/m]



removed materials [µm]

Test Date

AC80 Test #4 ①





AC80: hot spot1



Cell #5.

1mm



AC80: hot spot2



Cell #5.


1mm

**AC80: cat's eye
@cell#5_equator**



This does not match to T-map hot spot. Need to check again.

1mm



Status of NA

NA Outline



- **Status of infrastructure installations (FNAL, ANL)**
- **SRF R&D for ILC - S0/S1 (Jlab, Cornell)**
 - + **New vendor qualification**
- **Large Grain 9-cell first results (Jlab)**
- **Newcomer TRIUMF**

* From presentation in TTC at DESY


Argonne EP Commissioned with One-Cell



Cornell HPR System
Designed and Under
Construction (FNAL)




FNAL CM Assembly



Horizontal Test
Cryomodule, C22 tested



String Assembly with DESY Cavities






Cryomodule Assembly with DESY Assistance



First CM Ready for Test Facility

FNAL: Vertical Test Set Up Complete AES 9-cell Cavities under Test




**AES01 Tested,
AES03 under test**

9-cell EP and Vertical Tests

- **Jlab**
 - **Achieved 30 cycles of EP/VT per year.**
 - Post-EP ultrasonic cleaning with “soap” always used.
 - A6 and A7 processed 4 cycles for ILC S0/S1.
 - A8 started on S0 tight loop
 - KEK ICHIRO 5 cavity testing started
 - New vendor cavities evaluation AES 1 – 4
- **Cornell**
 - **One cycle per month**
 - Post-EP ultrasonic cleaning with “soap” always used.
 - A8 and A9 qualified for quench ≥ 25 MV/m
 - A8 sent to Jlab for tight S0 tight loop
 - A9 started micro-EP (5 microns) to study effect on quench
 - 9-cell re-entrant cavity work started
 - New vendor AES (new beam welder) 1-cell cavity rapid qualification

9-cell Test Results

Mostly Jlab and Some Cornell




Best 9-cell cavity gradient results

- 4 cavities (A6, A7, A8, AES2) best gradients of 31-42 MV/m. Quench limit sensitive to re-processing.
- 2 cavities (AES4, ICHIRO5) reached gradient of 28-36 MV/m. Field emission limit.
- 2 cavities (AES1, AES3) reached gradient of 19-21 MV/m. Quench limit insensitive to re-processing
- Pass-band & Thermometry to locate defect.
- AES 3 defect is in cell 6
 - Near, but outside equator weld
- AES 1 sent to FNAL to qualify VTS, Quench located in cell #3
 - AES 1 sent to KEK for optical microscopy

Total 43 vertical tests

Quench limited 58%




LL ICHIRO test at Jlab




New Ichiro #5(KEK),
#6(PAL)

New Ichiro #5(KEK) was
sent to Jlab for S0 work.




Pre-tuning (96% flatness) at Jlab,
total $30\mu\text{m}$ removal at Jlab
at 4-th vertical measurement




T-map development

FNAL



Model of half cage assembly



1-cell prototype was made and the fixture was cold tested (shock) successfully



Jlab One Cell Thermometry Assembly



LANL 9-cell T-map development

New Vendor Development Continued AES New Beam Welder

Rapid Qualification : 5 Single Cells, 110 μm BCP, HPR 2 hrs

- **Cornell/FNAL collaboration**
- **BCP and Tests carried out at Cornell**
- **4 of 5 cavities reached 25 MV/m without quench**
 - **limited by high field Q-slope**
- **1 of 5 cavities reached 17 MV/m limited by field emission**
- **AES new beam welder is qualified**

FNAL : delivery of 9 cell cavities


- **8 ACCEL : in next few weeks**
- **6 AES : Summer 2008**
- **10 ACCEL : Fall 2008**

9-cell Cavity performance(Jlab)


Large Grain

- Two 9-cell cavities (LG#1,LG#2) were fabricated at Jlab from large grain CBMM niobium (ingot"D"); several holes during EBW in both cavities
- Standard processing:pre-tuning, 100 micron bcp,hydrogen degassing at 600C for 10 hrs,final tuning, final bcp
- LG #1 received only ~ 40 micron, LG#2 ~ 57 micron bcp in final bcp
- LG#1: quench at $E_{acc} = 23$ MV/m,
- LG#2: quench at $E_{acc} = 20$ MV/m

Large Grain LG#1



Large Grain ILC 9-cell Cavity #2



October 15-19, 2007

SRF 2007

40




SRF@TRIUMF : Infrastructure



TRIUMF

PAVAC


Plasma Fabricator




Forming and Machining



EB Welding




Pre-weld Etching - TRIUMF



SCRF R&D Plan at Fermilab

from P5 talk by S. Holmes




Status of EU

* XFEL project


* From presentation in TTC at DESY

XFEL Overall Schedule as the Basis



- 1) Call for tender & ordering : middle of 2008 – middle of 2010
- 2) 101 modules production : middle of 2010 – end of 2012
- 3) Commissioning start in 2013

XFEL Overall Schedule - First Details



- 1) Module 3* pressure test: middle of 2008
- 2) Module 10, 11, 12 cold mass : 2008 – 2009
- 3) 30 EP cavities (prep & VT) : 2008
- 4) 3 pre-series modules : 2010 first half
- 5) First 5 modules : 2010 latter half
- 6) Module Test Facility commissioning : 2010

XFEL Overall Schedule - Comments

Module #3* will be 'destructively' tested at the CMTB; therefore it needs to be repaired; additional assembly training possible (old module type!)

Module #8 is going to be tested in Q1/2008; and needed for installation in FLASH in Q1/2009; it will be extensively tested at CMTB, and then be used for a first transportation test of assembled modules; we 'bought' a Return Ticket to Saclay.

We are going to receive the **cold mass for modules #10 to #11 (or #12?) beginning of Q4/2008**; these XFEL type modules offer assembly checks / training (remark: the final 101 module call for tender will not wait for the module assembly!!!)

Three pre-series XFEL modules need to be assembled approx. Q4/2009 – Q1/2010; a first check on CMTB should follow, then they are to be used for AMTF commissioning (Q2/2010); all sub-components have to be available.

We expect to see **the first few (≤ 5) assembled modules** at AMTF until end of 2010; after this we have two years time for the remaining $101 - 5 = 96$ modules; module tunnel installation starts in Q4/2012



WP – 3 Accelerator Modules

60% CEA
19% INFN
21% DESY

Invest

FTE

43% CEA
29% INFN
29% DESY



- Fabrication of cold masses (incl. outer vessel)
- module assembly w/o frequency tuner & power coupler; start with assembled string and finish with module installation
- weld connections
- alignment inside modules
- transportation of assembled accelerator modules
- material specifications, safety issues
- define processes for integration / assembly
- magnetic shielding / demagnetization
- sensors inside the accelerator modules
- pre-alignment of cavities and coupler position



WP – 4 Supercond. Cavities

50% INFN
50% DESY

Invest

FTE

34% INFN
66% DESY



- Procurement of all niobium
- Scanning of NB sheets
- Complete mechanical fabrication of all cavities
- Surface treatment
- Consultant at start up of infrastructure and at full running production
- Data base setup and database running
- EDMS
- Helium vessel incl. Titanium parts (taken over from WP-9)


WP – 5 Power Coupler

73% LAL
27% DESY

Invest




FTE

52% LAL
48% DESY



- Coupler production incl. project and industries follow-up
- Coupler conditioning
- Infrastructure required for coupler assembly and conditioning, i.e. clean room and modulator / klystron
- Technical interlock
- Tunnel installation / cabling of technical interlock
- Motor electronics

WP – 6 HOM Coupler / Pick-up



100%
Swierk

Invest

FTE

100%
Swierk

- Fabrication of HOM beam pipe absorbers
- HOM Pick-ups and cables


WP – 7 Frequency Tuners

100%
DESY

Invest

FTE

100%
DESY



- procurement of motors, gear box, piezo actuators
- fabrication of mechanical tuner parts
- fabrication of drive unit (motor and piezo) electronics
- cabling
- survey of production


WP – 8 Cold Vacuum

100%
DESY

Invest

FTE

100%
DESY



- procur of all vac components within the cold linac, i.e.
 - bellows between cavities
 - cold manual valves at both ends of cavity strings
 - valves in the module connection
 - isolation vac valves
 - ion and TSP pumps incl. power supplies/controllers
 - all vac components part of the cryogenic connection boxes and of the cold-warm transitions
- vacuum components in the injector as well as bunch compressor sections (to be transferred to WP – 19)




WP – 9 Cavity String Assembly / Clean Room Quality Assurance

90% CEA
10% DESY

Invest

FTE

51% CEA
49% DESY



- Helium vessel fabrication
- Titanium Tube and 2-phase line
- String assembly
- Knowledge transfer / consultant / training
- Database set-up and running / QC of infrastructure
- EDMS


WP – 11 Cold Magnets

56% CIEMAT
44% DESY

Invest

FTE

10% CIEMAT
90% DESY



- fabrication of 2K quadrupole package
- test of quadrupole package

XFEL Components (the “scrif ones...”)

XFEL needs

**808 cavities for
101 accelerator modules, i.e.
808 frequency tuners,
808 RF main input couplers,
1616 HOM pick-ups,
101 HOM absorbers
etc.**

Due to the long lead time, all components need to be specified in 2008,

- the call for tender process to be started before end of 2008,**
- orders be placed not later than beginning of 2009.**

WP 4: Cavities

Items not finished in the XFEL preparation phase

- **Fabrication of 30 cav.** for industrial EP

ACCEL delivered 15 cav.;

ZANON delivered 5 cav., rest till end of the year

- Qualifying of **new Nb vendors** on 9 cell cavities

1 cav. of PLANSEE niobium is in fabrication at ACCEL,

3 cav. of NINGXIA niobium are in fabrication at ACCEL


- **Industrial study of EP**

set up of prototype EP and carry out the first step EP
(rough EP) of 30 cav.

Fa. ACCEL: EP treatment of first cavities till end of 2007

Fa. Henkel is also going to start EP treatment now

WP 4: Cavities - Small design changes to reduce cost and simplify fabrication




Removal of coupler port stiffener

Reducing of flange machining short side


Removal of outside recess (equator area)

Less holes and thinner the stiffener ring


Review tolerances



Short side
(machined step
under discussion)



Long side



No rib

WP 4: DESY will supply companies with following material / equipment and carry out the training


- Niobium for 50 cavities
- Apparatus for scanning of niobium
- Equipments for RF measurement of half cells, dumb bells and end groups
- Equipment for warm tuning (tuning machine)




DESY Eddy current apparatus



DESY SQUID apparatus



Equipment for warm tuning (tuning machine)



RF measurement device
Equipments for RF measurement of half cells, dumb bells and end groups

WP 4: Pending Decisions

- **Vertical RF test of cavities with He tank or not**
- **Treatment procedure is not finally defined.**

Fine Grain:

Final EP (with or without ethanol) or BCP-Flash?

Large Grain:

BCP only

or rough EP with final EP (with or without ethanol)

or rough EP with BCP-Flash?



- **Material scanning: Eddy Current or SQUID**
- **Niobium for 50 cavities**
(as ingot material, discs or fine grain sheets??)

Argon Baking @ 145 °C vs. time

Electropolishing at KEK




Argon baking and RF tests at Saclay




ICHIRO IS#8

Horizontal Multi-beam Klystron test at DESY



10MW 1.5ms
67% efficiency

Scope picture of the klystron test.
The lines show the klystron voltage
(116 kV) in yellow, the current
(128 A) in blue and RF output
(5 MW each) in magenta and green.




**Toshiba
E3736H**



http://www.linearcollider.org/newsline/readmore_20080117_atw.html

Plans of cryomodules

cryomodule plans



end