



CLIC TDR plans

R. Corsini for the CLIC TDR Task Force and the
CLIC/CTF3 Collaboration

Talk outline

- Introduction – the CLIC roadmap
- Outline of the Technical Design phase
 - RF structures development
 - Technical development, prototyping
 - Test facilities
 - Other activities
- Resources





CLIC TDR plans

R. Corsini for the CLIC TDR Task Force and the
CLIC/CTF3 Collaboration

Talk outline

- Introduction – the CLIC roadmap
- Outline of the Technical Design phase
 - RF structures development
 - Technical development, prototyping
 - Test facilities
 - Other activities
- Resources





Work Plan until 2010:

Slide from CLIC '09 Workshop presentation

- Demonstrate feasibility of CLIC technology (R&D on critical feasibility issues)
- Design of a linear Collider based on CLIC technology
<http://clic-study.web.cern.ch/CLIC-Study/Design.htm>
- Estimation of its cost (capital investment & operation)
- CLIC Physics study and detector development
http://clic-meeting.web.cern.ch/clic-meeting/CLIC_Phy_Study_Website/default.html

Conceptual Design Report to be published in 2010 including:



- Physics, Accelerator and Detectors
- Results of feasibility study
- Preliminary performance and cost estimation

R&D Issues classified in three categories:

- critical for feasibility



fully addressed by specific R&D to be completed before 2010
results in CDR

- critical for performance
- critical for cost



being addressed now by specific R&D to be completed before 2016
first assessments in CDR
results in Technical Design Report (TDR) with consolidated performance & cost





Slide from CLIC '09 Workshop presentation

Tentative long-term CLIC scenario

Shortest, Success Oriented, Technically Limited Schedule

CERN Council decision on
Technical Design Phase



	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024
R&D on Feasibility Issues																		
Conceptual Design																		
R&D on Performance and Cost issues																		
Technical design																		
Engineering Optimisation&Industrialisation																		
Construction (in stages)																		
Construction Detector																		



Conceptual
Design Report
(CDR)



Technical
Design Report
(TDR)




Project
approval ?



First
Beam?





Present status

- CDR basically on track. First “good” draft end of the year, final publication in 2011.
- CTF3 fire \Rightarrow final results on Two-Beam feasibility issues mid 2011
- Final results on other feasibility issues by 2012

New boundary conditions: new CERN MPT 2010

- Previous CERN Medium Term Plan (MTP) included a (potential) large increase in CLIC resources, starting from 2011.
- Due to financial constraints, the new MTP approved in August 2010 by the CERN Council had substantially “reduced such increase”.
- Still, CLIC material budget @ CERN should almost double over the next 3 years (while manpower should remain basically constant).
- We are presently re-evaluating the plans for the next phase – we want to profit from this Workshop to ask you to help us to:
 - Revise, improve and better refine the technical plan.
 - Define the needed resources (and eventually secure them).





Work Plan for the next years:

Before 2011

CDR (2011), CLIC feasibility established

2011-2016 – Project Preparation phase

This is the current focus for planning in the collaboration, with main activities covering:

- review of the CLIC baseline design, taking into account CDR results and including:
 - cost & power consumption optimization
 - energy staging
 - technical risks and performance risks
- technical developments and test of critical component prototypes, using several facilities across the collaboration
- exploitation and upgrade of CTF3 to CTF3+, construction and commissioning of CLIC drive beam injector
- detector and physics studies
- site studies
- preparation of a Project Implementation Plan (PIP) for CLIC

This phase will culminate with a document, or several, covering the points above, with a detailed plan for the next phase

After 2016 – Project Implementation phase, including an initial period to lay the grounds for full approval

Considering the preparation steps foreseen and the resources situation it is clear that several key tasks will need further effort before the project can move into construction:

- finalization of the CLIC technical design, taking into account:
 - results of technical studies done in the previous phase
 - final energy staging scenario based on the LHC Physics results, which should be fully available by the time
- possible construction of CLIC Zero as first CLIC phase
- industrialization and pre-series production of large series components with validation facilities
- further detector and physics studies, with increased emphasis on technical coordination issues and integration
- revision of the Project Implementation Plan (PIP) of CLIC, following the energy staging strategy and detailed resource discussion with all partners – providing the basis for a staged or full approval, and subsequent construction start up

During this initial period we will need to produce the necessary documents to support a proposal for CLIC construction start-up






CLIC TDR plans

R. Corsini for the CLIC TDR Task Force and the
CLIC/CTF3 Collaboration

Talk outline

- Introduction – the CLIC roadmap
- Outline of the Technical Design phase
 - RF structures development
 - Technical development, prototyping
 - Test facilities
 - Other activities
- Resources






RF structures & High-power tests

- Basic feasibility \Rightarrow ~ **OK**
(for both accelerating structures & PETS)

Still to be done (2011-2016):

- Implement full features
(damping material, wake-field monitors, vacuum, cooling, PETS on-off ...)
- Increase statistics, long-term running
- Optimization of fabrication techniques for cost/performance
- Start industrialization/large-series production
- Explore potential for further improvements

Resume of CLIC acc. structure performance





PETS @ASTA - SLAC, klystron powered




$BDR < 1.2 \times 10^{-7} / \text{pulse} / \text{PETS}$

Typical RF pulse shape in ASTA during the last 125h of operation




PETS @ CTF3 - TBTS, beam powered






RF structures

Accelerating structure disk



Design and fabrication of 12 GHz accelerating structures & PETS for high-power and beam testing and associated R&D

Core activity – critical for cost and performance



Stacked disks




Structure ready for test


- • Improve infrastructure for manufacturing, brazing , assembly procedures and quality control
 - Precision machining center and metrology at CERN
 - Diffusion bonding furnace at CERN
- • Build and test about 100 “baseline “ accelerating structures
 - A few generations of reference structures
 - Optimization of damping material, cooling, vacuum, tolerances, cost, preparation of industrialization
 - Parallel testing for more statistics on performance, long-term testing
- • Build and test about 20 “alternative“ accelerating structures
 - Explore alternatives for improved cost/performance
 - RF design, materials, fabrication techniques
- • Build and test about 10 PETS prototypes
 - Alternative designs for cost/performance
- • Basic studies on breakdown physics

N.B.: more structures and PETS will be built and installed in CLIC modules, most of which will be tested with beam in CTF3


PETS ready for test



Temperature treatment for high-gradient



PETS bars






RF Test areas


Building, commissioning and operation of high-power Klystron-based RF test stands

Core activity – critical for cost and performance

- Continued support for high-power testing at 11.4 GHz at KEK and SLAC
- Build four new 12 GHz klystron-based high-power test stations from 2011 to 2016, at CERN and elsewhere
 - Eventually about two slots per station
 - Compatible with planned number of structures/PETS
- Contribution to high-power testing, including CTF3+
 - Measurements, operation, data analysis



NLCTA - SLAC





PETS under test at ASTA - SLAC



12 GHz klystron and pulse compressor for CERN high-power test stand

Nextef - KEK



RF conditioning & data acquisition for CTF3 - TBTS






Technical development, prototyping

- Conceptual design of technical systems \Rightarrow **CDR** (including basic feasibility)




April 2010 – nm stabilization results





Still to be done (2011-2016):

- Technical design, prototypes and beginning of industrialization for all large-series items (critical for cost, performance and schedule)
 - Nominal two beam modules with all features this includes accelerating structures & PETS
 - Drive beam accelerator units (modulator, klystron, RF network, accelerating structure)
- Technical design and working prototypes for all items critical for performance and cost
- Ensure technical feasibility of all components




CLIC two-beam modules

CLIC cavity BPM



CLIC FF QDO prototype



QDO inside its support




Technical development, prototyping

Technical R&D – design, build and test prototypes of CLIC critical components

Technical design and prototypes for all components critical for cost or performance and beginning of industrialization for large-series items

- Development of 15 MW 1 GHZ MBK and modulators
- R&D and prototypes of CLIC two-beam modules , including alignment and stabilization systems
- Prototypes of FF QDO quadrupole and stabilization system
- R&D and prototyping of critical beam instrumentation
- Prototypes and tests of critical equipment for DRs:
 - SC wiggler
 - Vacuum components
 - Fast extraction kickers
- Dynamic vacuum assessment
- Prototype installation of fs timing system
- Magnet prototypes, power supplies
- Design and studies of machine protection system
- ...




DR superconducting wiggler prototype

Draft program for technical developments

domain	deliverable
development of 15 MW 1 GHZ MBK	1 working prototype/firm
development of modulators for above	3 prototypes
prototypes of stabilized MB quads	at least one T1, T2, T3, T4
alignment system	400m working demonstrator in TZ32
alternative alignment system	prototypes
prototype for FF quad (including stabilization)	Short and long prototype
Validation of quad stability through beam experiments	validation
Prototypes of critical beam instruments	experimental validation; BPMs, ODR
Prototype installation of fs timing system	24 km transport of 10 fs timing reference
prototypes of fast kickers	10-4 jitter kicker in lab; beam tests
various magnet prototypes with power supplies	preparation of industrial production
Critical equipment for DRs: vacuum, SC wiggler	prototypes, verification in light sources
dump, masks	studies, designs, material tests

nm active stabilization systems







Test facilities

- Feasibility demonstration in CTF3 \Rightarrow **Mid 2011**
(present experimental program of CTF3 completed by 2012)


Outlook for (2011-2016):

- Consolidation/upgrade of CTF3 to fully exploit its potential
 - Verify stability/reliability performance in view of CLIC requirements, improve operational experience
 - Contribute to high-power RF testing, demonstrate operation of a drive-beam driven power source
 - Test with beam CLIC two-beam modules
- New drive beam injector facility, at nominal CLIC parameters
 - Final proof of drive beam performances, long-pulse, high-power operation
 - provides a focus for development and pre-industrialization of drive beam components – all hardware reusable
- Pursue and intensify experimental program in other facilities
 - ATF II
 - CesR-TA, SLS, ATF I, ANKA...
 - Asset
 - ...

CTF3+



ATF - KEK






Test facilities – CTF3+


CTF3 consolidation and upgrade

- Consolidation and upgrade (higher energy, stability, reliability, rep. rate)
- Drive beam phase feed-forward experiments
- Upgrade and operate TBL as 12 GHz power production facility
- Operation with beam of a long string of CLIC two-beam modules

Present




Upgraded




CTF3 energy upgrade



TBL - CLEX



CTF3 - Phase
feed-forward



Two-Beam modules in CTF3




CTF3+




CLEX – TBTS (until 2011)

CLEX - one two-beam module
(2012)



TBTS PETS

CLEX - Three two-beam modules
(2013)



2013+



N modules ($N < 20$)







Test facilities – CLIC Drive Beam Injector


Build and commission 30 MeV Drive Beam injector with nominal CLIC parameters


- Build and commission 30 MeV Drive Beam injector with nominal CLIC parameters
- Build and commission a few Drive Beam accelerator nominal modules
- Contribution to Technical Design of full CLIC Zero facility



CTF3
Injector








Outlook after 2016

CLIC Zero



All other parameters nominal - all components nominal and re-usable for CLIC





CLIC TDR plans

R. Corsini for the CLIC TDR Task Force and the
CLIC/CTF3 Collaboration

Talk outline

- Introduction – the CLIC roadmap
- Outline of the Technical Design phase
 - RF structures development
 - Technical development, prototyping
 - Test facilities
 - Other activities
- Resources





Activity	Description	Deliverables (2016)	Total material budget
CTF3 +	CTF3 consolidation and upgrade	<ul style="list-style-type: none"> Consolidation and upgrade (higher energy, stability, reliability) Drive beam phase feed-forward experiments Upgrade and operate TBL as 12 GHz power production facility Operation with beam of a long string of CLIC two-beam modules 	43 MCHF
CLIC Zero	Injector for the CLIC drive beam generation complex	<ul style="list-style-type: none"> Build and commission 30 MeV Drive Beam injector with nominal CLIC parameters Build and commission a few Drive Beam accelerator nominal modules Participation to Technical Design of full CLIC Zero facility 	42 MCHF
RF Structures	design and fabrication of 12 GHz accelerating structures & PETS and associated R&D	<ul style="list-style-type: none"> Build and test about 120 accelerating structures Build and test about 10 PETS prototype Establish quality control, brazing and assembly procedures for structure fabrication at CERN Precision machining center at CERN 	29 MCHF
RF test infrastructure	Building, commissioning and operation of high-power RF test stands	<ul style="list-style-type: none"> Four 12 GHz klystron-based RF high-power test stations, for about 8 slots, running before 2016 Continue high-power testing at 11.4 GHz (KEK and SLAC) Contribution to high-power testing in CTF3+ (TBL) 	13 MCHF
Prototypes of critical components	Technical R&D – design, build and test prototypes of CLIC critical components	<ul style="list-style-type: none"> R&D and prototypes of two-beam modules alignment and stabilization systems Prototype of final focus QD) quadrupole and stabilization system Several nominal CLIC two-beam modules, mechanically tested, possibly beam tested R&D and prototyping of critical beam instrumentation Design and studies of machine protection system DR superconducting wiggler prototypes, test with beam DR extraction kickers prototypes Dynamic vacuum assessment Contribution to the CLIC Zero TDR ... 	29 MCHF
Cost studies, Civil engineering, Proj, Implementation	Update and improve CLIC cost model & civil engineering studies	<ul style="list-style-type: none"> Technical Design (TD) and Project Implementation Plan (PIP) of CLIC Zero Improved cost model, feedback to CLIC baseline review 	4 MCHF
Beam physics studies	Beam physics and overall design	<ul style="list-style-type: none"> Review of the CLIC baseline design Contribution to the TDR of CLIC Zero 	3 MCHF






Material

- Ramp-up to about 30 MCHF in 2013
- Total integrated 2011-2016 \Rightarrow 165 MCHF

Assuming planned CERN contribution
(MTP 2010 – about 105 MCHF)

\Rightarrow need from collaborators 60 MCHF

Material contributions from outside CERN
should rise from 20-25% (present level) up to
more than 1/3





Manpower


- Ramp-up from about 110 to 170 FTE

Planned CERN contribution (MTP 2010) slightly decreasing!

However, in the MTP after 2011/2012 most of non-staff manpower is not accounted for

Taking this into account, the CERN manpower is substantially flat (however, a fraction of this will have to be provided by a material-to-personnel transfer)

⇒ need from collaborators up to ~ 50 additional FTEs





Conclusions

- CLIC feasibility is going to be demonstrated and documented by 2011
- Since some time we are preparing the plans for the next phase (Project Preparation phase, 2011-2016)
 - “Reduction of the increase” in CERN resources has forced us to review such plans
 - Still, the planned increase in material budget over the next few years should enable us to pursue the most critical R&D
 - A complete program is under study, needs larger resources (from outside CERN?)
- We need the help of present – and new – collaborators, in order to:
 - Revise, improve and better refine the technical plan
 - Provide additional resources

Please send your expressions of interest to us at cltc-tdr-contributions@cern.ch
(possibly indicating a technical contact person and a resource manager)

