



AHCAL electronics integration status

Mark Terwort ECFA meeting 21.10.2010

- Status of electronics/DESY activities
 - Next generation electronics status
 - Testbeam and charge injection setups and results
 - LED calibration systems
- Summary and outlook

The technological AHCAL prototype



Development of scalable LC detector based on successful experience with physics prototype



AHCAL layer – cross section





- Redesign and production of subcomponents ongoing or finished (DIF, CALIB2, POWER2, HBU2, CIB, Flexleads (SIB not needed yet))
- Compliant with steel and tungsten options

The SPIROC2





Current AHCAL electronics setup



- At DESY 2 setups (HBUs) available
- 1 for charge injection and LED calibration tests
- 1 for testbeam operation with 2GeV electron beam
- Multiple tests performed and issues discussed with Omega
 - SPIROC2a/2b just arrived at LAL
 - SPIROC3 design ongoing
- Redesigns of boards currently ongoing



DESY testbeam setup



- Setup optimization, channel-wise calibration with MIPs
- MIP level: S/N ~ 45
- Single pixel level: S/N ~ 5.5
- SiPM gain: $G_{LED} = G_{MIP} \sim 30$ ADC ch.





→ Very clear MIP signal with visible single pixels!

Autotrigger performance





Autotrigger threshold behaviour





- Example:
 - Charge injection: ~182 DACtics/pC
 - Testbeam: ~191 DACtics/pC
 (8 pix, 350 ADC/MIP, gain 5*10⁵)





Autotrigger MIP efficiency



How noisy is the system?

- Is the MIP efficiency high enough?
- Autotrigger threshold calculated channel-wise for 10⁻⁴ cut
- Keep in mind width of threshold!





Wuppertal LED calibration system





System task:

- SiPM gain calibration via single pixel spectra
- SiPM saturation curves

Wuppertal solution:

- Light directly coupled into the tile by 1 integrated LED per channel
- Multiple tests performed: uniformity, shifts...



Development of automatic fit and gain extraction routines (here for testbeam MIP signals)

Prague LED calibration system



Second option for LED system (Prague solution):

- Light distributed by notched fibers
- First tests (including lab and testbeam measurements) promising



Next important steps

2500

2000

1500

1000

0

pulsing

[TDC output [ADC tics]





- New technological AHCAL prototype under development
- 2 setups running in Hamburg
 - Successful testbeam operation and MIP calibration
 - Tests of SPIROC2 with charge injection
- Redesigns ongoing and partially finished
- LED calibration system development ongoing with 2 options

To do

- Test of TDC and power pulsing
- CALICE DAQ integration
- Start of SPIROC2a/b tests soon
- Integration to full slab (2.2m calorimeter layer)

Status redesigns









in preparation

