

Study of RPC-based HCAL DHCAL results & status

H.Weerts Argonne National Lab For DHCAL group

IWLC2010, Geneva, CH 18 - 22 October 2010











Novel approach to the measurement of jets at future lepton colliders





Particle Flow Algorithms require Imaging Calorimeters

Measure each particle in a jet individually tracker for charged particle Use electromagnetic calorimeter for γ 's entire calorimeter for neutral hadrons

> Factor ~2 improvement in resolution over previous experiments



One approach is RPC gas based Digital Hadron Calorimeter

This is approach we have taken, one of many approaches



Argonne, Boston University, FNAL, IHEP (Beijing), University of Iowa, McGill University, Northwestern University, University of Texas at Arlington

Sandwich calorimeter with

Absorber - 20 mm thick steel plates Active elements - Resistive Plate Chambers (RPCs)

Readout

Longitudinally – every layer individually Laterally – 1 × 1 cm² pads

Resolution

1 bit/pad

ILC detector concepts

RPC-DHCAL = Baseline of SiD RPC-DHCAL = Alternative option of ILD



Based on simple design Robust and reliable (yes!) Large signals Can be made to be thin Allows for segmented readout

4



Past Achievements

Detailed studies of RPCs with analog readout

G.Drake et al., Nucl. Inst. Meth A578, 88 (2007)

Development of a digital readout system

Tests with a VME based DAQ system Design of a front-end ASIC (the DCAL chip) Tests of various front-end boards





Vertical Slice Test

20 x 20 cm² RPCs (based on two different designs) 1 x 1 cm² readout pads Up to 10 chambers \rightarrow 2560 readout channels **Complete readout chain as for larger system**

Detailed tests with cosmic rays at Argonne and in Fermilab test beam (μ , 120 GeV p, 1 - 16 GeV π^+ , e^+)

Very successful \rightarrow extrapolation to large system

6

DHCAL **Papers from Vertical Slice Test**



IWLC2010, October 2010, CERN, H.Weerts

A few nice events from the testbeam....

A perfect μ



2 perfect µ's



With the small slice test calorimeter

e⁺ shower





Based on results confident to build a 1m³ hadron calorimeter



 π^+ showers





8



DHCAL Physics Prototype: 1m³

Started preparations/construction ~ one year ago~ Fall 2009.

150/114 RPCs built & tested (90cmx30cm)

DCAL III Front-end ASIC designed, produced and tested ~9,000 good parts in hand Pad-, front-end boards designed, fabricated and assembled Pad- and front-end boards glued (1536 glue dots) 276/228 boards glued and tested



35/20 Data collectors designed, produced and tested (Boston University) 6/3 Timing and trigger modules designed (FNAL), produced and tested

HV system complete (University of Iowa)
LV system: 7/5 power supplies in hand
7/5 distribution boxes designed and assembled
Gas system: Gas mixer designed, built, tested and used (Iowa)
Gas distribution rack designed, built, tested and used (Iowa)



DHCAL Collaboration	Heads
Engineers/Technicians	22
Students/Postdocs	8
Physicists	9
Total	39

Glass Spraying

Need to coat anode glass with resistive paint with R $_{\rm a}$ = 1 - 5 M Ω R $_{\rm a}$ of cathode glass not as important

Built automatic spraying booth

- 1 button operation
- fumes (non toxic) vented outside of building
- 1 glass/2 minutes, but long set-up times
- Standard operation: 8 glass/day
- Total production needed ~250 pieces





Production completed Never gained complete control over R₀ RMS actually rather good

0.5

RMS/mean



10

Index

RPC Assembly

Each chamber 32 × 96 cm² Important to maintain gas gap size constant Need 114 chambers to equip cubic meter

Built precision fixtures for assembly

- 1 frame cutting fixture
- 3 RPC assembly fixtures
- Assembly of 1 RPC/technician/day
- Produced a total of 159 chambers







Chamber Thickness

Lei,s chambe



Production completed with 159/114 chambers Thickness variation on rim acceptable (not all chambers measured) All chambers passed leak test at 0.3" of H₂O

IWLC2010, October 2010, CERN, H.Weerts

HV Connection

3 steps: 1) attach connector
2) cover chamber in Mylar sheets
3) protect connector with RTV

Nominal voltage 6.3 kV

Built test stand

- 6 chambers tested simultaneously
- Tests performed at 7.0 kV
- Monitoring of (dark) currents







~127/114 chamber successfully tested at 7.0 kV Currents ~ 0.25 $\mu A/chamber$

Pad- and FE-board Gluing

Each board contains 1536 channels which need to be connected with conductive glue The glue dries in 3 hours

Built a gluing fixture

- Dispenses glue on gluing dots
- Takes only 25 minutes/board
- Glued 10 boards/day
- Glue is cured in oven at 70 C^0







Front-end Boards

Each board contains 1536 channels and 24 ASICs The data concentrator is implemented into the same board 2 boards are needed per RPC

Built 3 computer controlled test stations

- Extensive tests (S-curves, noise rates...)
- 3 6 hours/board
- Accepted boards with less than 4/1536 dead channels





Testing complete 276/228 boards tested successfully

Data Collector Modules

1 Data Collector Module per 12 front-end boards Need 19 for cubic meter

Built test station at Boston



Production complete 30/20 boards delivered to Argonne





Timing and Triggering Module



Provide control to up to 24 Data Collectors Need 1 Master and 2 Slaves for cubic meter

Designed and debugged at FNAL

12 boards produced 6/3 assembled so far DHCAL

Cassette Assembly

3 RPCs assembled into a cassette Front-plate is copper (for cooling of ASICs) and back plane is steel Cassette is compressed horizontally with a set of 4 (Badminton) strings Strings are tensioned to ~ 20 lbs

Assembly

- Not very difficult
- Best timing so far:
 45 minutes/cassette





40/38 cassettes assembled

DHCAL

Nine layers of production RPC chambers (30x 90 cm), with 1x1cm pad readout. <u>Self</u> triggering and requiring hits in > <u>two planes</u> for trigger. Total ~ 25000 channels.

Trigger-less noise data with requirement of hits in > 2 layers (no other tricks!!!!)





Completed cassettes at Argonne





Peripherals



Low Voltage Power Supply

Need power to 228 front-end boards (+5V) Acquired 7 Wiener power supplies Built 7 power distribution boxes All fully operational

High Voltage Power supply

Need 6.3 kV to 38 layers (3 RPCs powered by 1 line) Borrowed 3 LeCroy 4032 power supplies Borrowed 2 sets of controllers Developed computer control program All fully tested

Gas Supply

Need 19 lines (2 layers or 6 RPCs per line) Built mixing rack for 3 gases Built distribution rack All fully operational All complete







Transportation to FNAL and installation



Installation complete





Cabling up

12 hours of hard work (350,000 readout channels)



40/38 layers built and checked out successfully

40 layers transported to FTBF

CALICE HCAL structure and stage ready

Thanks to Karsten, Beni and Sven

38 layers installed into CALICE HCAL structure

Cabling done

224 data cables 76 low voltage cables 38 high voltage cables 19 x 2 gas lines

Trigger Scintillators installed and cabled up

Thanks to Beni, Sven, Karsten

TCMT cabled up and ready

Thanks to Eric Johnson

Safety review passed

Gas Electrical Mechanical



Summary



Schedule:

- 4 October start moving hardware to Fermilab
- 8 October RPCs installed, hook up gas, HV, get permits, start cabling
- 15 October all cabled up, ready for beam
- 16 October first noise runs and muons from beam
- 20 October (today) waiting for hadrons First indications so far →

32 GeV secondary beam with 3 m beam blocker = muons NO event selection



Occasional noise hits

Chambers operated at higher temperature than usually

- \rightarrow Higher efficiency
- \rightarrow Much higher noise rate \rightarrow higher pad multiplicity

Noise run

Event selection requesting at least 5 different layers with hits Due to high data rates, only selection of layers read out





DHCAL Run 610056



<u>Very</u> preliminary from testbeam: muons

28 Layer number), October 2010, CERN, H.Weerts

<u>Very</u> preliminary from testbeam: muons

DHCAL Run 610056



Δ

Testbeam plans

Broadband muons for calibration

Calorimeter not rotated Move calorimeter around to expose entire volume (probably not needed) Trigger with 1 x 1 m² Scintillator paddles Adjust timing of Scintillator coincidence, TCMT DAQ, and Cerenkov signals Most likely for one week, depending on statistics and width of beam (rough calculation: (100/pad)*(9216 pads)/(350 muons/spill) = 2,600 spills = 44 hours)

Energy scans (separation of positrons and pions offline using Cerenkov)

Calorimeter not rotated Into center of calorimeter Trigger with coincidence of 20 x 20 cm² Scintillator counter and 1 x 1 m² Scintillator paddle 1,2,4,8,12,16,20,24,32,40,48,60 GeV (rough calculation: 100,000 events/energy /(300 particles/spill)*(12 energies)= 4,000 spills = 67 hours)

Test beam ends November 2

Next test beam January 2011 (DHCAL + RPC-TCMT)

3rd test beam April 2011 (ECAL + DHCAL + RPC-TCMT)

4th test beam ? 2011 (DHCAL + RPC-TCMT)



Summary

CALICE now has at least two HCAL modules in testbeam one at FNAL & one at CERN (Fe and W).

Thanks to FNAL for making it easy

Thorough testing, commissioning and calibration of first digital RPC based HCAL with Fe in next few months. Exciting next few months.

Next with Tungsten?

Next also other gas based HCAL 1m³'s: RPC based semi-digital and micro-megas based.

Especially gratifying for me..... after 5 years of pushing finally in testbeam. Over one year long construction period





Backup slides





Cuts

- At most 1 cluster/tracking |
 χ²/DOF < 1.0
 N_{track} > 5
- x_{int} within 0.0 ÷ 95.0
- y_{int} within 0.0 ÷ 31. 0







DHCAL

Installation into CALICE absorber Structure



Testbeam started last Friday

With help from DESY

