

# **ENGINEERING DESIGN AND FABRICATION OF X-BAND ACCELERATING STRUCTURE TD24 WITH WFM**



A. Solodko, A. Samoshkin, D. Gudkov, JINR, Dubna, Russia, G. Riddone, A. Andersson, Geneva, Switzerland, F. Peauger, P. Girardot, CEA Saclay, France, R. Zennaro, PSI, Villigen, Switzerland

#### Abstract

To achieve high luminosity in CLIC, the accelerating structures must be aligned to an accuracy of 5 µm [1] with respect to the beam trajectory. Position detectors called Wakefield Monitors (WFM) are integrated to the structure for a beam based alignment. For the adaption of WFM the accelerating structure TD24 12GHz, based on CERN design, is used. The WFM is integrated to the structure, without modifying its accelerating and damping properties. This paper reports engineering design of a prototype accelerating structure with WFM. Precise machining of disks with a tolerance of ±2.5 µm and a surface roughness of 25 nm is demonstrated. The fabrication status of three complete accelerating structures with WFM is finally presented for a feasibility demonstration with beam in CTF3 at CERN.







### **Assembly procedure**

#### **Pre-assembly of couplers**

- Diffusion bonding of high power couplers under H<sub>2</sub>
- Re-machining of flat surface for the WR90 waveguide connection
- Drilling special holes in the external butt

#### Assembly

- Diffusion bonding of high precision disk stack and prepared couplers under H<sub>2</sub>

#### **Tuning system**

- Push-pull principle

- 4 tuning studs inside each cell

It is possible to increase or decrease the internal volume of each cell by deforming the thin wall.







The positioning of WG with WFM relative to AS is realized by two pins. A good electrical contact, needed between the WG and AS, is provided by tightening of four bolts, used for fixing the WG on the AS body. One SiC absorber, needed for damping of high-order modes, is fixed in each WG by means of bracket. The coaxial connectors with screwed RFpick-ups are fixed directly to the adapter.

## The two accelerating structure with WFM will be finally installed for a feasibility demonstration in CTF3 (CLIC Test Facility 3) at

The mechanical design of the structure has taken into account the dedicated surfaces for providing integration to the testing

#### CONCLUSION

A new wakefield monitor design has been presented. It is integrated to the CLIC main linac accelerating structure without any major change. The wakefield monitor allows to study two kinds of hybrid HEM modes at the same time. The mechanical design has taken into account the required high gradient fabrication technologies of normal conductive cavities as well as the integration constraints in the CTF3 environment. The disks are currently in fabrication at the French company Mecachrome. The manufacturing should be finished by the end of 2010 so that low level RF tests and installation in the vacuum tank will occur in spring 2011. In parallel, the electronic acquisition system under development at CERN will be installed and first tests with beam and high power RF from PETS will be performed in 2011/2012.

ACKNOWLEDGMENT	REFERENCES
The development described in this paper is the result of the international collaboration. The authors wish to thank all of the members of the collaboration for their valuable contribution.	<ul> <li>[1] The CLIC Study Team, "CLIC 2008 Parameters", CLIC-Note-764.</li> <li>[2] M. Dehler, I. Wilson, W. Wuensch, "A Tapered Damped Accelerating Structure for CLIC", LINAC'98, Chicago, August 1998</li> <li>[3] A. Grudiev, W. Wuensch "Design of an X-band accelerating structure for the CLIC main linac", THP062, LINAC08, Victoria, BC, Canada.</li> <li>[4] http://www.meggittsafety.com</li> <li>[5] http://www.elhyte.fr</li> <li>[6] F. Peauger, W. Farabolini, P. Girardot, A. Andersson, G. Riddone, A. Samoshkin, A. Solodko, R. Zennaro, R. Ruber, "Wakefield monitor development for CLIC accelerating structure", LINAC'10</li> </ul>