



Two-beam acceleration: two-beam prototype validation program

G. Riddone in collaboration with N. Gazis, D. Gudkov, A. Solodko
(input from CLIC Module WG members)

OUTLINE

- Two beam acceleration feasibility issue
- Prototypes modules to be tested without RF and beam: design and procurement status, objectives, schedule
- Prototypes modules to be tested with RF and beam: design and procurement status, objectives, schedule




CLIC FEASIBILITY ISSUES

System	Item	Feasibility Issue	Unit	Nominal
Two Beam Acceleration	Drive beam generation	Fully loaded accel effic	%	97
		Freq&Current multipl	-	2*3*4
		12 GHz beam current	A	4.5*24=100
		12 GHz pulse length	nsec	240
		Intensity stability	1.E-03	0.75
		Drive beam linac RF phase stability	Deg (1GHZ)	0.05
	Beam Driven RF power generation	PETS RF Power	MW	130
		PETS Pulse length	ns	170
		PETS Breakdown rate	/m	< 1·10-7
		PETS ON/OFF	-	@ 50Hz
		Drive beam to RF efficiency	%	90%
		RF pulse shape control	%	< 0.1%
	Accelerating Structures (CAS)	Structure Acc field	MV/m	100
		Structure Pulse length	ns	240
		Structure Breakdown rate	/m MV/m.ns	< 3·10-7
Two Beam Acceleration	Power producton and probe beam acceleration in Two beam module		MV/m - ns	100 - 240
	Drive to main beam timing stability		psec	0.05
	Main to main beam timing stability		psec	0.07
Ultra low beam emittance & sizes	Ultra low Emittances	Emitttance generation H/V	nm	500/5
		Emittance preservation: Blow-up	nm	160/15
	Alignment	Main Linac components	microns	15
		Final-Doublet	microns	2 to 8
	Vertical stabilisation	Quad Main Linac	nm>1 Hz	1.5
		Final Doublet (assuming feedbacks)	nm>4 Hz	0.2
Operation and Machine Protection System (MPS)		72MW@2.4GeV main beam power of 13MW@1.5TeV		

Demonstration of novel scheme of two beam acceleration in compact modules integrating all technical systems for RF production, beam measurement and acceleration including alignment, stabilisation and vacuum at their nominal parameters.

A. Samoshkin



Prototype modules → as close as possible to CLIC modules




STEPS TOWARDS TWO-BEAM ACCELERATION MODULES

germana.riddone@cern.ch

2009-2011


Two-beam test stand
(PETS and ac.
structures)



Demonstration of the two-beam acceleration with one PETS and one accelerating structure at nominal parameters in CLEX

2010-2013


Prototype modules in
LAB



Demonstration of the two-beam module design

This implies the assembly and integration of all components and technical systems, such as RF, magnet, vacuum, alignment and stabilization, in the very compact 2-m long two-beam module

Prototype modules in
CLEX



Demonstration of the two-beam acceleration with two-beam modules in CLEX

Address other feasibility issues in an integrated approach


Industrialization and mass production study



germana.riddone@cern.ch


PROTOTYPE TWO-BEAM MODULES IN THE LAB

4 modules representative of all CLIC module types
 First two modules under procurements
 Reception at factory of girders started on 20 October



SiC girder before final
 Grinding at Boostec

Layout of first two modules
 with all technical systems



D. Gudkov



PROTOTYPE MODULES IN THE LAB: OBJECTIVES


germana.riddone@cern.ch


- Integration of all technical systems (dummy RF structures and quadrupoles can be used – real dead weight and interfaces to other systems)
- Validation of different types of girders and movers
- Pre-alignment of girders/quadrupoles in the module environment, including fiducialisation
- Full metrology of the module components
- Validation of interconnections under different simulated thermal loads
- Stabilization of main beam quad in the module environment
- Vibration study of all systems and identification of vibration sources
- Measurement of resonant frequencies (both in lab and in the tunnel/underground area)
- Simulation of several thermal cycles: measurements of thermal transients (e.g. how long it takes to achieve a new equilibrium state), fiducialisation verification
- Transport of the module and verification of alignment

CLIC'09




PROTOTYPE MODULES IN THE LAB: TEST PROGRAM






3 companies with three different strategies:


- **Boostec:** supply of 2 SiC girders with V-shaped supports [Nov 2010]
- **Microcontrole:** supply of 2 SiC girders with V-shapes supports, and positioning system [Dec 2010]
- **Epucet:** supply of 2 Mineral cast girders [Nov 2010]



Boostec (SiC)




SiC Girder Half




SiC V-support



SiC Girder Brazed



SiC Girder before V-support brazing





Conceptual Design Feb – Jul 2010

Epucet (Mineral Cast Material)





Girder Mould fabrication



Metal V-supports, U-clamps
DB-quad support plate




N. Gaziz




➤ Modal Analyses for all CLIC Two-Beam Module Girder prototype configurations:
Eigenfrequencies (f) \geq 35 Hz

➤ Static Analyses of loaded CLIC Two-Beam Module Girder prototype configurations: 80 μm \geq Deformations (ϵ) \geq 10 μm

Pre-stressed girders, according to the simulated RF component loads, with precision machining after the integration of the V-shaped supports.



Modal Analysis




Pre-stressed solution



MAIN BEAM AS ASSEMBLY SEQUENCE (1/4)

D. Gudkov

1. Brazing of the manifolds (preliminary brazed);
2. Brazing of plugs and cooling fittings adapters;




3. Brazing of 2 stacks 1005 mm long each:

Includes:


4 AS with manifolds;

Interconnection MB-MB;


4. Installation of the damping material
and EB welding of covers




5. Welding (EBW) of two stacks together:




6. Installation of splitters;
7. Installation of alignment targets (spheres);
8. Installation of cooling adapters;
9. Installation of cooling tubes.





DB BPM – Vacuum chamber ASSEMBLY (June version)



DB BPM – Vacuum chamber ASSEMBLY (July version)




1. Vacuum chamber and BPM are joined as one part to increase the precision;
2. Damping material added;
3. Alignment frame is finalized;
4. Production drawings: CLIATLBI0009





PRTOTOTYPE MODULES – LAB: SCHEDULE

germana.riddone@cern.ch



Actuators/sensors under fabrication

MB T1 and T4 at CERN

Girders under fabrication

Under tendering: vacuum system , beam instrumentation and RF system

For details, see
EDMS number: [1076281](#)



PROTOTYPE TWO-BEAM MODULES IN CLEX



TEST MODULES - CLEX: OBJECTIVES

germana.riddone@cern.ch

- Two-beam acceleration in compact modules integrating all technical systems for RF production, beam measurement and acceleration including alignment, stabilisation and vacuum at their nominal parameters.
- Accelerating structure alignment on girder using probe beam
- Wakefield monitor (WFM) performance in low and high power conditions, and after a breakdown
- Investigation of the breakdown effect on the beam
- Alignment and stabilization systems in a dynamic accelerator environment
- RF network phase stability especially independent alignment of linacs
- Vacuum system performance, both static and dynamics with rf
- Cooling system, especially dynamics due to beam loss and power flow changes
- Validation of assembly, transport, activation, maintenance etc.


CLIC'09

PROTOTYPE MODULES TO BE TESTED IN CLEX


- 3 modules to be tested with beam and RF
- module layout compatible with CLEX requirements:

- double length PETS feeding two accelerating structures
- accelerating structures with all technical systems and damping features

- First module to be ready by end of 2011




Integration of test modules in CLEX



A. Solodko


Phase 3 foresees the installation and testing of 1 module type 0: AS equipped with WFM (5 μm accuracy / few WFM in the 1st powered AS)



Existing PETS

3.1 / Nominal power and pulse length for 1 PETS and 2 AS
Recirculation
12 A and 240 ns


3.2 / No modifications on the module type 0 HW
No Recirculation
Current increase from 12 A to 19.2 A
Pulse length reduced from 240 ns to 140 ns



PHASE 4.1

Existing PETS

No modifications on the module type 0
Addition of new modules - type 1 and 4
 Increase of current from 19.2 A to 22 A




PHASE 4.2

Existing PETS

Modification on the module type 1
(2 CLIC PETS)
 Needed klystrons and PC

All AS are with WFM



Phase 3:

- Existing PETS (currently under test) will be reused
- It will be moved to allow for Type 0 module installation


Phase 4:

- Instrumentation downstream the type 0 module will be removed
- Installation of type 1 and 4 without displacing type 0



PRTOTOTYPE MODULES – CLEX: SCHEDULE

germana.riddone@cern.ch




- Two-beam module is part of the CLIC feasibility program
- At the end of 2009 the prototype module project has been approved: 7 modules
- Prototype Module project very challenging:
 - Non standard procurement, several iterations needed with firms
 - First girders in Nov 2010 for type 0 test modules in the lab, although reception at factory already started
 - Eucard WP 9.2 NC linac – NC accelerating cavities is part of test modules in CLEX → several collaborators highly contributing
- Next months will be very busy with the assembly of the first two modules: metrology and thermal cycles tests are expected to be finished before CDR



germana.riddone@cern.ch

EXTRA SLIDES

CLIC module type 0



Parameters	CTF3	CLIC
Energy	0.150 GeV	2.4 GeV
Pulse length	1.2 μ s	140 μ s
Multiplication factor	$2 \times 4 = 8$	$2 \times 3 \times 4 = 24$
Linac current	3.75 A	4.2 A
DB final current	30 A	100 A
RF frequency	3 GHz	1 GHz
Repetition rate	up to 5 Hz	50 Hz
Energy per beam pulse	0.7 kJ	1400 kJ
Average DB power	3.4 kW	70 MW

CLEX module type 0

Double length PETS

